

THE LAW RELATING TO  
CORRUPT PRACTICES  
AT ELECTIONS.

BY  
MILES WALKER MATTINSON  
AND  
STUART CUNNINGHAM MACASKIE.


7/6

WATERLOW & SONS LIMITED, LONDON WALL, LONDON.




THE LIBRARY  
OF  
THE UNIVERSITY  
OF CALIFORNIA  
LOS ANGELES







THE LAW RELATING TO  
CORRUPT PRACTICES AT ELECTIONS.



THE LAW RELATING TO  
CORRUPT PRACTICES AT ELECTIONS,

AND THE  
PRACTICE ON ELECTION PETITIONS,

WITH AN

APPENDIX OF STATUTES, RULES AND FORMS.

BY

MILES WALKER MATTINSON,

OF GRAY'S INN, BARRISTER-AT-LAW; JOINT AUTHOR OF "PRECEDENTS OF PLEADING.

AND

STUART CUNNINGHAM MACASKIE,


OF GRAY'S INN, BARRISTER-AT-LAW; AUTHOR OF "LAW OF EXECUTORS AND  
ADMINISTRATORS," AND A "TREATISE ON BILLS OF SALE."

LONDON:

PUBLISHED BY WATERLOW AND SONS LIMITED,  
LONDON WALL, E.C.

1883.

L O N D O N :  
PRINTED BY WATERLOW AND SONS LIMITED,  
LONDON WALL, E.C.



## PREFACE.

**T**HE sweeping changes in the Law for the Prevention of Corrupt Practices at Elections effected by the Act of 1883 have rendered obsolete existing works on the subject, at the same time that the increased stringency of punishment enacted has heightened the importance of a clear comprehension of the whole subject by all persons concerned in the conduct of elections. In these circumstances the Authors present to the Profession and the Public this work, in which they have sought to engraft what has been newly enacted by the Legislature upon such of the old learning as has been retained, and so to offer a complete view of the whole law relating to Corrupt Practices at Elections as it will prevail throughout the United Kingdom on the 15th of October.

The Act of 1883 is not a code of the Laws against Corruption: it is only an Amending Act. To grasp the subject resort must be had to four distinct sources, viz., the Common Law of Parliament, the unrepealed sections of the Acts for the Prevention of Corruption prior to the legislation of this year, the Act of 1883 itself, and the reported decisions of the Election Judges.

There were two methods open to the Authors in treating of the Laws relating to Corrupt Practices at Elections. One was to follow a course, not uncommon, of merely editing the Act of 1883

and presenting it with notes appended to its sections explanatory of their meaning and indicative of the changes in the law. But the Authors felt that this would be but an inadequate and confusing treatment of a subject of great inherent complexity, and would have the necessary effect of making their work a sealed book to all save lawyers. They accordingly discarded this method, and, instead, arranging and methodising the whole learning of the subject in what has seemed to them the most intelligible order, they have inserted the provisions of the new Act in those parts of the Statement into which they seemed naturally to fall.

The Authors hope it will be found that a discussion of no part of the law has been omitted by them, and that they have not failed to note in its appropriate place any decision of authority; while they trust their anxiety to give all the references in contemporary reports to cases quoted will add to the practical usefulness of the book in the hands of the Profession.

M. W. M.

S. C. M.

1, THE CLOISTERS, TEMPLE, E.C.,

*5th September, 1883.*



## CONTENTS.

### TABLE I.

Showing all the Offences which avoid an Election.

### TABLE II.

Showing the Punishments, Incapacities, and Penalties inflicted on Offenders.

### TABLE OF CASES.

---

## PART I.

### THE FORFEITURE OF THE SEAT.

#### CHAPTER I.

Corrupt Practices.

Section 1.—Bribery.

Section 2.—Treating.

Section 3.—Undue Influence.

Section 4.—Personation, and Aiding and Abetting Personation.

Section 5.—False Declaration.

#### CHAPTER II.

Illegal Practices which Avoid the Election if committed by any Agent.

#### CHAPTER III.

The Candidate's Agents within the meaning of Chapters I. and II.

#### CHAPTER IV.

Illegal Practices which Avoid the Election if committed by the Election Agent.

Section 1.—Offences which become Illegal Practices when committed by the Candidate or his Election Agent.

Section 2.—Illegal Practices which only Avoid the Election when committed by the Candidate or his Election Agent.

## CHAPTER V.

The Employment of a Corrupt Agent.

## CHAPTER VI.

General Corruption.

## CHAPTER VII.

The Office and Duties of the Election Agent, and Election Expenses.

Section 1.—His Appointment.

Section 2.—The Nature and Amount of Election Expenses.

Section 3.—The Payment of Election Expenses.

Section 4.—The Return and Declaration of Election Expenses.

## CHAPTER VIII.

Practice and Procedure.

Section 1.—On Applications for Relief.

Section 2.—On Election Petitions.

Section 3.—On a Scrutiny.

Section 4.—Evidence on Election Petitions.

Section 5.—The Awarding and Taxation of Costs.

---

PART II.

THE PUNISHMENT OF OFFENDERS.

## CHAPTER I.

Their Detection and Prosecution.

## CHAPTER II.

Their Punishment.

Section 1.—By Election Commissioners.

Section 2.—By the Election Court.

Section 3.—By a Court of Summary Jurisdiction.

Section 4.—By the Court of Assize.

Section 5.—By the High Court in Suits for Penalties.

## \* APPENDIX

## INDEX.



TABLE I.

(GIVING A COMPLETE LIST OF ALL CORRUPT AND ILLEGAL PRACTICES WHICH AFFECT THE SEAT, AND INDICATING THE SECTION AND ACT UNDER WHICH THEY DO SO.)

PRACTICES WHICH AVOID THE ELECTION.

Corrupt practices (if committed by the candidate or any agent) (secs. 4, 5, 6).		Illegal practices (if committed by the candidate or any agent) (sec. 11).		Illegal practices (if committed by the candidate or the election agent).		Employment of a corrupt agent by the candidate personally (Act of 1865, sec. 41).		General corruption (by whomsoever committed).					
		1	2	3	4								
		Paying for conveyance of voters to the poll (sec. 7).		Paying for electioneering, &c. (sec. 7).		Paying for committee rooms in excess of the number authorised (sec. 7).		Paying election expenses except the authorised election agent (sec. 28).					
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							
		1	2	3	4	5							

K. v. — The offences in italics are so emphasised because the court has no power in any of those cases to grant relief, either under sec. 33 or 33 of the Act of 1883, or at all.

TABLE II.

SHOWING MAXIMUM PUNISHMENTS, INCAPACITIES AND PENALTIES TO WHICH PERSONS ARE EXPOSED FOR OFFENCES AGAINST THE ACT OF 1883.

Offence.	Maximum Punishment.	Incapacities.	Penalties in Civil Court.
Knowingly making a false DECLARATION as to election expenses	7 years' penal servitude and	(1) Incapacity to sit in House of Commons for 7 years. (2) Incapable of being registered as elector or voting at any election (Parliamentary or otherwise) for 7 years. (3) Incapable for 7 years of holding any public or judicial office. (4) If a justice of the peace, barrister, &c., &c., liable to further consequences under sec. 38. All the above incapacities.	
PERSONATION, or aiding, abetting, or inducing to the commission of personation Any other CORRUPT PRACTICE (viz., bribery, treating or undue influence)	2 years' hard labour and 1 year with or without hard labour, or fine of £200 and	All the above incapacities.	
A CORRUPT ARRANGEMENT for the withdrawal of a petition (sec. 41)	1 year's imprisonment or a fine of £200	No incapacities.	
Election agent FAILING to MAKE RETURN OF EXPENSES after being ordered by the Court	Fine of £500 . . . .	No incapacities.	
ILLEGAL PRACTICES . . . .	Fine of £100 . . . .	Incapable of being registered and voting at any election in constituency where <i>illegal practice</i> committed for five years. No incapacities.	
ILLEGAL PAYMENT, HIRING or EMPLOYMENT	Fine of £100 . . . .	No incapacities.	£100 a day to any person who sues for the same.
A Member Sitting and Voting after the expiration of time limited for transmitting return of Election Expenses, when the return is not made	. . . . .	. . . . .	
PROVIDING or GIVING COCKADES, RIBBONS, &c., to persons in constituency during election	. . . . .	. . . . .	40s. and full costs of suit to any person who sues for the same.

N.B.—The above *incapacities* apply to every person convicted of or reported as guilty of any of the offences named; but if a CANDIDATE is reported by an *Election Court* as personally guilty of any *corrupt practice*, in addition to all those incapacities he is disabled for ever sitting in the House of Commons for the constituency in which he offended (sec. 4), and if he is reported as personally guilty of any *illegal practice* he is incapable for the next seven years of sitting in the House of Commons for the constituency in which he offended (sec. 11).

## TABLE OF CASES.

	PAGE		PAGE
Aldridge <i>v.</i> Hurst . . . . .	140, 142, 150	Galway (1) . . . . .	50, 54, 102, 106, 136, 163
Barnstaple . . . . .	173	Galway (2) . . . . .	101
Beal <i>v.</i> Smith . . . . .	144	Gloucester . . . . .	55, 142
Belfast . . . . .	25, 34	Gravesend . . . . .	21, 26, 80, 150, 165
Berwick . . . . .	144, 150, 153, 155, 156, 157, 160, 166	Greenock . . . . .	158
Beverley . . . . .	19, 162	Guildford . . . . .	6, 160
Bewdley . . . . .	37, 42, 68, 71, 73, 75, 81, 144, 165	Hackney . . . . .	166
Blackburn . . . . .	6, 10, 52, 66, 69, 76, 162	Harwich . . . . .	69, 73, 74, 78, 145, 161, 163
Bodmin . . . . .	69	Hartlepool . . . . .	142
Bolton . . . . .	59, 72, 145, 166	Hargreaves <i>v.</i> Scott . . . . .	171
Boston . . . . .	11, 16, 29, 149, 165	Hastings 15, 16, 17, 20, 24, 39, 40, 162	
Bradford . . . . .	9, 41, 42, 103, 159, 163	Hereford . . . . .	139, 143, 144
Bradlaugh <i>v.</i> Clarke . . . . .	129	Hertford . . . . .	75
Brecon . . . . .	9, 43, 142	Hill <i>c.</i> Peel . . . . .	170, 172
Bridgwater . . . . .	84	Hindle <i>c.</i> Waring . . . . .	136
Bristol . . . . .	21, 145	Horsham . . . . .	15
Britt <i>v.</i> Robinson . . . . .	21, 40	Huguenin <i>v.</i> Baseley . . . . .	53
Carrickfergus . . . . .	14, 29	Hughes <i>v.</i> Meyrick . . . . .	173
Carter <i>v.</i> Mills . . . . .	135	James <i>c.</i> Henderson . . . . .	152
Cashel . . . . .	75	Joyce <i>c.</i> O'Donnel . . . . .	151
Clark <i>v.</i> Wallond . . . . .	140, 144	Kidderminster . . . . .	7, 39, 136
Clark's Case . . . . .	56	King's Lynn . . . . .	161
Clitheroe . . . . .	155	Kingston-upon-Hull . . . . .	139
Cheltenham . . . . .	7, 19, 159, 163	Kirkwood <i>v.</i> Webster . . . . .	171
Chester . . . . .	146, 159	Knaresborough . . . . .	158
Cooper <i>v.</i> Slade . . . . .	15, 16, 37	Launceston . . . . .	22, 26
Coventry 15, 33, 40, 56, 145, 158, 166		Lenham <i>v.</i> Barber . . . . .	144
Dover . . . . .	163	Lichfield . . . . .	49, 50, 103, 160, 161
Down . . . . .	49, 55	Limerick . . . . .	82, 105
Drinkwater <i>v.</i> Deakin . . . . .	155	Longford . . . . .	27, 39, 53, 105, 144, 165
Drogheda . . . . .	104, 162	Lord Rendlesham <i>v.</i> Haward . . . . .	97
Dublin . . . . .	15, 68	Londonderry . . . . .	11, 72, 80, 160
Dudley . . . . .	105	Louth . . . . .	39, 43
Durham . . . . .	12, 69	Mackley <i>c.</i> Chillingworth . . . . .	173
Evesham . . . . .	158	Malcolm <i>c.</i> Parry . . . . .	84, 154, 156
		Mallow . . . . .	7, 146

	PAGE		PAGE
Maidstone . . . . .	45	Stafford . . . . .	27, 55, 84
Maunder <i>v.</i> Lowley . . . . .	140	Staleybridge . . . . .	15, 55, 72, 145
Marshall <i>v.</i> James . . . . .	135	Stevens <i>v.</i> Tillett . . . . .	21
Mayo . . . . .	166	Stowe <i>v.</i> Jolliffe . . . . .	97, 151, 154
McLaren <i>v.</i> Home . . . . .	149, 173, 174	Stroud . . . . .	9, 21, 75, 146, 150, 164
Moore <i>v.</i> Kennard . . . . .	143		
Moore <i>v.</i> Scully . . . . .	155		
Morton <i>v.</i> Galway . . . . .	135		
		Tamworth . . . . .	8, 12, 26, 39, 84, 104, 163, 171
Neill <i>v.</i> Batty . . . . .	152	Taunton (1) . . . . .	16, 17, 27, 74, 78
North Durham . . . . .	52, 105, 142	Taunton (2) . . . . .	74
North Norfolk . . . . .	50, 51, 52, 55, 69, 83, 100, 159, 163	Tewkesbury . . . . .	74
Northallerton . . . . .	53, 54, 163	Thirsk . . . . .	150
Norwich . . . . .	10, 68, 83, 85, 101, 104, 144, 153, 155, 161	Thomas <i>v.</i> Wylie . . . . .	139
Nottingham . . . . .	106	Tillett <i>v.</i> Stracey . . . . .	171, 172
		Tipperary . . . . .	160, 161
Oldham . . . . .	19, 153, 156	Trench <i>v.</i> Nolan . . . . .	155, 172
Oxford . . . . .	12	Turnbull <i>v.</i> Janson . . . . .	173
		Tyrone . . . . .	151
Pease <i>v.</i> Norwood . . . . .	136, 139		
Penryn . . . . .	23, 114, 171	Wakefield . . . . .	80
Petersfield . . . . .	52, 165	Wallingford . . . . .	27, 38, 41, 165
Pickering <i>v.</i> Sturtin . . . . .	140	Waterford . . . . .	23, 146
Plymouth . . . . .	15, 30	Wells <i>v.</i> Wren . . . . .	143
Poole . . . . .	8, 44, 105, 165	Wentworth <i>v.</i> Lloyd . . . . .	171
Pontefract . . . . .	45	Westbury, 25, 42, 52, 69, 73, 77, 165	
		Westminster . . . . .	6, 14, 41, 61, 73, 75, 77, 145, 161, 162, 165
Renfrew . . . . .	154	Wigan . . . . .	31, 42, 78, 145, 146, 149, 159, 165
Rothwell's Case . . . . .	56	Wigtown . . . . .	155, 166
		Will's Case . . . . .	56
Salford . . . . .	10, 85, 105, 106, 136, 145, 163	Windsor (1) . . . . .	8, 25, 26, 28, 45, 48, 51, 68, 69, 162
Salisbury (1) . . . . .	13, 73, 164	Windsor (2) . . . . .	51, 73, 162
Salisbury (2) . . . . .	31, 73, 105	Woodward <i>v.</i> Sarsons . . . . .	155, 166
Sandwich . . . . .	14	Worcester . . . . .	160, 166
Shrewsbury . . . . .	10, 73, 138, 140		
Sligo . . . . .	8, 103	Yates <i>v.</i> Leach . . . . .	135, 155
Southampton . . . . .	7, 20, 27, 86, 153, 163, 171	Yorkshire, S.W. Riding . . . . .	145, 153
		Youghal . . . . .	26, 41, 43, 85

THE  
LAW RELATING TO CORRUPT PRACTICES  
AT ELECTIONS.

---

WE purpose treating of the law relating to corrupt and illegal practices at elections; *first*, with reference to the effect of corrupt and illegal acts upon the Seat, and, *secondly*, with reference to their consequences to Individuals.

PART I.

THE FORFEITURE OF THE SEAT.

An election, upon petition, is avoided and the seat forfeited by:

I. Any corrupt act committed by the sitting member *or any one of his agents*, or by—

II. Any of the illegal practices enacted by Sections 7 and 28 of the Act of 1883, whether committed by the sitting member *or any one of his agents*, or by—

III. Any illegal practice enacted by the Act of 1883, committed by the sitting member, *or by his election agent*, or by—

IV. The employment of an agent convicted of or reported for corrupt practices by the candidate *personally*, or by—

V. General corruption by *whomsoever committed*, subject in *certain cases* to the possibility of relief under Section 22, 23, or 34 of the Act of 1883.

## CHAPTER I.

## CORRUPT PRACTICES.

CORRUPT PRACTICES are expressly defined by the Act of 1883. Section 3 is as follows:—

“The expression, ‘corrupt practice,’ as used in this Act, means any of the following offences, namely: Treating and undue influence, as defined by this Act, and bribery, and personation as defined by the enactments set forth in Part 3 of the 3rd Schedule to this Act, and aiding and abetting, counselling and procuring the commission of the offence of personation, and every offence which is a corrupt practice within the meaning of this Act shall be a corrupt practice within the meaning of the Parliamentary Elections Act, 1868.”

And Section 33 of the Act of 1883 makes it a corrupt practice knowingly to make a false declaration accompanying the return of election expenses.

Therefore, under the first head of corrupt practices, it appears that an election is defeated and the sitting member loses his seat if he is guilty of any of the following acts, viz., either

1. BRIBERY ;
2. TREATING ;
3. UNDUE INFLUENCE ;
4. PERSONATION AND AIDING, ABETTING, COUNSELLING,  
AND PROCURING THE COMMISSION OF PERSONATION ;
5. A FALSE DECLARATION ;

whether any one of these corrupt acts is committed by him personally, or by anyone whom the law construes as his agent for the purposes of the election.

It is proposed, in the first instance, to examine the authorities as to what constitutes the offences named, and then to discuss the meaning which has been given to the word “agent” in this connection.

## SECTION I.—BRIBERY.

The Act of 1883 contains no new definition of bribery. On the contrary, Section 3, already quoted, expressly incorporates the definitions of bribery contained in former Corrupt Practices Prevention Acts into the Act of 1883, and in the third schedule of the Act those definitions are set out in detail. It is necessary that in this place we should give their full text. Section 2 of the Corrupt Practices Prevention Act, 1854 (the 17 & 18 Vic. c. 102), provides :

Statutory definitions of bribery.  
17 & 18 Vic.  
c. 102, s. 2.

“The following persons shall be deemed guilty of bribery, and shall be punishable accordingly—

- “1. Every person who shall, directly or indirectly, by himself or by any other person on his behalf, give, lend, or agree to give or lend, or shall offer, promise, or promise to procure, or endeavour to procure any money or valuable consideration to or for any voter, or to or for any person on behalf of any voter, or to or for any other person in order to induce any voter to vote or refrain from voting, or shall corruptly do any such act as aforesaid on account of such voter having voted or refrained from voting at any election : Sub-sec. 1.
- “2. Every person who shall, directly or indirectly, by himself or by any other person on his behalf, give or promise, or agree to give or procure, or offer, promise, or promise to procure or to endeavour to procure any office, place, or employment to or for any voter, or to, or for any person on behalf of any voter, or to or for any other person in order to induce such voter to vote or refrain from voting, or shall corruptly do any such act as aforesaid on account of any voter having voted or refrained from voting at any election : Sub-sec. 2.
- “3. Every person who shall, directly or indirectly, by himself or by any other person on his behalf, make any such gift, loan, offer, promise, procurement, or Sub-sec. 3.

Statutory  
definitions of  
bribery.  
17 & 18 Vic.  
c. 102, s. 2.

agreement as aforesaid to or for any person in order to induce such person to procure or endeavour to procure the return of any person to serve in Parliament, or the vote of any voter at any election:

Sub-sec. 4.

“4. Every person who shall, upon or in consequence of any such gift, loan, offer, promise, or procurement or agreement procure, or engage, promise, or endeavour to procure the return of any person to serve in Parliament or the vote of any voter at any election:

Sub-sec. 5.

“5. Every person who shall advance or pay or cause to be paid any money to or to the use of any other person with the intent that such money or any part thereof shall be expended in bribery at any election, or who shall knowingly pay or cause to be paid any money to any person in discharge or repayment of any money wholly or in part expended in bribery at any election. Provided always, that the aforesaid enactment shall not extend, or be construed to extend to any money paid or agreed to be paid for or on account of any legal expenses *bonâ fide* incurred at or concerning any election.”

Sec. 3.

Section 3 of the same Act provides:

“The following persons shall also be deemed guilty of bribery, and shall be punishable accordingly—

Sub-sec. 1.

“1. Every voter who shall, before or during any election, directly or indirectly, by himself or by any other person on his behalf receive, agree, or contract for any money, gift, loan, or valuable consideration, office, place or employment for himself or for any other person, for voting or agreeing to vote, or for refraining or agreeing to refrain from voting at any election.

Sub-sec. 2.

“2. Every person who shall, after any election, directly or indirectly, by himself or by any other person, on his behalf receive any money or valuable consideration on account of any person having voted



or refrained from voting, or having induced any other person to vote or refrain from voting at any election."

Section 49 of the Representation of the People Act, 1867 (the 30 & 31 Vic. c. 102), is as follows:—

30 & 31 Vic.  
c. 102, s. 49.

"Any person, either directly or indirectly, corruptly paying any rate on behalf of any ratepayer for the purpose of enabling him to be registered as a voter, thereby to influence his vote at any future election, and any candidate or other person, either directly or indirectly, paying any rate on behalf of any voter for the purpose of inducing him to vote or refrain from voting, shall be guilty of bribery, and be punishable accordingly; and any person on whose behalf and with whose privity, any such payment as in this section is mentioned, is made, shall also be guilty of bribery and punishable accordingly."

The Representation of the People (Scotland) Act, 1868 (the 31 & 32 Vic. c. 48, s. 49), contains an exactly similar provision with reference to acts of the kind done in Scotch constituencies.

31 & 32 Vic.  
c. 48, s. 49.

The Universities Elections Amendment (Scotland) Act, 1881 (44 & 45 Vic. c. 40, s. 2), provides:

44 & 45 Vic.  
c. 40, s. 2.

"Any person, either directly or indirectly, corruptly paying any fee for the purpose of enabling any person to be registered as a member of the general council and thereby to influence his vote at any future election, and any candidate or other person, either directly or indirectly, paying such fee on behalf of any person, for the purpose of inducing him to vote or refrain from voting, shall be guilty of bribery, and shall be punishable accordingly; and any person on whose behalf and with whose privity, any such payment as in this section mentioned, is made, shall also be guilty of bribery and punishable accordingly."

Applying these sections to the subject under consideration, viz., the effect of bribery upon the seat, the general result is, that if a candidate or any one of his agents, gives or lends, or offers, or promises to procure, or to endeavour to procure (1) any money; (2) valuable consideration;

Effect of  
statutory  
definition.

Effect of  
statutory  
definition of  
bribery.

(3) office, place, or employment, to or for any voter or to or for any person on behalf of any voter, or to or for *any other person*, in order to induce such voter to vote or refrain from voting, or if he shall *corruptly* do any of the above-mentioned acts on account of any voter having voted or refrained from voting at any election, then the offence of bribery is complete and the seat lost. There are other special acts which are defined as amounting to bribery. They will be treated of in due course; but the effect of the more material sections is as we have stated.

Bribery,  
though  
nothing  
received.

It will be observed that to constitute the full offence of bribery, it is not necessary that the person bribed should actually have received anything. "Every person who shall" . . . merely "agree to give," &c., or even "offer, promise," &c., is guilty of bribery. Nor is it necessary that the person to whom the offer is made should even accept the promise, or be in any way influenced by the corrupt overture. "When bribery is alleged," said Martin, B. in the *Westminster Case* (L.T., n.s., 238; 1 O'M. & H., 89), "the question is as to the *motive of the briber* and not as to the effect on the bribed. It is whether the alleged briber intended to influence or induce the vote, not whether the vote was actually influenced." Therefore, to adopt the illustration used by Mr. Justice Willes, in the *Blackburn Case* (1 O'M. & H., 202; 20 L.T., n.s., 826), if a voter is bribed with half-a-crown and he accepts the bribe and then goes and votes against the party from which he received it, still the corrupt act of giving the money (or promising it) will defeat the whole election. So it has been held that giving, or offering to give a bribe to a person who was on the register, but who, owing to a disqualification arising from non-residence, was not entitled to vote, and did not vote, is none the less bribery (*Guildford Case*, 1 O'M. & H., 15; 19 L.T., n.s., 729).

Motive of the  
briber the  
test.

Stronger  
evidence re-  
quisite when  
offer only

It should be observed that in one or two cases learned judges have pointed out that where the bribery charged is that of corrupt *offers* merely the evidence required to prove

it should be stronger than where money actually passed. (*Cheltenham Case*, 1 O'M. & H., 64; *Mallow Case*, 2 O'M. & H., 22.) This, however, is only a suggestion as to the light in which evidence, on a subject where misunderstanding is so possible, should be viewed, and it must not be taken as in any way infringing upon the well-established law that where the fact of a corrupt offer is once established, the consequence is the loss of the seat. The *Kidderminster Case* (2 O'M. & H., 170) affords a good illustration of a corrupt offer amounting to bribery, though the persons to whom it was made received nothing under it. There the respondent the night before the election, in the course of a speech, said: "When we have won the election we will have an entertainment together." He repeated this *after* the election, and in pursuance of his promise sent down a large sum of money to be spent in organising a *fête*. The entertainment was not, in fact, held, but Mr. Justice Mellor decided that the corrupt promise made on the night before the polling constituted bribery, and the respondent was unseated.

But offer may be bribery.

It is not necessary that the bribe should be made *directly* to the voter or to the person sought to be bribed. If, though in fact it is given or made to some third person, the Court is satisfied that through such third person it is intended that the voter shall actually receive the benefit of it, or be influenced by it, that is enough: as when colourable payments are made to the children of voters for fancied services in order that their parents may be induced to vote in a particular way. Mr. Justice Willes, in the *Southampton Case* (1 O'M. & H., 223), referred to such a case and drew this distinction. If payments are made to young children forming part of a family in respect of services really rendered by them, the payments are to be regarded as made to their parents, and if the latter vote at the election, their votes must come off on a scrutiny. But if payments are made to young children who have rendered no services, or nominal services, with the view of influencing their parents who are voters, that will be bribery which will affect the seat. No doubt the latter proposition is as sound now as

Bribe need not be given directly.

Payments to children may be bribes to their parents.

Bribe need  
not be given  
directly.

when the learned judge first laid it down some years ago ; but with regard to the first it must be remarked that Section 17 of the Act of 1883, makes it an illegal employment involving the sacrifice of the seat, when committed by the candidate *or his election agent*, to employ for payment any persons over and above the limited number specified in the Schedule. This would seem to include children and to affect the election when they are employed by the persons specified in excess of the number allowed. In another case it was laid down that treating (and *à fortiori* bribing) women with a view of influencing their husbands, brothers or sweet-hearts, who were voters, would avoid the election (per Willes, J., in the *Tamworth Case*, 1 O'M. & H., 86 ; the *Poole Case*, 31 L.T., n.s., 171).

Bribing  
women may  
affect the  
seat.

Time when  
bribe given.

With regard to the time at which the bribery is committed, it is immaterial how long *before* the election the bribe is given. The law on this point was stated emphatically and clearly in the *Sligo Case* (1 O'M. & H., 302) : " Any act committed previous to an election, no matter at what distance of time, *with a view to influence a voter at a coming election*, whether it is one, two, or three years before, is just as much bribery as if it was committed the day before the election ; nay, more, if a man commits bribery in the first week of a Parliament, and if he sues for the suffrages of that constituency in the last week of the seven years which precede the dissolution, that act committed six years before can be given in evidence against him, and his seat will not hold an hour." Lord Blackburn in the *Windsor Case* (31 L.T., n.s., 136), suggested a limitation to the generality of this rule—viz., that a bribe given a long time before the election only invalidates the subsequent election if it is *possible* that it may still be operating on the mind of the voter. Therefore in the cases put by his lordship, where (1) a bribe is given to a voter and he dies before the election ; or, (2) where a bribe is given but before the election both the briber and the voter repent and the money is returned, he stated the election would not be avoided ; but having regard to the stringency of Sections 4 and 5 of the Act of 1883, which, without any qualification

Immaterial  
how long  
*before*.

Suggested  
limitation.

whatever, incapacitate a person from sitting in Parliament for a term specified therein who has been guilty of any corrupt practice in reference to an election, it is doubtful whether in the cases put the seat would now be safe.

When something is given to a voter *after* he has voted, it must be noted that in the words of the Act the giving of the thing is only bribery where it is given "corruptly." The distinction which has been drawn is this : Where money or money's worth is given to a voter before he votes in order to induce him to do so, the law infers the corrupt act, which is the material element in bribery ; but where money or money's worth is given to a man after he has voted the burden of proving a corrupt arrangement or understanding between him and the candidate or his agent prior to the voting is thrown upon those suggesting bribery. "If money is given to a man before an election to induce him to vote or refrain from voting, it is *ipso facto* bribery, and has the effect of disqualifying the candidate from being elected ; but if the money is given after the man has voted it must be shown to have been given corruptly." (Martin, B., in the *Second Bradford Case*, 19 L.T., n.s., 723 ; *Brecon Case*, 2 O'M. & H., 44.) It may well be doubted, however, whether in the practical conclusion to be drawn from the giving of money to a voter immediately after an election there is much distinction between such a case and the case where it is given before. Possibly the fact of the gift in the former case may be explained consistently with the honesty of the giver, but apart from some satisfactory explanation, the mere circumstance that a voter received money or money's worth for voting would afford a very strong presumption that he received it in fulfilment of a corrupt bargain. In the case suggested by the present Lord Bramwell in the *Stroud Case* (2 O'M. & H., 184), the inference of a corrupt arrangement would not be drawn. "For instance," said his lordship, "such a thing as this might happen, if a man voted and got turned out of his situation and went to anybody for charity, and a man said, 'I am sorry for you, here is a sovereign,' that would not be a corrupt payment, though

Effect of  
bribe given  
*after* election.

Little practical  
difference.

it might be said to have been given on account of the man having voted a particular way. Nevertheless, in almost every case where a payment is made in consequence of a voter having voted, it would be a corrupt giving, unless some reason, such as I have suggested, could be given."

The *amount* of the bribe is of no importance when the fact that it was given as a bribe is established. It is strange that there was once some doubt on this point. Baron Martin intimated in the *Salford Case* (1 O'M. & H., 142; 20 L.T., n.s., 127) that when the sum spent in bribery did not exceed half-a-crown and it was not brought home to the candidate *personally*, that such bribery would not be sufficient to forfeit the seat. The doubt which has arisen on the subject and crept into some works of authority is entirely founded upon this *dictum*, which, however, was *obiter*, as his lordship found the particular bribes suggested had not in fact been proved. On the other hand Mr. Justice Willes, in the *Blackburn Case* (1 O'M. & H., 202; 20 L.T., 823), distinctly stated that in his view a bribe of half-a-crown given to a voter, though it did not in fact influence his vote, would upset the election. Mr. Baron Channell, in the *Shrewsbury Case* (2 O'M. & H., 37), said that he agreed with Mr. Justice Willes rather than with Baron Martin, and that in his view, when once the act of bribery is made out the Court cannot consider whether it is significant in amount or insignificant. And in the *Norwich Case* (2 O'M. & H., 41), Mr. Justice Keating decided that a single act of bribery without reference to the sum given, avoided the election. Taking the plain words of the Act of 1854, which defines bribery as the giving, &c., of *any* money or valuable consideration, and the current of authorities quoted above, it cannot be doubted that the law now is that if the sitting member or his agent has given a bribe, no matter how small the sum or comparatively valueless the thing, the election is defeated. The inference is the stronger since the passing of the Act of 1883, as it must be carefully noted that the 22nd Section which, under very stringent conditions, relieves a candidate from the consequences of an agent's

Amount of  
bribe  
immaterial.



misconduct where the same is of a "trivial, unimportant and limited character," applies only to cases of treating, undue influence and illegal practices, and has no application to a case of bribery. To pay a debt of a voter, to release him from prison that he may vote is an act of bribery (*Londonderry Case*, 1 O'M. & H., 275).

The *form* in which the bribe is given is immaterial. If, though the money is given under the name of a payment for services rendered, it is really a reward for voting, the offence is proved. The Court will look at the substance of the transaction and not allow itself to be hoodwinked by a mere name. A common way in which the law against bribery has been sought to be evaded has been by payments made to voters for services alleged to have been rendered in connection with the election, as where voters have been appointed canvassers, messengers, watchers, clerks, and so forth and paid—generally in excess of the remuneration ordinarily given to persons in their station. From the earliest times the law has been that this "colourable" employment of voters with the real view of paying them for their votes was bribery. One of the leading cases on this subject is the *Boston Case* (44 L.T., n.s., 288; 3 O'M. & H., 153). The acts of bribery complained of in the petition there consisted mainly of the employment on the polling day of a large number of persons, the bulk of whom were voters, to act as watchers. They were ranked in the election accounts amongst "clerks, messengers, tickers, canvassers and watchers;" they were paid at rates varying from 10s. to 2s. 6d. a day, and there appear to have been about 300 or 400 of them. The Court was of opinion, on the facts, that the object in employing all these persons was not to obtain *bonâ fide* services from them but to influence their votes and the sitting member was unseated accordingly. The judgment, which was given by the late Lord Justice Lush with the concurrence of the other judge (Mr. Justice Manisty), is worth a perusal as well for the review of the authorities it contains as the clear and emphatic language in which the law

The form of the bribe immaterial.

Paying voters for services may be bribery.

The *Boston Case*.

Lush, L.J., judgment of.

Payment for  
"colourable"  
service.  
Judgment of  
Lush, L.J.

on the subject is expressed. "In view of all these circumstances, can we come to any other conclusion than that the employment of this large body of voters was a colourable employment and a pretext for finding them a day's wages in order to induce them to vote? It is immaterial whether the object was to gain over voters from the other side or to prevent them going over to that side. The Act forbids and makes penal any attempt to influence a vote by such means. We need hardly say that it is no answer to a charge of violating the Bribery Act in this way, that it is a common practice, or that it was resorted to in self-defence and as a means of counteracting illegal practices on the other side. Sitting here in a court of justice we cannot accept such a plea. We have reason to fear that the practice is too common, notwithstanding the warnings which have been given in previous decisions. In 1869, Mr. Justice, now Lord, Blackburn, reported the employment of voters as watchers, who rendered no service of any value, as a corrupt practice. In the same year, in the *Tamworth Case*, the late Willes, J., had to consider a case where the agent had been authorised to engage a few men, none of whom were to be voters, whereas the man on the polling day engaged 130, of whom 29 only were voters. He came to the conclusion that the agent employed them, not to advance the interest of his employer, but to gain popularity for himself; but he emphatically said, that if he had arrived at the conclusion that the object was to engage one voter to vote for his employer, who would otherwise have voted for his opponent, he should have declared the election void. In 1874, Baron Bramwell deprecated the practice as shown in the *Durham Case*, and warned future candidates of the danger they incurred by following such a practice. And in 1875 I had to declare in the *Norwich Case* that the election was void, solely on the ground of the colourable employment of voters as messengers on the polling day." (See also *Oxford Case*, 3 O'M. & H., 154.)

Review of the  
authorities  
on the subject.

Payment of  
voters not  
necessarily  
bribery.

On the other hand, the mere employment and payment of a considerable number of voters in connection with an election,



when there was *bonâ fide* work for them to do, and they were not paid substantially in excess of the ordinary remuneration, did not, prior to the Act of 1883, invalidate the election (The *Salisbury Case*, 4 O'M. & H., 23). Nor is it now a *corrupt practice*, defeating the election, when committed by any agent, though, as will be seen later on, it is (except under certain strict limitations) an illegal employment, avoiding the election, when committed by the candidate or *his election agent*. Prior to the new legislation, the law was this: If persons were colourably employed and paid for work they never did, in order to influence their votes, this was bribery, and if done by any agent of the candidate, the election was defeated. But if persons were *bonâ fide* paid for work which they really did, it was not bribery, though inasmuch, as by the 30 & 31 Vic. c. 102, s. 11, voters who have received any payment in connection with the election, are disqualified from voting, on a scrutiny their votes would be struck off. Now it is conceived that the colourable employment and payment of voters to secure their votes, is as much bribery as ever, and when it is committed by *any* agent, the seat is lost. On the other hand, when the employment and payment of voters is *bonâ fide*, and when they are not employed by the candidate *himself* or *his election agent*, though the votes given must come off on a scrutiny, and though the persons employing and the persons knowingly employed, are liable to certain penalties mentioned later on, it is submitted the seat will not be affected. But under the Act of 1883, to employ and pay any voters, except the few specified in the schedule, is an illegal employment, and an illegal employment, when committed by a candidate, or *his election agent*, becomes an illegal practice, and vitiates the election. The way in which the law will now operate may be illustrated thus: A is an agent of the sitting member at the election (though not his election agent). He *bonâ fide* employs B, who is a voter, and pays him for work he really performs. The election is not defeated; though on a scrutiny, B's vote must come off, and both A and B are liable to punishment. A is an agent of the sitting

Law prior to  
Act of 1883.

Law on this  
point now.

The present  
law  
illustrated.

member at the election (though not his election agent). He pays B a sum of money under the name of wages, but really to get his vote. This is bribery, and the election is vitiated. A is the election agent of the candidate. He *bonâ fide* (but in excess of the proper number) employs B, who is a voter, and pays him for services he really rendered. This is an illegal practice when committed by an election agent and the election is defeated.

Bribery  
cloaked  
under pay-  
ments.

Other instances of bribery, cloaked under the pretence of payment, are where excessive prices are paid for things bought or rooms hired which are not wanted, with a view of influencing the vote of the persons who receive the money. Thus, in the *Westminster Case* (1 O'M. & H., 90; 20 L.T., n.s., 238) it was suggested that the respondent through his agents had paid unusual sums for the right of placarding, in order to secure the votes of the persons paid. The learned judge was not satisfied that the charge was made out, but he stated emphatically that if it were proved that money had been paid with such an object, it would be bribery. So, where cabs are colourably hired for the purpose of procuring the votes of their owners (the *Carrickfergus Case* 3 O'M. & H., 91) or as in the *Sandwich Case* (3 O'M. & H., 158) where a large number of rooms were hired in public-houses with a view of securing the vote and interest of the innkeepers. "There is no difference," said the Lord Justice Lush in this case, "in substance between a colourable hiring of a voter's room as a committee-room, and the colourable hiring of the voter himself as a messenger. The object in each case is to secure his vote. The only difference between the two cases is the form of the disguise." It may be mentioned that the three cases last given are all specially dealt with by the Act of 1883. The hiring of committee-rooms in excess of the limit allowed, and the hiring of windows or boards from *electors* are made illegal practices (Sec. 7), which avoid the election, if committed by any agent; and the hiring of cabs in connection with the conveyance of voters, is an illegal hiring (Sec. 14), which avoids the election when committed

Hiring rooms  
in public-  
houses.

Bribery  
cloaked under  
payments.

by the election agent. The offences are complete under the new Act, without any reference to the question whether the voters, boards, or cabs were *bonâ fide* needed.

Analogous to bribery under the colour of paying wages for work done, or a price for things supplied, is bribery under the pretence of compensating a voter for loss of time and for travelling expenses. It has always been held that promising to pay a voter his day's wages, so that he may be no loser by coming to vote, was an act of bribery (the *Staley-bridge Case*, 20 L.T., n.s., 75; 1 O'M. & H., 67; *Hastings Case*, 10 O'M. & H., 219; 21 L.T., n.s., 234.) "It is clear that as the law is framed and as the statute is worded, to pay a person for coming to vote, giving him his day's wages or making up to him his loss of time for the purpose of voting at an election, would be a bribe. The words of the Act are clear beyond all question on this point." (Per Blackburn, J., in *Hastings Case*, quoted *supra*.) Equally the payment of a substitute to do the voter's work while he is away voting is bribery. (The *Plymouth Case*, 3 O'M. & H., 107.)

Bribery to compensate voter for loss of time.

Or pay for a substitute.

So with regard to travelling expenses, to promise to pay a voter his travelling expenses if he comes and votes for a particular candidate is bribery. This was first clearly decided in the case of *Cooper v. Slade*. (6 House of Lords' Cases 747; 27 L.J., Q.B., 449; 4 *Jurist*, n.s., 791.) The action was brought to recover penalties from the defendant, who had been a candidate at the Cambridge election; and the question which came before the Lords for decision was whether a letter written to an outvoter requesting him to come to the borough and record his vote, and adding in a postscript "your railway expenses will be paid," was an act of bribery. The House of Lords, after consulting the judges, held that such a promise amounted to bribery. In the *Coventry Case* (1 O'M. & H., 109; 20 L.T., n.s., 405), *Dublin Case* (1 O'M. & H., 273), and still more lately in the *Horsham Case* (3 O'M. & H., 54) this view of the law was acted upon; and there can be no doubt that as the law now stands a promise to pay the *bare* travelling expenses of a voter if he

So to promise to pay travelling expenses.

*Cooper v. Slade*.

will come and give his vote is an act of bribery. But when a circular was sent to an outvoter asking him to come over and record his vote and enclosing a railway pass, but annexing no condition to its use, it was held that this did not come within the doctrine of *Cooper v. Slade*, and though (as the law then stood with regard to borough elections) an illegal act, it was not bribery (the *Bolton Case*, 31 L.T., n.s., 194; 2 O'M. & H., 138.) In giving his decision the learned judge (Mr. Justice Mellor) carefully distinguished the case before him from *Cooper v. Slade*. In the latter he pointed out the travelling expenses were promised conditionally if the voter came and voted for Mr. Slade. In the case before him, the railway pass was sent and received by the voter without any condition. All control over the railway pass was gone after it left the office of the respondent's agent, and the voter if he liked could avail himself of the pass without being under any compulsion to vote for the respondent.

But unconditional payment is not bribery.

Now all payments for travelling expenses illegal.

However, the *Bolton Case* has now ceased to be of much practical importance. No doubt the ruling of the learned judge in that case will still be accepted to the extent that sending a railway pass to a voter, or giving him his bare travelling expenses unconditionally, will be held to fall short of a corrupt practice; but Section 7 of the Act of 1883 makes the payment of any money on account of the "conveyance of electors to or from the poll" an illegal practice, which if committed by a candidate or *any one of his agents* will avoid the election.

Payments for attending Revision Court may not be bribery.

But though paying a voter for his loss of time in attending to vote is bribery, paying him for his loss of time attending at the Registration Court to claim and support his vote is not necessarily bribery. It may or may not be bribery according to the time when, the circumstances under which the money was paid, and the amount paid. The *Taunton Case* (1 O'M. & H., 353; 21 L.T., n.s., 169), where the present Lord Blackburn decided that payments in respect of loss of time at the Registration Court *did* amount to bribery, and the *Hastings Case* (1 O'M. & H., 219; 21 L.T., n.s., 234), where the same learned judge held that such payments

*did not* establish bribery, may profitably be examined in this connection. In the *Taunton Case* it was proved that the Registration Court was held in September. The election came off in November. The payments were not made till November and upon the eve of the election, and they were made without due precautions being taken that only persons who had really attended the Registration Court and earned the money got it. Under these circumstances, it was held that the money was not paid *bonâ fide* to recoup the persons for their loss of time at the registration, but to influence their votes at the election.

When payments for attending Revision Court bribery.

"It may well be," said the learned judge, "that there may be a payment for an attendance at the Barrister's Court, which should be *bonâ fide* for that purpose and no other, and which is not meant by the Act of Parliament. From the fact of paying a person money for attending to be put upon the register, it is a matter of inference that doubtless the persons who put the voter on the register expected him to vote for their party. No doubt that would be in their minds at the time. Doubtless, if you were to pay a man direct for being put upon the register, and to offer a reward for every person who would himself come and be registered by the Conservative Association or the Liberal Association, as the case might be, it would not be as a matter of law that that would be a bribe for a vote; but it would be a matter of very strong observation, and there would be reasonable grounds for inferring that those who paid people belonging to any particular political party for coming and being put upon the register did expect, as part of what they were paying for, that they were to vote for that party when the election came. It would be a matter of fact, not of law, but the inference would be strong from it. When it is merely re-paying them what might be called money out of pocket, the loss of a day's work, the inference is by no means so strong. It might be so, or it might not be. In each case it would be a matter of inference looking at the facts, and a very important fact would be whether or no an election was pending or close approaching. It would require

The *Taunton Case*.

The test is whether payment is really made for loss of time at Revision Court.

Or was intended to influence vote at election.

looking at that to see whether it was really or not paid to induce the votes, or whether it was really and *bonâ fide* a repayment for money out of pocket. I certainly think it would be a wise thing on the part of all people to avoid making such payments at any time, because, certainly it is always open to the observation and inference that it may be for the corrupt practice of inducing the vote, and may, therefore, be considered bribery. In the present case, however, we have to go a great deal further than that. I think, where it was *bonâ fide*, it would not be a bribe; where it was intended to induce a vote, which would be a matter to be collected from the whole of the facts, it would be a bribe."

The *Hastings Case*.

On the other hand, in the *Hastings Case* (quoted *supra*), the payments were made at the time of the registration, they did not exceed the sums the voters were out of pocket, and some precautions were taken that only persons entitled got the money. The learned judge held that in this case the payments did not amount to bribes, pointing out that the important elements in determining whether the money was a payment for the vote were (1st), whether the payments were really and truly made contemporaneously with the registration; and (2ndly), whether they were honestly intended to be merely a remuneration for what the man was out of pocket, so that he should not be a loser, or whether the intention was that he should make a profit. Although his lordship decided that the payments in that case fell short of bribes, yet, in concluding his judgment, he said that payments made for a registration, especially when the registration is coming so closely before an election, were suspicious things, and a very little additional evidence in such a case as that before him, would lead him to the conclusion that the intention of the payment was to influence the election.

Paying rates to put a person on the register.

By the express words of the 30 & 31 Vic. c. 102, s. 49, corruptly paying any rate on behalf of a ratepayer for the purpose of enabling him to be registered as a voter, and for the purpose of influencing his vote at any future election, is bribery. The mere fact of paying the ratepayer's rates is not

enough to constitute the offence. It must be proved that it was done to influence his vote (the *Cheltenham Case*, 1 O'M. & H., 64), though, apart from any evidence of a direct arrangement, the court will, when the surrounding circumstances point to it, infer the corrupt intention with which the thing was done. In the *Oldham Case* (1 O'M. & H., 165), it was proved that an alleged agent paid a voter's rates in order that he should get him on to the register; but it was also proved as a fact that there was no arrangement or understanding come to as to how he was to vote. The learned judge held that there was no corrupt payment of rates, and, therefore, no act of bribery. Payments made to a freeman, or on his behalf, to enable him to take up his freedom, and so be placed upon the register, do not come within the provisions of the 30 & 31 Vic. c. 102, s. 49; and, therefore, whether or no such payments amount to bribery will turn upon the question of the existence of any arrangement or understanding as to the vote.

Although the bribe is given at a municipal election, yet, if it is intended or calculated to influence the parliamentary election, it is in law a bribe with reference to the latter as well as the former. In the *Beverley Case* (1 O'M. & H., 143; 20 L.T., n.s., 792) there was little or no bribery suggested at the parliamentary election, but the case for the petitioners was that a wholesale system of corruption prevailed at the municipal election, held a fortnight before the parliamentary election. It was proved that bribery at municipal elections in **Beverley** was so common and notorious that the price which votes brought upon such occasions was well known. The ordinary bribe was 5s. a vote, and the sum usually spent at a municipal election in corruption was £130. At the particular election in question, however, it was shown (1) that sums three or four times in excess of the ordinary bribes were paid to each voter; (2) that about £800 was disbursed in this way; (3) that nearly 1,000 persons were bribed; and (4) that after the municipal elections were practically decided, the respondent's agents went on bribing as extensively as before. The learned judge held, that though these bribes

Effect of  
bribery at  
municipal  
election.

The *Beverley*  
*Case*.

were nominally given with reference to the municipal election, they were really intended to influence the parliamentary election, which was known to be imminent, and indeed came off in a fortnight, and he unseated the sitting members accordingly. In this case the facts were clear, and the whole proceeding most flagrant and gross.

Must be  
connection  
between  
municipal and  
parliamentary  
election.

The *South-*  
*ampton Case*.

It is necessary, however, to connect the two elections—the municipal and parliamentary—together, and show that though nominally they are two contests, in fact, they are regarded by the parties bribing as one. And in the *Southampton Case* (1 O'M. & H., 226), and the *Hastings Case* (1 O'M. & H., 217, 21 L.T., n.s., 234), where the evidence failed on this point, bribery at a municipal election which preceded the parliamentary by a very short while, was held not to affect the validity of the latter. “These elections,” said Mr. Justice Willes in the former case, “are *primâ facie* distinct; there is no necessary connection between them, and it is not enough to show misconduct with reference to the municipal election without connecting that election in some way with the parliamentary election. There have been cases in which it was clear that the municipal and the parliamentary election were part of one political contest, and that corrupt action at the municipal election either was intended expressly to operate upon parliamentary elections, or that the necessary result of what was done at the municipal election was to affect the parliamentary election; where, upon the principle being applied that persons must contemplate the natural consequences of their acts, an intention to affect the parliamentary election ought to be attributed both to people who were shown to have misconducted themselves with reference to the municipal election, and to agents of the members who have been guilty of corrupt practices in the course of the municipal election, but with a view to the effect of such practices upon the parliamentary election. In such cases the judges have held that the two elections were, under the circumstances, really parts of one and the same political contest, and that the members in the parliamentary contests were bound by the acts of their agents in the course of the municipal contest.”



On the same principle, in the *Bristol Case* (2 O'M. & H., 27), reported as *Britt v. Robinson* in the Common Pleas (L.R. 5, C.P., 503; 39 L.J., C.P., 265; 23 L.T., 188; 18 W.R., 866), where a test ballot was held amongst three Liberal candidates to determine which should be the candidate of the party, and an act of bribery was committed with a view of securing a vote *at the test ballot*, it was held that inasmuch as the effect of the bribe would probably also be to secure the vote for the respondent (who, as the event of the test ballot, was accepted as the Liberal candidate and elected) at the real contest which was impending, the corrupt act had relation to it, and avoided the election.

Bribery at a test ballot.

So the bribery need not have been committed with reference to the particular parliamentary election the return at which is petitioned against. Suppose A is a candidate at an election in January, and is unsuccessful at the poll, but succeeds in unseating his opponent on petition, and a new election is held in May, and A is a candidate again and polls a majority of votes. In the event of a petition against his return, he is liable to be unseated for any act of corruption committed either at the January election or the May election, for the second election, under these circumstances, is but a continuation of the first, the exigency of the writ not being satisfied until there is a *good* return. (See *Stevens v. Tillett*, L.R. 6, C.P., 147; 40 L.J., C.P., 58), as to the law on the subject, and the three *Stroud Cases* (2 O'M. & H., pp. 107, 179 and 181) as to its practical operation.

Bribery committed at former election.

Giving workmen a holiday on the polling day, and paying them as if they had worked, may be an act of bribery. In the *Gravesend Case* (3 O'M. & H., 84; 44 L.T., n.s., 64), it was held to amount to bribery. In the *Stroud Case* (2 O'M. & H., 181) it was held to fall short of it. In the first of these cases it was proved that on the day *before the polling* a communication was made to all the workmen in the respondent's employment that they would have a holiday on the next day, but that they would be paid as usual, and that they must come the next morning and give in their time. It was proved that on the occasion of previous elections a holiday

Giving a holiday may be bribery.

*Gravesend Case.*

Giving a holiday may be bribery.

had been given to the respondent's men, *but no payment was made to them in respect of the day*. In giving judgment, Mr. Justice Denman said: "It was contended that Weeks (the respondent's agent) made the above-mentioned communication to the men with the intention of influencing their votes. It was urged on the other side that it was a mere act of benevolence or justice, and had no connection with the pending election. We cannot adopt this latter view. We think it beyond all question that Weeks had the election in view when he made his communication to the men on the night preceding the polling day, and intended it to influence the votes of all who might be doubtful." On the other hand, in the *Stroud Case* (quoted *supra*), it was also proved that the men at certain mills belonging to the respondent's agents received a holiday on the polling day, and were paid for that day; but, unlike the *Gravesend Case*, there was no evidence that *previous* to the polling day they were promised their wages. It was argued for the petitioners that there was an implied promise, inasmuch as at an election held three months before the men also had a holiday, and afterwards got their wages; but Mr. Baron Bramwell held that a single instance of prior payment did not warrant the inference that payment would be made a second time, and he declined to hold that the act of paying the wages after the election, disconnected from any promise made before, was bribery.

Promising an advantage bribery, though no condition annexed.

*Launceston Case.*

The principle of the *Gravesend Case* seems to be that a promise of some advantage to an elector, made with the view of influencing his vote, is bribery, though it is not proved that any express condition is annexed to the fulfilment of the promise. And in full accordance with this principle is the decision in the *Launceston Case* (2 O'M. & H., 129; 30 L.T., n.s., 823). There it was proved that the respondent was a large landowner in the borough. During the progress of the contest some clamour was raised with reference to his preservation of the rabbits on his estate. A night or two before the polling the respondent, addressing a public meeting, said: "I give authority for you, everyone of you, to kill every rabbit upon my estate; kill them, ferret

them, shoot them, trap them, do whatever you like, send them to market." At other meetings the respondent and his agents used similar language, and they took special measures to secure the wide circulation of a local paper containing the public declaration of the respondent's views on this subject. Mr. Justice Mellor, who tried the case, decided that this was an offer of a "valuable consideration" within the statutes and that an act of bribery had been committed by the respondent *personally*. His lordship drew the distinction between the case where the motive for the act was the *bonâ fide* desire of a landlord to give his tenants a privilege, and where the object was to influence the election, as he believed was the object in the case before him.

The statute makes it bribery to offer any office or employment as an inducement to an elector to vote. In the *Waterford Case* (2 O'M. & H., 25), it was held that an offer made by the agent of the respondent to vacate a seat in the town council in favour of a certain person if he would vote for the respondent was a bribe within the meaning of the Act. But to give a man *bonâ fide* employment unconnected with the election is not bribery, merely because the man happens to be a voter. "A man is not bound to refuse to take into his service a man of his way of thinking if he is going to set up for the borough. He must not do that as a reward for the vote he hopes to obtain, and he must not make the vote a condition of employment. But the employment of persons to do work must go on in election times as well as in others; the affairs of life cannot be brought to a standstill." (*Per* Willes, J., in the *Penryn Case*, 1 O'M. & H., 128). Employment in connection with the election is a different thing, and, except to a very limited extent, it is now entirely prohibited by the Act of 1883.

Offer of an office.

Giving *bonâ fide* employment not bribery.

It remains that we should consider to what extent a candidate may bring himself within the law against bribery by lavish expenditure in the constituency, by large subscriptions to institutions, and by profuse and wholesale charities. It may be presumed that the importance of this branch if the law is destined to increase. Profusion *at* an election

Profusion before an election.

is now under the ban of the legislature; but there is no express enactment against profusion *before* an election, and it may be it will be found that the wealthy will seek to indemnify themselves for their enforced parsimony during the contest by increased generosity in the intervals between elections. There can be little question that a system of corruption as pernicious, and probably almost as efficacious, could grow up in this way as the profusion at an election which, under this new law, is apparently doomed.

Lavish  
expenditure.

The only case in the books upon the subject of lavish expenditure and its effect upon an election is the *Hastings Case* (1 O'M. & H., 217; 21 L.T., n.s., 234). In giving judgment the present Lord Blackburn said: "It was shown that Mr. and Mrs. Brassey had bills with the tradesmen and spent a very considerable sum of money in the town; and it was said as part of the petitioner's case, that that expenditure had been increased, and was the more lavish, because the election was coming on; in short, that there was a lavish household expenditure, with a view of influencing the election with the same intention and in the same way as would, if it had been an expenditure of meat and drink to influence the election, have come within the definition of treating. *But there is no law yet which says that any lavish expenditure in a neighbourhood with a view of gaining influence in the neighbourhood and influencing an election, is illegal at all.*" In order to constitute anything that would be a corrupt practice in respect of expenditure of that sort, it must be made with a view of *influencing a particular vote*. If such an expenditure is made at a place with a tacit understanding of this kind, 'I will incur bills and spend my money with you if you will vote for me, that being not the side on which you intended to vote,' if it is intended to produce that effect upon the vote, it amounts to bribery. In the present case there is nothing to show that in either of the cases there was such an understanding or such an arrangement made. Whether or not the expenditure was more lavish than it would otherwise have been is no matter for me to enquire into, because that would not affect the election if it was made out."

Not neces-  
sarily illegal.

The law which his lordship laid down fourteen years ago is law still; and there is no attempt in the Act of 1883 to alter it, for the design of the new law seems to be that those things which were bribery before shall be bribery still, but that the punishment of the offence shall be greatly increased. The view of Lord Blackburn is this: There is no reason why a man who is a candidate in a constituency should not live and spend his money there. That is perfectly legal, but if he makes the spending of his money with any particular persons conditional on their voting for him he is guilty of bribery.

Lord Blackburn's view.

Subscriptions in themselves are legal, and, though of course they may be given under such circumstances as to amount to bribery, it would probably require a strong case to satisfy the court of this. There are two reported cases where subscriptions were charged as corrupt acts. In the *Westbury Case* (1 O'M. & H., 49) it was proved that the petitioner (the recriminatory case was under investigation) had sent a cheque for £10 as a subscription to a dissenting chapel almost at the same time that he issued his address as a candidate. Mr. Justice Willes said: "I have myself often observed that people who mean to become candidates subscribe to things they would otherwise not have subscribed to; but I think that is a step off corrupt practices; it is charity stimulated by gratitude or hope of favours to come." So, in the *Belfast Case* (1 O'M. & H., 282; 21 L.T., n.s., 475) where it was proved that the respondent had subscribed to an Orange Lodge, although his principles were not identical with those of the lodge, Baron Fitzgerald declined to hold that this was an act of bribery.

Subscriptions.

But there is much more danger attendant upon the distribution of charities, and though no person has yet been unseated on account of subscriptions or a lavish expenditure, there are many cases of seats forfeited for acts which the sitting member called charitable acts, but the court held to be bribes under the cloak of charity.

Charities.

In the *Windsor Case* (1 O'M. & H., 2; 19 L.T., n.s., 613) the respondent gave a pound to a voter who had previously

The *Windsor Case*.

promised him his vote, and who subsequently came to him in distress. Mr. Justice Willes held that upon all the facts this was not a bribe. This case must not be misunderstood. It does not settle that giving a pound to a voter who is in distressed circumstances is necessarily an innocent act. On the contrary, unexplained it raises a strong presumption of bribery against the person who gives the money. In the *Windsor Case* it must be assumed that the learned judge who saw and heard the parties was satisfied that the respondent acted from motives of pity merely. In this view the case is an authority for saying that a single gift of money by a candidate during an election is not necessarily bribery. If, however, several benevolences of the same kind were established against the respondent, he would seem clearly to come within the *Gravesend Case* (44 L.T., n.s., 64; 3 O'M & H., 84), and the *Launceston Case* (2 O'M. & H., 129; 30 L.T., n.s., 823).

*Tamworth Case.*

In the *Tamworth Case* (20 L.T., n.s., 181) it was proved that the respondent, on the night of the nomination, visited one of the cottages on his property, in company with a person whose name was not known, for the purpose of canvassing the tenant. He saw the tenant's wife, who complained that she was in pain and distress and about to be confined, and that the roof of the cottage was out of repair and it was raining in. At the respondent's request his companion gave her 5s. Mr. Justice Willes held that this was not a corrupt act, but charity, natural under the circumstances.

*Foughal Case.*

The *Foughal Case* (21 L.T., n.s., 307; 1 O'M. & H., 294) is a somewhat singular case. It was proved that on and immediately before the polling day, large sums of money were distributed in shillings and half-crowns to poor people in the streets of the borough. As much as £160 was so given away by one person, £130 by another, and £50 by another. None of this money, however, was given to voters. The learned judge unseated the respondent on other grounds, but as to this part of the case, suggested that bribery was not made out. It is impossible to criticise a decision in

which everything turns upon the character of the evidence, of which the judge at the hearing is obviously the most competent judge; but it is necessary to point out that such a proceeding as openly distributing money on the polling day among poor persons, though none of them may be voters, is sailing perilously near a very grave violation of the law. We do not think the fact that the money is given to non-voters only is conclusive, because money given to persons not on the register, with the view of bringing their influence to bear on voters is, we submit, within the words and meaning of the statute. The definition of bribery, given in the Act of 1854, runs:—"Every person who shall . . . give . . . to any voter, or to *any person*, in order to induce any voter to vote," &c., &c. And in the *Longford Case*, 2 O'M. & H., 15. which, though a case of treating and not of bribery, we think, stands upon the same principle, it was distinctly laid down, "the treating of non-electors may be illegal and corrupt just as much as the treating of voters." And see, also, the *Wallingford Case* (1 O'M. & H., 58); the *Tamworth Case* (1 O'M. & H., 86; 20 L.T., 181; and the *Southampton Case* (1 O'M. & H., 224).

Is distribution of money to non-electors bribery?

In the *Stafford Case* (1 O'M. & H., 230; 21 L.T., n.s., 210), it was proved that at the Christmas before the election the sitting member, through his agent, distributed £720 in charity. At the corresponding period of the year before—when the election was more distant—he only distributed £300 in this way. The election was avoided on other grounds, but in giving judgment the present Lord Blackburn said: "I do not for a moment mean to say that there may not be many excellent charities distributed to these amounts and more by many people, but where I find that charities are distributed in a borough by those who are expecting to contest it as candidates, and distributed, without check, by the election agent of the borough, I am not charitable enough to draw any other conclusion than that they do it with the intention of giving the voters money in the hope and expectation that it will influence the future election. And there is the further very great danger attending

*Stafford Case.*

Bribery  
cloaked as  
charity.  
*Windsor Case.*

it, that the knowledge that they may have been doing it will cause men at the future elections to give their votes in the expectation and hope that they will hereafter receive payment. When that is brought home to any one, I think it would undoubtedly mean corruption."

In the second *Windsor Case* (2 O'M. & H., 89; 31 L.T., n.s., 133) *some long time* before the election, and upon the occasion of distress caused by a flood, the respondent gave away about £100 *among his tenants*, some of whom were voters and some not, and who paid him altogether about £3,000 a year in rent. This money was spent in coals, beef, and tea, and the respondent, on being asked whether, when he made these gifts, he had in view the election for the borough hesitated to say that to a certain extent he had not. Mr. Baron Bramwell held that, under the circumstances, the gifts were not corrupt. He said: "It is certain that the coming election must have been present to the respondent's mind when he gave away these things. But there is no harm in it if a man has a legitimate motive for doing a thing, although in addition to that he has a motive which, if it stood alone, would be an illegitimate one. He is not to refrain from doing that which he might legitimately have done on account of the existence of this motive, which by itself would have been an illegitimate one. If the respondent had not been an intending candidate for the borough, and yet had done as he has done in respect of these gifts, there would have been nothing illegal in what he did, and the fact that he did intend to represent Windsor, and thought good would be done to him, and that he would gain popularity by this, does not make that corrupt which otherwise would not be corrupt at all." These remarks of his lordship have given rise to a good deal of discussion, and while some judges have expressed their approval of them, others have thought they were too wide, and calculated to mislead candidates into acts which would be held corrupt. The decision itself is probably sound enough, for it is to be observed (1) That the money was given a long time before the election; (2) upon a legitimate occasion;

Remarks of  
Bramwell, B.



(3) that it was given merely to the respondent's tenants, from whom he received a large rental, and (4) the amount was not great.

In the *Carrikerfergus Case* (3 O'M. & H., 90,) Baron Dowse read the passage from the judgment of Lord Bramwell in the *Windsor Case* that we have given and said that he quite approved of it.

Approved in  
*Carrikerfergus*  
*Case*.

The *Boston Case* (2 O'M. & H., 161) is a very important one in this connection. There it was proved that the respondent, who lived in the neighbourhood of Boston and had been in the habit of giving largely to the local charities through the medium of other persons, and of entrusting sums of money to the clergy to distribute among the poorer classes, in the December preceding the general election of 1880 directed his agent to distribute 150 tons of coal among the poor of Boston. As a matter of fact, this was within a few weeks of the dissolution of Parliament; but the learned judge said he was of opinion that the respondent did not know that the election was imminent. The person to whom the respondent entrusted the distribution of the coal had cards printed with these words on them, "Please deliver                      cwts. of coal to                      for Thomas Parry (the respondent), B. B. Dyer, (the agent), and on the back of the cards the words "With Mr. Parry's compliments." The cards were distributed among the electors and non-electors of Boston, and the coals were obtained upon them. Mr. Justice Grove held, that having regard to the circumstances under which the charity was conferred there was on the part of the respondent's agent an intention to influence the votes of the recipients. His lordship said, "It has been over and over again held that an unfair and improper donation with the view, motive, and intention of securing a vote is corrupt within the meaning of the Act of 1854. It might be a doubtful question (and it is one which was discussed in the *Windsor Case*) whether assuming two motives to exist, the one being pure and the other with the intention to corrupt, you could exclude the corrupt intention and rely wholly upon the pure intention. I think that must

*Boston Case*.

Distribution  
of coal on eve  
of election.

Judgment of  
Mr Justice  
Grove.

be rather a question of degree. A man may wish to be charitable in a neighbourhood, but at the same time he may have an eye to his own interests, and there must be in fact some limiting line, incapable of being defined in words, where the two things come to a nearly equal balance. We know, for instance, that persons looking forward to be candidates for Parliament are generally pretty liberal to the charities in the district, and such liberality, so far as I am aware, has never been held to vitiate the election." His lordship then proceeded to say that if it had been known that Parliament would be dissolved upon the 26th of January, and these gifts of coal had been made on the 14th of January with that knowledge, he would have had great difficulty in holding that the respondent was not personally guilty of bribery. He thought, however, that at the time he did not think the election was imminent, and though his agent had carried out the dispensing of the charity in a way which showed that he meant to influence votes and the seat must be forfeited, yet he would refrain from reporting the respondent as guilty of personal bribery.

Charities  
when bribes.

*Plymouth Case.* In the *Plymouth Case* (3 O'M. & H., 107) it was proved that the respondent ever since he was returned as member was in the habit of sending to the mayor and other persons in the borough sums of from £250 to £500 to be distributed among the poor. These gifts were usually made on occasions like that of the marriage of one of his children, and they were made in other districts with which the respondent was connected as well as Plymouth. One such distribution was made in 1874 and another in 1876. On the election being called in question, in 1880, it was argued that the gifts were merely colourable charity and were intended to influence votes. The court (the late Lord Justice Lush and Mr. Justice Manisty) refused to draw any such conclusion from the evidence. They said they were of opinion that the respondent was a man of large-hearted benevolence whose disposition was to share his large means among the poor and needy of the places with which he was connected, and that in making these gifts he acted from a laudable sense of duty. But at

the same time the learned judges stated distinctly that charitable gifts may be nothing more than a specious and subtle form of bribery, a pretext adopted to veil the corrupt purpose of gaining or securing the votes of the recipients, and "if this is found to be the object of the donor it matters not under what pretext or in what form, to what persons, or through whose hands the gift may be bestowed, or whether it has proved successful in gaining the desired object or not."

The *Wigan Case* (4 O'M. & H., 14) is one in which treating, rather than bribery, under the pretext of charity, was suggested; but the following remarks made by the present Lord Justice Bowen are of general application—"Charity at election times ought to be kept by politicians in the background. No doubt the distress was great in Wigan at the time, and there was, probably, many a fireless and breadless house throughout the town, but the persons who ought to have relieved the distress were not the politicians of Wigan; they ought to have stood aloof, they had another duty to discharge on that day, and they could not properly discharge both duties on the same day. In truth, I think it will be generally found that the feeling which distributes relief to the poor at election times, though those who are the distributors may not be aware of it, is really not charity, but party feeling following in the steps of charity, wearing the dress of charity and mimicking her gait."

*Wigan Case.*

Remarks of  
Bowen, L. J.

The second *Salisbury Case* (4 O'M. & H. 21) is the last authority on the subject. There it was proved, that very shortly after the election the respondent distributed £100 to be spent in coals and blankets among the poor; but it was also proved, that after the election of 1880, when he was defeated, he gave a similar gift, and that it was a tradition in the borough for each of the members to give £100 a year for distribution among the poor. On these facts the court (Mr. Baron Pollock and Mr. Justice Manisty) held that the fair inference to be drawn was, that the gift was not given with the intention of corrupting the minds of future voters, or as a reward for past voting, but that it was done honestly as a matter of charity, and with the view of keeping up that

*Salisbury Case.*

Pollock, B., doubts dictum of Bramwell, B., in *Windsor Case*.

sort of good feeling which it is desirable should exist between the rich and the poor. Mr. Baron Pollock referred to the dictum of Lord Bramwell in the *Windsor Case* already quoted and remarked: "If it were necessary to consider this as a new matter, I am not quite sure that I should be prepared to go so far as Lord Bramwell went in that proposition. I should prefer, myself, to say we must take the whole of the evidence into consideration, and consider whether the governing principle in the mind of the man who gave such gifts was, that he was doing something with a view to corrupt the voters, or whether he was doing something which was a mere act of kindness and charity."

Result of the authorities.

We have set out the authorities on this subject at some length, but we think at no greater length than the difficulty and importance of the question discussed warrants. The conclusions to be deduced from the cases, it is submitted, are as follows:—

1. *Bonâ fide* charitable benefactions in a constituency which a person represents, or aspires to represent, do not constitute bribery.

2. But benefactions made under the colour and name of charity, with the view of influencing the votes of the recipients, or other persons through them, are bribes.

3. What was the motive of the donor in each case is a question of fact to be determined by the court from an examination of all the evidence. But, in determining such fact, attention must be paid to the time when with reference to the election the gifts were made, the habit and practice of the donor with regard to charities elsewhere and before he became a candidate, even to the traditions of the constituency, and to the amount of the gift. If the distribution of charity is made shortly before an election, a strong presumption of a corrupt motive arises (the *Boston Case* and the *Stafford Case*, quoted *supra*); if, on the other hand, it is made some time before, there is no such presumption (the *Plymouth Case* and the *Windsor Case*, quoted *supra*).

Section 2 of the 17 & 18 Vic. c. 102 (already quoted) makes it bribery for any person, directly or indirectly to

The motive of the donor the test.

make any gift, loan, offer, promise, procurement or agreement to or with any person in order to induce such person to *procure* or *endeavour to procure* the return of any person to Parliament or the vote of any voter at any election, "provided always that the aforesaid enactment shall not extend or be construed to extend to any money paid or agreed to be paid for or on account of any legal expenses *bonâ fide* incurred at or concerning any election." This provision, which is substantially a re-enactment of a statute of George III., was probably primarily devised to strike against corrupt arrangements by which patrons of close boroughs sold their influence in them. But it would seem to have a larger scope than this, and to make it an act of bribery to pay or promise anything to any person (though a stranger to the borough) with a view of securing that person's assistance or influence in the election unless such payment was in the nature of "legal expenses *bonâ fide* incurred at or concerning the election." The only case in which this section has come before any of the judges was the *Coventry Case* (1 O'M. & H., 97; 20 L.T., n.s., 405). In that case there were two respondents, and it was proved that there was an agreement between them by which one of them agreed, in the event of the other consenting to stand in conjunction with him, that he would pay all his expenses. The latter had previously contested the constituency and, it was said, was popular in it. It was suggested that this promise to pay his election expenses if he would stand in conjunction with the other was within the section. Mr. Justice Willes said that the question for him was, whether the one respondent intended by this promise to purchase the influence of the other in the constituency or was the promise merely made with the view of serving the party. His lordship came to the latter conclusion, and refused to avoid the election; but his language was very precise as to the operation of the section in a case which really comes within it. "It would be bribery in the case of the person who gave, as well as in the case of the person who received the benefit, and if the respondent E agreed to give the

To pay for  
influence  
bribery.

*Coventry Case.*

Judgment of  
Willes, J.

respondent II £5, I may say a farthing in point of law—if he agreed to give him anything, if only a peppercorn, for the purpose of purchasing any influence which the respondent II had with the electors of Coventry, and of advancing the respondent II's interest as a candidate at the election." This case is an authority that an agreement by one candidate to pay the expenses of another is not necessarily a bribe, but it may be one.

The last sub-section of the 17 & 18 Vic. c. 102, s. 2, makes it bribery to advance or pay any money *with the intent* that such money should be expended in bribery or to knowingly pay any money in repayment of any money, wholly or in part, expended in bribery at any election. This provision in no way strikes at subscriptions towards defraying the expense of any particular candidate or of candidates belonging to a particular party. Such subscriptions are very common. They have never been called in question and in the *Belfast Case* (1 O'M. & H., 285; 21 L.T., 475) Baron Fitzgerald intimated an opinion that they were perfectly legal and constitutional.

There are cases in the reports of the proceedings before election committees where the latter have held that the fact of a bet made by a voter on the event of an election invalidates his vote and necessitates its being struck off on a scrutiny. It is difficult to understand these decisions on the facts as presented in the meagre reports preserved. But, apart altogether from authority, it would seem on principle that if the court is satisfied that a bet or wager made by a candidate or any one of his agents is merely a corrupt contrivance to influence a voter, and to induce the voter to cast his vote in one direction or another, or to abstain from voting, this would seem to be bribery which will defeat the election. (See "Cunningham on Elections," p. 152.)

Subscriptions  
towards ex-  
penses of  
candidates  
legal.

Wagers may  
be bribes.

## SECTION II.—TREATING.

Treating is the second of those corrupt acts which, if committed by a candidate or any one of his agents, will

avoid the election. Various statutes from the 7 & 8 Wm. III. c. 4, onwards have prohibited the giving of meat, drink and entertainment with the view of influencing votes, and there are innumerable cases where the seat has been forfeited for corruption of this description. Those statutes were all repealed by the Corrupt Practices Act, 1854 (the 17 & 18 Vic. c. 102), which in its fourth section enacted as follows:—

“Every candidate at an election who shall corruptly by himself, or by or with any person, or by any other ways and means on his behalf, at any time, either before, during, or after any election, directly or indirectly give or provide, or cause to be given or provided, or shall be accessory to the giving or providing, or shall pay, wholly or in part, any expenses incurred for any meat, drink, entertainment or provision, to or for any person, in order to be elected, or for the purpose of corruptly influencing such person, or any other person to give or refrain from giving his vote at such election, or on account of such person having voted or refrained from voting at such election, shall be deemed guilty of the offence of treating, and shall forfeit the sum of £50 to any person who shall sue for the same, with full costs of suit; and every voter who shall corruptly accept and take any such meat, drink, entertainment or provision shall be incapable of voting at such election, and his vote, if given, shall be utterly void and of non-effect.”

Old definition of treating.

And by the joint operation of the Act of 1854, section 36, and the 46th section of the 31 & 32 Vic. c. 125, the election of any person who was guilty by himself or his agent of treating was avoided. Section 23 of the Act of 1854 made it an illegal act, rendering the person guilty of it liable to a penalty of 40s. (though the seat was not affected), to give any meat, drink, &c., to any voter on the nomination day or the polling day.

Treating avoided the election.

Section 1 of the Act of 1883 repeals Section 4 of the Act of 1854, and by Section 66 of the same Act the 23rd Section is also repealed, and in lieu of the provisions of the old law the following section is substituted: “Whereas, under Section 4 of the Corrupt Practices Act, 1854, persons other than can-

Definition of treating in Act of 1883.

didates at parliamentary elections are not liable to any punishment for treating, and it is expedient to make such persons liable; be it, therefore, enacted: Any person who corruptly by himself, or by any other person, either before, during, or after an election, directly or indirectly, gives or provides, or pays wholly or in part the expense of giving or providing, any meat, drink, entertainment or provision to or for any person, for the purpose of corruptly influencing that person, or any other person to give or refrain from giving his vote at the election, or on account of such person, or any other person having voted or refrained from voting, or being about to vote, or refrain from voting at such election, shall be guilty of treating.

“And every elector who corruptly accepts or takes any such meat, drink, entertainment or provision shall also be guilty of treating.” (Section 1.)

It is submitted that although the verbiage of section 1 of the Act of 1883 differs considerably from section 4 of the Act of 1854 there is no material alteration in the definition of the offence of treating. The latter includes in its definition the causing to be given or provided meat, &c., but inasmuch the former forbids the giving or providing directly or indirectly of any meat, &c., and it is a principle of law that a man does that himself which he does through another it would seem that the words of section 1 are comprehensive enough to include every Act in this connection which the repealed section was directed against. Again, section 4 of the old Act contained the words, “or shall be accessory to the giving or providing.” Those words are omitted from section 1, but evidence that a candidate knew that meat, &c., was to be given and consented to the giving, which would constitute him an accessory, would also be evidence that he actually gave it within the meaning of section 1. Towards the end of the definition given in section 1 some words are added which are not in section 4. It is treating to give . . . on account of such person *or any other person* having voted. The words in italics are new, and they somewhat enlarge the sweep and scope of the description of the offence. But subject to the minor variations we have men-

No material alteration between old and new definition.



tioned, the old definition of treating is preserved, and substantially all that the legislature has done is to bring within the penalties annexed, classes of persons who before escaped them.

Definition of  
treating in  
Act of 1883.

It will be noted that in the definition of treating contained in the Act of 1854 the word "corruptly" is introduced. "Every candidate who *corruptly*, &c. . . . is guilty of treating." This word is preserved in the definition given in the Act of 1883, "any person who *corruptly*," &c., &c. No such qualifying word occurs in the definitions of bribery given in the Act of 1854 and incorporated into the new Act. There has been a good deal of discussion as to the precise effect which ought to be given to this word "corruptly," and the extent to which it distinguishes the liability of a candidate for the act of giving a glass of beer from his liability for the act of giving a shilling. However, it is now well settled that the word "corruptly" in this connection does not mean wickedly, or immorally or dishonestly or anything of that sort, but with the object and intention of doing that which the legislature plainly means to forbid. (See judgment of Willes, J., in *Cooper v. Slade*, 6 H.L. Cases, 747; 27 L.J., Q.B., 449; and the *Bewdley Case*, 1 O'M. & H., 19; 19 L.T., n.s., 676.) "In fact, giving meat or drink is treating when the person who gives it has an intention of treating—not otherwise; and in all cases where there is evidence to show that meat or drink has been given, it is a question of fact for the judge whether the intention is made out by the evidence, which in every individual case must stand upon its own grounds, and although each individual case may be a mere feather's weight by itself and so small that one would not act upon it, yet if there is a large number of such cases, a large number of slight cases will together make a strong one; and consequently it must always be a very important inquiry what was the scale, the amount and the extent to which it was done." (Per the present Lord Blackburn in the *Bewdley Case*, *supra*.)

Meaning of  
the word  
"corruptly."

Remarks of  
Lord Black-  
burn.

The essence of the offence of treating is the *intention* with which the meat or drink is given. If it is given with an

Essence of  
offence of  
treating.

intention to influence a vote, that is treating, and the effect upon the election is exactly the same as the effect of a bribe, subject to the possibility of the Court granting relief under Section 22 of the Act of 1883, in the circumstances to be presently discussed. "Whenever a candidate," said the present Lord Blackburn, in the *Wallingford Case* (1 O'M. & H. 59), "is either by himself or by his agents in any way accessory to providing meat, drink, or entertainment for the purpose of being elected, with an intention to produce an effect upon the election, that amounts to corrupt treating. Whenever, also, the intention is by such means to gain popularity, and thereby to affect the election; or, if it be that persons are afraid that if they do not provide entertainment and drink to secure the strong interests of the publicans and of the persons who take drink whenever they can get it for nothing, they will become unpopular, and they therefore provide it to affect the election—when there is an intention in the mind either of the candidate or his agent to produce that effect, then I think that it is corrupt treating. But everything is involved in the question of intention, and it becomes important to see what is the amount of the treating. The statute does not say or mean that it shall depend upon the amount of the drink. The smallest quantity given with the intention will avoid the election. But, when we are considering, as a matter of fact, the evidence, to see whether a sign of that intention does exist, we must, as a matter of common sense, see on what scale and to what extent it is done."

The test is the intention.

Distinction between bribery and treating.

There is one obvious distinction between bribery and treating in regard to the light in which evidence of the giving of money and drink should respectively be viewed. As soon as it is proved that money was *given*, only one of two inferences is possible—it is either a case of charity or a bribe. But when it is proved that drink or meat has been *given*, you are not driven to either one or other of these alternatives, because it is common knowledge that good fellowship, and friendly relations, and the customs of the country lead to an interchange of treating between persons

where both charity and bribery are out of the question. Therefore, it may be said that, as a rule, it requires stronger evidence of an intention to influence the vote in a case where the thing given is meat or drink, than where the thing given is money or some other valuable consideration.

It will be observed that, in the statutory definitions of treating, it is not made an offence to *offer*, or *promise*, or *agree to give* meat, etc. Still, it is right to remind the reader that to offer, promise, or agree to give any valuable consideration is bribery (see *Kidderminster Case*, 2 O'M. & H., 366); therefore, it is doubtful whether the omission of these words from the statutory definition really adds anything to the protection of candidates.

To offer  
drink, &c.,  
not treating

But may be  
bribery.

As in the case of bribery, so in that of treating, it is not necessary that the meat or drink should be given directly to the voter whose vote it is sought to influence. Drink given to women with the view of influencing their husbands, brothers and sweethearts, was, in the *Tamworth Case* (1 O'M. & H., 80), held to be treating, and so in the *Longford Case* (2 O'M. & H., 15), the treating of non-electors was held to be within the statute; and, in the *Wallingford Case* already quoted, Lord Blackburn seemed to intimate that treating of all classes with a view to obtaining popularity, would avoid the election, though, as to the latter proposition, it must be stated that in a later case (the *Louth Case*, 3 O'M. & H. 161), Baron Dowse expressed a contrary view.

Treating need  
not be direct.

It has been stated already that bribery at a municipal election may be construed to be bribery at a parliamentary election held shortly afterwards, and the same principle exactly applies to the case of treating. See the *Hastings Case* (1 O'M. & H. ; 21 L.T., n.s., 234), when, though, on the facts before him, Mr. Justice Blackburn did not think that the treating at the municipal election in any way influenced the parliamentary contest, yet he clearly intimated that if it had had such an effect the seat would have been forfeited. Equally, treating at a test ballot to determine which of three candidates shall be accepted as the nominee of the party, is as fatal to the election as

Treating at  
municipal  
may affect  
parliamentary  
election.

bribery on a similar occasion. (*Britt v. Robinson*, 5 L.R., C.P., 503 ; 39 L.J., C.P., 265 ; 23 L.T., n.s., 188 ; 18 W.R., 866.)

Treats  
given at time  
of registration.

Again, just as payments made to persons in respect of their loss of time attending the Registration Court may be bribery, so treats of meat and drink to persons who attend the court to support their votes may be treating affecting the election "when its object is to procure popularity and votes at the Parliamentary election." (Per Blackburn in the *Hastings Case*, 21 L.T., n.s., 234.) On the other hand, if it is shown that the treating has reference merely to the proceedings in connection with the registration, it will not affect the election, as where a supper is held to celebrate a triumph at the Revision Court, and the entertainment is paid for by the sitting member or his agent. This was held in the *Coventry Case* (1 O'M. & H., 106) not to affect the election.

In the course of the discussion of the law relating to bribery, it was pointed out that prior to the Act of 1883 the fact of employing and paying voters in connection with the election was not necessarily bribery. The question in every case was—Were the persons *bonâ fide* employed and paid a fair sum? If they were it was not bribery, though if they voted their votes would come off on a scrutiny. On the other hand, if they were only colourably employed, and really paid in order to secure their votes, this was bribery which avoided the election. It was also pointed out that the importance of the distinction is a great deal diminished by the new Act, which makes it an illegal practice defeating the election for a candidate or his election agent to employ and pay any persons (over and above the limit allowed in the schedule) in connection with the election.

Refreshments  
to voters.

There is authority for saying that a similar distinction prevailed with regard to refreshments given to voters who were employed in the promotion of the election, and it is submitted that the distinction still prevails. The distinction is this—Meat and drink given in moderation by a candidate to persons (whether paid or not) who were really engaged in the work of the election was not, and it is submitted is not,

corrupt treating. On the other hand, meat and drink given to persons who do no real service in connection with the election, though as a cloak and screen they may be called committeemen and canvassers, will be regarded as corrupt treating. The law on this point was clearly laid down by Baron Martin in several cases in 1869, and his statement of it has never been judicially questioned.

Refreshments  
to voters.

In the second *Bradford Case* (19 L.T., n.s., 723; 1 O'M. & H., 35), it was proved that on the polling day refreshments were provided in the committee rooms for all the persons who were necessarily there for the purposes of the election. Those persons were voters, but inasmuch as they were all partizans honestly engaged in the work of the election, his lordship held that there was no treating to secure their votes.

So in the *Westminster Case* (1 O'M. & H., 90; 20 L.T., n.s., 236) the same learned judge held that providing refreshments on the polling day for persons *bonâ fide* engaged in the work of the election, was not corrupt treating.

The present Lord Blackburn, in the *Wallingford Case* (1 O'M. & H., 58; 19 L.T., n.s., 766) apparently had the distinction present to his mind when without in any way impugning it, he said it would be very much better if candidates left their agents and those who were working gratuitously in their behalf to provide their own refreshments. And, indeed, it is obvious that a candidate who is consenting to any supply of refreshments during the course of an election is treading upon perilous ground, and unless the very greatest prudence is exercised he may be hopelessly committed by some one of the numerous subordinates whom he must employ in such a case.

A dangerous  
practice.

The grosser forms of treating are where public-houses are opened, as it is called, and persons, whether voters or not, allowed to go in and out and drink or eat what they want with little limit imposed. This was what happened in the *Youghal Case* (21 L.T., n.s., 306; 1 O'M. & H., 291), where it was proved that crowds of electors and non-electors were gratuitously supplied with drink at the bar of the hotel

Opening  
public-houses.

Opening  
public-houses.

in which the respondent's committee met, whenever they asked for it. So in the first *Bradford Case* (19 L.T., n.s., 720; 1 O'M. & H., 33) Baron Martin held that it was proved that the respondent opened 115 public-houses in the borough, and in these houses all persons who came there and went through the farce of having their names put down as committeemen were supplied with drink. In the *Bewdley Case* (1 O'M. & H., 16; 19 L.T., n.s., 676) it was proved that a large number of public-houses—about 20—were habitually open during the election, that whoever went in there, got drink as he wished, and that all the drink was ordered and controlled by a clerk of the respondent's agent. The judge was clearly of opinion that this treating invalidated the election. There are many other cases where the seat has been forfeited where treating has been carried on on a similar scale. Indeed, where such general and widespread treating as this is established, the election is in deadly peril at common law apart altogether from proof that the corruption was the act of the respondent or his agent.

Amount of  
drink, &c.,  
given  
generally  
immaterial.

It cannot be stated too precisely that when once the court is satisfied that meat or drink was given with the corrupt intention of influencing a vote, the offence of treating is complete, utterly regardless of the amount of drink given. The authorities establishing this proposition are substantially consistent from the *Westbury Case* in 19 L.T., n.s., 24, to the *Wigan Case* (4 O'M. & H., 13). This position is further fortified by section 22 of the Act of 1883, which contemplates that treating may be of a trivial, unimportant, and unlimited character, and so far as the seat is concerned gives relief in such cases, only under stringent conditions.

Giving drink,  
&c., to voters  
may *not* be  
treating.

On the other hand, there are many cases in the books where it has been clearly proved that meat and drink has been given to voters by a candidate or his agent, and yet the election has been upheld. These cases all go on the principle, which is a perfectly sound one, that the giving of the meat and drink is not in itself corrupt treating; it is giving it with the intention of influencing the vote which makes the offence. In the cases we mention the court has con-

sidered all the surrounding circumstances, and come to the conclusion, *as a fact*, that the candidate or his agent did not mean to affect the votes of the recipients of his or their hospitality. See the *Louth Case* (3 O'M. & H., 161), where all the cases on this point are carefully collated and discussed by Baron Dowse.

It is clear that treating *before* an election, with a view of influencing it, is as much an offence as treating *at* the election. (The *Fouhal Case*, 21 L.T., n.s., 317). Whether treating *after* an election will invalidate it depends upon whether or no the treating was in pursuance of any arrangement, express or implied, made during the course of the election. The leading authority on this point is the *Brecon Case* (2 O'M. & H., 43). There it was proved that after the election an entertainment was given by the mother of the respondent, but with his knowledge and concurrence, to a large number of persons, among whom were many who had voted for the respondent at his election, and some who had voted against him. It was not, however, proved that this entertainment had been mentioned or even thought of until the election, was over, neither was it proved that any such entertainment had ever been given before, or that it was intended thereby to influence the voters at a future election. The learned judge (the late Lord Justice Lush) upheld the election. In giving judgment, he said: "In what then does corrupt treating after the election consist? It is easy enough to state what would be corrupt treating before the election. Indeed, the Act itself defines it, but what is that ingredient which must enter into the treating in order to make it corrupt with reference to an election which is over and past, and when it can no longer influence the voting, or have any effect upon the election. I do not agree that treating with a view to attach the voters to the candidate, and secure their future support, is within this branch of the section. Treating for such a purpose may peril the future election which it is designed to influence, but we are now dealing with a past election, and the treating charged is, therefore, a proceeding which reflects back and taints that by-gone election. Nor

Treating after  
an election.

*Brecon Case.*

Judgment of  
Lush, L.J.

can it be merely giving an entertainment as an expression of gratitude, or by way of rewarding the voters. So to hold, would be to give no meaning to the word 'corruptly,' for the Act says that the offence shall consist, not in the giving meat, drink, &c., to a voter 'on account of his having voted,' but the doing so corruptly on account of his having voted. I am, therefore driven to the conclusion that the treating which the Act calls corrupt, as regards a by-gone election, must be connected with something which preceded the election, must be the complement of something done or existing before and calculated to influence the voter while the vote was in his power. An invitation given before to an entertainment to take place afterwards, or even a promise to invite, or a practice of giving entertainments after an election, which it may be supposed the voters would calculate on, would, if followed up by the treating afterwards, give to it the character of corrupt treating."

The test is, was there a promise express or implied *before*.

It will be seen that the learned judge intimated that a practice of giving entertainments after an election which the voters might be supposed to calculate upon, might be equivalent to a promise made during an election, so as to make the subsequent treating corrupt. This very point arose in the *Poole Case* (2 O'M. & H., 123), and was decided by Mr. Justice Grove in accordance with Lord Justice Lush's opinion. There it was proved that after the election there was considerable treating of voters by the respondent's agents. No previous promise was suggested, but it was proved that after the last election, at which the respondent was also a candidate, a great deal of drink was given away by his agents, and the learned judge held that, having regard to what took place then, there was a tolerably clear understanding among the voters of Poole, that drink would be distributed as soon as the poll was over. His lordship fully adopted the doctrine of the *Brecon Case*, in cases where it was proved that the entertainment was given on a spontaneous rejoicing.

Implied promise of a treat.

It is thus reasonably clear that the hospitality of a member after an election, if entirely unconnected with any ex-



press promise before or previous conduct from which a promise can be implied, will not amount to corrupt treating and avoid the election. Hospitality before an election, admits to some extent of different considerations. There is no law to prevent a man being hospitable in the place he aspires to represent; but if the court is satisfied that he dispenses his hospitality with a view of securing votes, he comes within the statute. It is entirely a question of intention; and each case must stand upon its own bottom. In the *Windsor Case* (1 O.M. & H., 3; 19 L.T., n.s., 613) it was proved that the respondent was in the chair at a dinner of a non-political society—the Oddfellows—some two or three weeks before the election began. He ordered champagne to be served to all the persons present, many of whom were voters, and he paid for it. The question was whether, under the circumstances, this was an act of corrupt treating. Mr. Justice Willes held it was not. He described it as a “questionable” proceeding, and as being of an “objectionable” character, but acting upon a decision of an election committee, he, apparently with some reluctance, upheld the election. The election committees on this point drew a distinction which is not very intelligible. In the *Pontefract Case* (W. & D., 71) the respondent stood a quantity of drinks at a dinner of the Oddfellows, and the committee held that this was not treating within the Act, as the society, at whose dinner he gave the treat, was not a political one. The *Maidstone Case* (W. & D., 104), on the other hand, is an authority that exactly similar treating, at the dinner of a political society, would be corrupt treating. We confess we cannot understand the distinction. If anything, treating at the dinner of a non-political society is likely to be more pernicious, and have a greater effect upon the election. In the one case, the candidate is treating partizans, whose votes in nine cases out of ten, are already secured. In the other case, he is treating persons, many of whom have no fixed views, and who are peculiarly open to influences of the kind. It must be carefully noted with reference to the *Windsor Case*, that it is

Hospitality.

Standing  
drink at  
public dinner.

merely a decision upon the facts. It lays down no principle of law, and it is no authority for saying that a candidate can, with impunity, dispense gratuitous drink or meat on the eve of an election.

Amount of treating material where relief sought under Section 22 of Act of 1883.

It has been already stated, that the quantity of meat or drink given, where the corrupt intent is made out, is immaterial, so far as the offence of treating is concerned; but the quantity of the meat or drink given is most material in the connection we have now arrived at. Judges have again and again expressed their sense of the hardship of the law which compelled them to unseat a member who had done his best to conduct his election purely, but who had been committed by some trifling act of bribery or treating done by an agent. Until the Act of 1883 they had no option in the matter. Now by the 22nd section of that Act, a certain limited power is given them in the class of cases which come within the section. It is desirable that we should set out the full text of the section before we offer any comments upon it.

Election court has now power to support election where treating trivial.

“When upon the trial of an election petition, respecting an election for a county or borough, the Election Court report that a candidate at such election has been guilty by his agents of the offence of treating, and undue influence and illegal practice, or of any such offences in reference to such election, and the Election Court further report that the candidate has proved to the Court:—

And when the other conditions of Section 22 of Act of 1883 are complied with.

“(a.) That no corrupt or illegal practice was committed at such election by the candidate or his election agent, and that the offences named in the said report were committed contrary to the orders, and without the sanction or contrivance of such candidate or his election agent; and

“(b.) That such candidate and his election agent took all reasonable means for preventing the commission of corrupt and illegal practices at such election; and

“(c.) That the offences mentioned in the said report were of a trivial, unimportant, and limited character; and

“(d.) That in all other respects the election was free from any corrupt or illegal practice on the part of such candidate, and of his agents,

then the election of such candidate shall not, by reason of the offences mentioned in such report, be void, nor shall the candidate be subject to any incapacity under this Act.”

A glance at this section is sufficient to show that the indulgence it permits is so hedged round with restrictions and limitations that it cannot have any general or wide application. It has no application to any act of *bribery*, or to any act of *personation*, though the bribe given be never so trifling in amount, and though there be every circumstance of extenuation in the case. But it does apply to treating, and this curious result may follow. To promise a glass of beer as an inducement for a vote is bribery. To actually give a glass of beer is treating. If it is proved that an agent of a candidate (not being his election agent) *has given* a glass of beer, and if the other conditions of Section 22 are satisfied, the Court cannot unseat the sitting member. But if it is proved that the agent merely *promised* a glass of beer, has the Court any power to relieve from this trifling act of bribery? It is submitted it has not.

Section applies to treating but not to bribery.

Assuming, however, that the act or acts in respect of which the candidate wishes relief, under Section 22 is or are acts of treating merely, which is the only subject with which we are now concerned, the candidate is not entitled to such relief unless he proves (1st) that the said acts were not done by *himself* or *his election agent*; or (2nd), with his or the election agent's knowledge or consent, and (3) that he and his agent took all reasonable means to prevent the commission of corrupt and *illegal practices*; (4) that the acts in question were committed contrary to his orders and the orders of his election agent; (5) that in all other respects the election was free from any corrupt or *illegal practice*, and (6) that the acts in question were of a trivial, unimportant and limited character.

What the respondent must prove to obtain relief.

## SECTION III.—UNDUE INFLUENCE.

The offence of undue influence is thus defined by Section 2 of the Act of 1883 :

Definition of  
undue  
influence.

“Every person who shall, directly or indirectly, by himself or by any other person on his behalf, make use of or threaten to make use of, any force, violence or restraint, or inflict, or threaten to inflict, by himself or by any other person, any temporal or spiritual injury, damage, harm or loss upon or against any person in order to induce or compel such person to vote or refrain from voting, or on account of such person having voted or refrained from voting at any election, or who shall, by abduction, duress, or any fraudulent device or contrivance, impede or prevent the free exercise of the franchise of any elector, or shall thereby compel, induce or prevail upon any elector either to give or to refrain from giving his vote at any election, shall be guilty of undue influence.”

The corresponding section under the old law was Section 5 of the Corrupt Practices Act, 1854, which was almost identical in terms, but the words “temporal and spiritual” are new, and the general words “in any other manner practise intimidation” and “or otherwise interfere with” the free exercise of the franchise, are omitted. These modifications do not appear to alter the law.

Antiquity of  
the law.

This portion of the law is as old as Parliament itself. By 3 Edw. I. c. 5 : “Because elections ought to be free, the king commandeth, under pain of great forfeiture, that no great man nor other *by force of arms nor by malice or menacing*, shall disturb any to make free election.” A vote, to be a good vote, must be freely given, and the question whether a man gives a free vote is much the same as the question whether a man has made a free will (*Windsor*, 1 O’M. & H., 6 ; 19 L.T., 43).

“The proper definition of that undue influence” which was dealt with in 17 & 18 Vic. c. 102, s. 5, is using any violence or threatening any damage, or resorting to any

fraudulent contrivance to restrain the liberty of a voter so as either to compel or frighten him into voting or abstaining from voting otherwise than as he freely wills (*Lichfield*, 1 O'M. & H., 25; 20 L.T., 11). Yet the statute leaves entirely untouched influences which operate upon the mind of a voter and coerce him in the exercise of his franchise *without any act being committed* on the part of the person from whom the influence emanates. For example, a shopkeeper fears to incur the displeasure of profitable customers, a workman fears to incur the displeasure of his employer, a tenant fears to incur the displeasure of his landlord, and they will be influenced by these considerations although neither the landlord nor the employer nor the customer either intends or threatens, or does any act of injury whatever in consequence of the exercise of the franchise (*Down*, 3 O'M. & H., 136).

Silent and  
legitimate  
influence

"The law cannot strike at the existence of influence. The law can no more take away from a man who has property, or who can give employment, the insensible but powerful influence he has over those whom, if he has a heart, he can benefit by the proper use of his wealth, than the law can take away his honesty, his good feeling, or any other qualities which give a man influence with his fellows. It is the abuse of influence with which alone the law deals. Influence cannot be said to be abused because it exists and operates" (Per Willes, J., *Lichfield*, 1 O'M. & H., 22; 20 L.T., 11).

Legitimate influence might be unduly used although no injury were actually done or threatened in so many words. At Lichfield, a very influential person, who was a magistrate, a poor law guardian, a town councillor, and a trustee of several local charities, stationed himself in the yard in front of the polling place and there exhorted and persuaded poor voters coming to the poll, and ticked off their names on the register. His servant, who was also there, on seeing an elector come up wearing adverse colours, cried "We will remember him another day." No other persons but special constables were allowed in the yard. The Court was of

Illegitimate  
canvassing.

opinion that that exceeded the bounds of legitimate canvassing and reprehended it, but, with some doubt, declined to avoid the election (*Lichfield*, 3 O'M. & H., 136).

The "undue influence" clause is to be read by the light thrown upon it by the "bribery" clause, and that which it would be bribery to promise the enjoyment of it is intimidation to threaten the deprivation of (*Westbury*, 1 O'M. & H., 52).

"Bottling"  
voters.

The use of "force, violence or restraint," or a threat to use it, to prevent the free exercise of the franchise, is rare. Either under the first, or under the concluding words of the section, would be included the practice of making voters drunk in order to prevent their voting, shutting them up, driving or sending them away from the polling place with a like object, or, as was done in some old cases, taking out voters to Norway under the pretence that they were being taken to the place of polling. Any such act done by any agent avoids the election (*North Norfolk*, 1 O'M. & H., 236; 21 L.T., 264).

Undue in-  
fluence by  
landlords.

The case becomes more difficult when the act charged is the utterance of a threat to inflict some temporal or spiritual injury in order to influence the voter or because he has voted or refrained from voting, but an ambiguous act may generally be interpreted by surrounding circumstances.

The law does not strike at the legitimate influence of any person. Thus, where a nobleman said to a number of his tenants: "If you can vote for my friend, Captain T., I shall be delighted if you will do so. If you cannot vote for him, at all events stay at home and do not vote against him." Mr. Justice Keogh brushed aside a suggestion that any resolution of the House of Commons could make it illegal for a peer so to interfere in an election, or make law at all, and continued: "It would be a sorry day for this country (and for none more than for the tenant class themselves) if landlords, noblemen or gentlemen, were entirely shut off from the exercise of that legitimate influence which a landlord has a right to use" (*Galway*, 2 O'M. & H., 55). It is to be noted

that in that case it was not suggested that the nobleman in question evicted or threatened to evict or injure any recalcitrant tenant. So where it merely appeared that all Mr. M.'s tenants who were in arrear with their rent had voted as he asked them to do, the seat was not affected. "The mere fact of a person having influence and intentionally retaining it is not alone evidence of unduly exercising that influence" (*Windsor*, 1 O'M. & H., 6; 19 L.T., 43). A case much nearer the line was the second *Windsor Case* (2 O'M. & H., 88; 31 L.T., 133). There it was proved that the respondent had evicted a number of his tenants after the election of 1868 because they had voted against him, but it was not proved that this conduct did, as a fact, influence any elector at the election of 1874, which was the one in question. Nor, so far as can be gathered from the reports, does it seem that the respondent went to his tenants in 1874, saying, "I want you to promise me." Bramwell, B., declined to unseat the respondent, because it was not proved that the threat which was practically held out to the tenants in 1868—that if they voted against their landlord in future they also would be evicted—was operative in 1874. Probably it would have been otherwise if in 1874 the respondent had canvassed his tenants. That would have been equivalent to saying, "I have come to ask for your vote and if you don't give it you had better remember what happened in 1868." The learned judge marked his disapproval of the respondent's conduct by depriving him of the costs of the petition, but admitted that there was a legitimate mode of influence, and that a landlord having a choice between two tenants—one agreeing with him in politics and the other not—might properly select the person agreeing with him.

A threat  
must be  
operative.

Landlords  
may choose  
their tenants.

The result seems to be that a landlord or his agent (*North Norfolk*, 1 O'M. & H., 237; 21 L.T., 264) may canvass his tenants and exhaust every argument in order to persuade them to vote as he wishes, provided that he neither inflict nor threaten to inflict any injury upon any tenant who holds out. If the tenant became such on his promise to vote for his landlord's party, it would be exceedingly dangerous for the land-

lord in canvassing him to remind him of his promise (*Petersfield*, 2 O'M. & H., 94).

Undue influence by employers.

Undue influence by employers is often difficult to prove, when it takes the form of dismissal after the election, on account of the workmen having voted, as it may be suggested that the dismissal was for some other reason. At *Westbury* (1 O'M. & H., 50) the employer told his workpeople, "No man shall remain in my employment who votes for L.," and afterwards dismissed some of his workpeople who voted for L., after promising not to vote at all. It was ingeniously but vainly suggested that they were dismissed because of their untruthfulness in voting after promising not to vote and not because of their political opinions. The wrongful dismissal by an employer of a single voter from his employment shortly before an election, upon the ground of his political opinion, is evidence of intimidation (*Blackburn* 1 O'M. & H., 203; 20 L.T., 823). But where an employer has a mixed motive for dismissing his man, when he has a reason for getting rid of him apart from his politics, is the employer bound to abstain from discharging him merely because an election is at hand? At *Blackburn, supra*, Willes, J., thought not, but recommended employers so acting to preserve clear evidence of the non-political ground for dismissing the workman (*North Norfolk*, 1 O'M. & H., 241; 21 L.T., 264). When the majority of the workpeople in certain mills, just before the election, drove out some of the minority who held unpopular opinions and prevented them from continuing their work, the masters looking on and not attempting to interfere, the election, agency being proved, was avoided (*Blackburn, supra*).

Undue influence by workmen.

Withdrawal of custom.

The case of withdrawal of custom stands upon the same ground. A man may deal with a tradesman because he is of the same political opinions, and not because he sells commodities cheap or good. But to withdraw, or to threaten to withdraw, custom from a tradesman because of his voting or not voting is using undue influence (*North Norfolk*, 1 O'M. & H., 241; 21 L.T., 204; *North Durham*, 2 O'M. & H., 159; *R. v. Barnwell*, 5 W. R., 557). There



are some observations of the present Lord Blackburn made in the first case to the effect that the loss threatened or inflicted by the withdrawal of custom must be a substantial loss. "It must be so serious that one could direct a jury in a criminal court to find that a person was guilty of misdemeanour." The tendency of the law during the last 15 years has been, however, to increased stringency, and no one could be recommended to presume upon the chance of these *dicta* being adopted. In election matters the maxim *de minimis non curat lex* seldom applies.

It has been held to be intimidation to threaten a dissenting minister to give up a pew in his chapel if he will not vote as his congregation or any one of the congregation desires him to do (*Northallerton*, 1 O'M. & H., 168; 21 L.T. 113).

The limits of the exercise of spiritual influence by ecclesiastics and others have never been very exactly fixed, and while the subject was under debate in Parliament it seemed to be assumed that a great deal must be left to the common sense of the election court. But it is not too much to say that threats of spiritual harm uttered by an ecclesiastic will be viewed more seriously than when uttered by one layman to another. Yet even the clergy may exercise their legitimate influence. It is not unlawful for a body of clergymen to meet together to select a candidate (*Longford*, 2 O'M. & H., 14), nor for any clergyman to canvass for his favourite candidate. But he must not, either in dealing with members of his flock or with any elector, use the influence which his position confers upon him, in the words of Sir S. Romilly in *Huguenin v. Baseley*, 14 Ves. 273, "with such an engine to work upon the passions, to excite superstitious fears or pious hopes, to inspire, as the object may be best promoted, despair or confidence, to alarm the conscience by the horrors of eternal misery, or support the drooping spirits by unfolding the prospect of eternal happiness, that good or evil, which is never to end." A priest may, said Fitzgerald, J., at *Longford* (2 O'M. & H., 16), "counsel, advise, recommend, entreat, and point out the true line of moral duty and explain why one candidate should be preferred to another." All that is

Spiritual  
intimidation.

merely advice and argument. But “he must not hold out *hopes of reward here or hereafter*, and he must not use threats of temporal injury, or of disadvantage, or of *punishment hereafter*. *He must not*, for instance, *threaten to excommunicate*, or to withhold the sacraments, or to expose the party to any other religious disability, or *denounce the voting for any particular candidate as a sin*”—per Fitzgerald, J., *supra*. And Keogh, J., at *Galway County* (2 O’M. & H., 47), declared that if the meanest freeman who crawled about the town were shown to have been refused the rites of the church by an agent of the sitting member on account of his vote or the vote of any one of his family, the election would have been avoided instantly.

These principles are not confined to Ireland. They are of general application. It cannot be doubted that if any clergyman or ecclesiastic, whether of the established church or of any dissenting community, were to threaten his flock generally or any elector with the refusal of any rite of the church or that his (the ecclesiastic’s) influence would be exerted to prevent the election to any office in the church (as churchwarden, deacon or elder) of any person who should not vote in a particular way, or were, in sermons or otherwise, to speak of voting in a particular way as a sin, he would be guilty of using undue influence, and, if he were an agent of the candidate returned, the election would be avoided. Spiritual intimidation is an offence easily committed, and as an election court in considering whether it has been committed looks at the surrounding circumstances, it will be much safer, in the conduct of an election, to abstain from using any church or chapel for the purpose of a place for political meetings or for any other purpose connected with an election, especially as any such practice might supply a link necessary to the chain of proof of agency.

Attempts to  
intimidate.

“A mere attempt on the part of an agent to intimidate a voter, even though it were unsuccessful, would avoid an election” (Willes, J., at *Northallerton*, 1 O’M. & H., 168; 21 L.T., 116). If an agent were to bring a mob into a town to terrify hostile electors, or were to exhort a mob

not to allow hostile voters to vote, the election would be avoided, although it may not be shown that the rioting or violence prevailed to such an extent as to prevent the election being entirely free. (*Staleybridge*, 1 O'M. & H., 72; 20 L.T., 75; *Stafford*, 1 O'M. & H., 228; 21 L.T., 210; *North Norfolk*, 1 O'M. & H., 240; 21 L.T., 264.)

But if there is no act done after a threat, but the case rests on a threat alone, although that makes no difference in law, the election court will require to be satisfied that the threatening words were serious and deliberate, intended to affect the vote, and not merely a hasty expression by an angry man. (*North Norfolk*, 1 O'M. & H., 240; 21 L.T., 267, per Blackburn, J.) Hasty words.

As to "fraudulent devices or contrivances used" to impede or prevent the free exercise of the franchise, it would seem that these words would cover an agreement by A to pair with B, A intending all the while to vote, and voting accordingly. (See *Northallerton*, 1 O'M. & H., 169.) Possibly also an agreement by a paid agent, who cannot vote, to pair with an elector, who is ignorant of the former being a paid agent, would be within the section. And it would be a "fraudulent device" to issue cards of instruction for voting, marked with a cross opposite one candidate's name, and stating that any other mark would invalidate the vote, if the Court should think that the cards were *intended* to mislead ignorant voters, but not otherwise. (*Gloucester*, 2 O'M. & H., 60.) Whether it was "undue influence" for an agent to advertise that the ballot was a sham, and that he would be able to ascertain how each elector voted, and to distribute among the electors 10,000 copies of a newspaper containing an article taking the same view was a question on which Fitzgerald, B., and Barry, J., differed. (*Down*, 3 O'M. & H., 122.) As the voting of some electors would certainly be different according as the voting was to be secret or open, it is certainly not easy to understand on what grounds it can be said that such a contrivance does not "impede or prevent the free exercise of the franchise." Then as such a statement is untrue and calculated to mislead ignorant voters, surely it is fraudulent? Fraudulent devices.

Relief against  
consequences  
of undue in-  
fluence.

Undue influence is one of the offences against which, on an election petition, relief may be granted by the Court, upon the conditions already stated in dealing with the subject of treating. (*See* the Act of 1883 sec. 22.)

#### SECTION IV.—PERSONATION AND ABETTING PERSONATION.

Personation  
defined.

The offence of personation or of aiding, abetting, committing, or procuring the commission of the offence of personation is a corrupt practice and felony, and if committed by any candidate or agent of a candidate will avoid his election. (Sections 3 and 5 of the Act of 1883.) The offence is defined by the Ballot Act 1872, sec. 24: "A person shall for all purposes of the laws relating to Parliamentary and municipal elections, be deemed to be guilty of the offence of personation who at an election for a county or borough or at a municipal election, applies for a ballot paper in the name of some other person, whether that name be that of a person living or dead or of a fictitious person, or who having voted once at any such election applies at the same election for a ballot paper in his own name." It would seem that the offence is not committed if the person voting or attempting to vote, *bonâ fide* and upon reasonable grounds of belief, but erroneously, believes that he is the person entitled to vote; nor would it be committed if an agent, who instigated another to vote, in a similar way and on similar grounds, erroneously believed the person instigated to be entitled to vote. If an agent should instigate the commission of the offence it would seem that the election would also be bad at common law. (*Coventry*, 1 O'M. & H., 100; 20 L.T., 495.) If B, who is entitled to vote, chooses to be called Z and so votes, that does not vitiate his vote. (*Wills's Case*, 20 L.T., 310).

Where there were two persons named R, one of whom was on the register and the other voted—it was held that this was an act of personation, and the vote was struck off. (*Rothwell's Case*, 20 L.T., 314; *Clark's Case*, 44 L.T., 290.) If they had both been on the register, although

in respect of the same premises, both might have voted. (20 L.T., 315.) The offence is complete upon the *application* for a ballot paper being made.

#### SECTION V.—A FALSE DECLARATION.

Section 33 of the Act of 1883 requires the election agent of the candidate to transmit a true return of the election expenses to the returning officer within a time specified. This return must be accompanied by two declarations, one made by the candidate, and the other by the election agent, in the forms set forth in the schedule, in effect stating that the return is a true one, and that the sums mentioned in it are the only sums which have been paid in connection with the election. The nature of the return and declaration are fully discussed in Chapter VII. Sub-section 7 of the 33rd Section provides : “ If any candidate or election agent *knowingly* makes the declaration required by this section falsely, he shall be guilty of an offence, and on conviction thereof, on indictment, shall be liable to the punishment for wilful and corrupt perjury ; *such offence shall also be deemed to be a corrupt practice within the meaning of this Act.*” And being a corrupt practice it avoids the election.

A false  
declaration  
a corrupt  
practice.

## CHAPTER II.

## ILLEGAL PRACTICES WHICH AVOID THE ELECTION IF COMMITTED BY ANY AGENT.

Such illegal  
practices four  
in number.

These are four in number. Three are contained in Section 7 of the Act of 1883, and one in Section 28; and by Section 11 of the Act of 1883, if the Election Court reports that candidate at any election has been guilty by *his agents* of any illegal practice “in reference to such election, that candidate shall not be capable of being elected to or sitting in the House of Commons for the said county or borough during the Parliament for which the election was held, and if he has been elected, his election shall be void.”

Section 7 is as follows:—

Section 7 of  
Act of 1883.

“(1.) No payment, or contract for payment, shall for the purpose of promoting or procuring the election of a candidate at any election be made,

“(a.) On account of the conveyance of electors to or from the poll, whether for the hiring of horses or carriages, or for railway fares, or otherwise; or

“(b.) To an elector on account of the use of any house, land, building, or premises for the exhibition of any address, bill, or notice; or

“(c.) On account of any committee room in excess of the number allowed by the first schedule to this Act.

“(2.) Subject to such exception as may be allowed in pursuance of this Act, if any payment or contract for payment is knowingly made in contravention of this section either before, during, or after an election, the person making such payment or contract shall be guilty of an illegal practice, and any person receiving such payment, or being a party to any such contract, knowing the same to be in contravention of this Act, shall also be guilty of an illegal practice.

Sub-section 3  
proviso.

“(3.) Provided that where it is the ordinary business of

an elector, as an advertising agent, to exhibit, for payment, bills and advertisements, a payment to or contract with such elector, if made in the ordinary course of business, shall not be deemed to be an illegal practice within the meaning of this section."

The first offence consists (whether to an elector or not) in actually paying, or contracting to pay, any money on account of the conveyance of electors to or from the poll, and it is specifically stated that the offence is complete, whether the payment or contract for payment relates to the hiring of horses or carriages, or for railway fares, or *otherwise*. This is a material change upon the old law. Prior to the new Act, in *county elections* it was perfectly legal to convey electors to or from the poll in hired carriages, or to bring them from a distance by means of free passes on the railway, or otherwise; and in the case of *borough elections*, while the conveyance of voters to or from the poll in hired conveyances was legal within the limits of the boroughs themselves (43 & 44 Vic. c. 18, s. 2), any payment on account of their conveyance outside the boroughs was illegal, though it did not avoid the election (the *Bolton Case*, 2 O'M. & H., 31; L.T., n.s., 194).

Illegal to pay for conveyance of voters to the poll.

The old law on the subject.

Now, counties and boroughs are placed upon exactly the same footing, and not only is the conveyance of electors at the candidate's expense to or from the poll in *hired conveyances*, or upon the railway, made illegal; but when any agent of the candidate makes any payment, or contract for payment, with a view to their conveyance, the election is avoided. So far as regards payments made for railway fares this is reasonably clear; but with reference to the effect of entering into a contract to secure carriages and horses for the conveyance of voters to the poll, the wording of a later section of the Act, raises a nice question. Section 14, sub-section 1, forbids any person to *let*, lend, or employ for the conveyance of voters to or from the poll, any carriage, horse, or animal, *which he keeps or uses for the purpose of letting out to hire*, and the second sub-section goes on: "A person shall not *hire*, borrow, or use for the purpose of the conveyance of electors to or from

Contract with livery stablemen for conveyance of voters.

The effect of a contract with livery stablemen for conveyance of voters.

Sections 7 & 14.

the poll any carriage, horse, or other animal which he knows the owner thereof is prohibited by this section to *let*, lend, or employ for that purpose, and if he does so, he shall be guilty of an *illegal hiring*." An illegal hiring is treated in the Act as a less heinous offence than an illegal practice, and does not avoid the election, unless it is committed by the candidate personally, or *his election agent*. Now, suppose a person who is held to be an agent of the candidate, though he is not the election agent, hires all the carriages and horses in the stables of a livery stableman, and uses them for the conveyance of voters to or from the poll, is he only guilty of an illegal hiring? If so, the election will stand. On the other hand, if he hires a single horse from a person who is not a livery stable keeper, he clearly comes within Section , sub-section 1, and, committing an illegal practice, the election is avoided. If this be so, the result is curious, for then, to make a contract with persons whose business it is to supply horses and carriages, and who can supply them wholesale, would *not* defeat the election, but to make a contract with other persons *would*. It can hardly be supposed that the legislature meant this, but it is open to argument that it has enacted it. Section 7 contains a merely general prohibition against entering into contracts for the hire of conveyances, and annexes a heavy penalty to any breach of it. Section 14 specifically deals with the hiring of conveyances from one class of persons, and prohibits this under a much lighter penalty. Unless the view is adopted, that the penalty under Section 14 is cumulative, and that, therefore, the persons mentioned in it are guilty *both* of an illegal practice and an illegal hiring, the only other construction is that the latter section qualifies the former, and takes the persons specifically dealt with by it out of the general words of Section 7. However this may be, it should be noted in connection with the prohibition contained in Section 7 against payments and contracts for the conveyance of voters to the polls, that sub-section 3 of the 14th Section provides that "nothing in this Act shall prevent a carriage, horse, or other animal being *let to*, or *hired*, or employed, or used by an elector, or

Proviso to sub-section 14 engrafted on Section 7.



several electors, at their joint cost, for the purpose of being conveyed to or from the poll."

The second offence consists in paying *to any elector*, or contracting to pay to him, any sum on account of the use of any house, land, building or premises, for the exhibition of any placard, &c., or on account of the exhibition of any placard, &c., with the proviso that if it is the ordinary business of an elector as an advertising agent, to exhibit placards, &c., any payment to him shall not be illegal. This section speaks for itself. It strikes at a form of corruption suggested in the *Westminster Case* (referred to at p. 14) where it was charged that the respondent sought to influence voters by paying them sums of money for the privilege of exhibiting his placards in their window or upon their shutters. That was held to be a corrupt practice only where the payment was made with the corrupt view of influencing the vote of the person who got the money; but under this section it is an illegal practice to make these payments *to any elector* without reference to the motive which dictates the payment. It would seem, however, that it is legal to pay non-electors for the right of exhibiting placards, &c., unless it could be clearly shown that by excessive payments to such persons it was sought to influence the votes of electors connected with them. Then it would probably be bribery.

Illegal to pay electors for placarding.

But not illegal in case of non-electors.

The third offence consists in paying, or contracting to pay, for any committee rooms in excess of the number allowed in the first schedule to the Act. The second part of the first schedule prescribes the number of committee rooms which may legally be paid for in the cases respectively of borough and county elections.

Illegal to pay for committee rooms in excess of number allowed.

In a borough, at least one committee room is allowed. If the number of electors exceed 500, then one extra committee room for every complete 500, and if there is a number of electors over and above any complete 500, then another committee room for such extra number. Thus where the number of electors is 1,501, it would seem four committee rooms would be allowed, and so on.

Legal number of committee rooms in boroughs.

In the case of counties, the following committee rooms are

In counties.

Committee  
rooms in  
counties.

allowed:— (1.) One central committee room; (2.) One committee room for each polling district; (3.) When the number of electors in any polling district exceeds 500 one additional committee room for every *complete* 500 electors over and above the first 500. Thus if there is a county with polling districts A, B, C, and D, and in A there are 400 electors, in B 600, in C 1,000, and in D 1,060, the committee rooms which may be legally hired will be as follows: (1.) One central committee room; (2.) One committee room in A; (3.) One committee room in B, for though there are more than 500 electors there is not a second *complete* 500; (4.) Two committee rooms in C; and (5.) Two committee rooms in D. It is important to have a clear view of the number of committee rooms which may be hired and *paid for*, because, under the section we are considering, any payment or contract for payment made in respect of any committee room in excess of the number allowed is an illegal practice which will defeat the election if made by any agent.

What is a  
committee  
room.

There is no definition in the Act of what constitutes a committee room. Is a committee room a single room or a suite of rooms? Is it an illegal practice for the election agent to have in addition to the room in which the general work of the election is conducted, another room contiguous in which he sits himself, and uses for necessary purposes of the election? The only attempt at a definition of a committee room is a negative one in the general interpretation clause, "the expression committee room shall not include any house or room occupied by a candidate at an election as a dwelling, by reason only of the candidate there transacting business with his agents in relation to such election; nor shall any room or building be deemed to be a committee room for the purposes of this Act by reason only of the candidate, or any agent of the candidate, addressing therein electors, committee men, or others." What the Act strikes at is *payment* for additional committee rooms. There is apparently no objection to a candidate using as many committee rooms as his friends are content to lend him, subject to a restriction on the premises employed as committee rooms to be presently mentioned.

Only *payment*  
for committee  
rooms illegal.

Section 28 creates another illegal practice, which, if committed by any agent, will avoid the election. It declares that no payment and no advance or deposit shall be made, whether by the candidate or any other person, before, during, or after an election, in respect of the expenses incurred on account of the election, except through *the election agent*, acting in person or by a sub-agent. There is a proviso to the effect that this section shall not apply to—(1) any payments made by the returning officer; or—(2), any sum disbursed by any person out of his own money for any *small expenses legally incurred by himself, if such sum is not repaid to him*. The design of this section is to secure the payment of all election expenses through the medium of a responsible election agent, who is bound to make a return of every farthing. No other person is now allowed to make any payment on account of them. If such a person does disburse any small sum in any way in promotion of the election it must be taken to be a gift, and he cannot recover it again from the candidate. What is “a small expense” within the meaning of the proviso has yet to be decided. It will probably receive a very strict construction, because the latter portion of Section 28 provides—“All money provided by any person other than the candidate for any expenses incurred on account of or in respect of the conduct and management of the election, whether as gift, loan, advance or deposit, shall be paid to the candidate or his election agent, and not otherwise.” Unless, therefore, the permission given in the proviso is strictly limited, it will convert Section 28 into a dead letter.

Illegal to pay election expenses except through election agent.

Proviso to this rule.

Small sums disbursed by person other than election agent gifts.

To what extent is it *possible* for a candidate to obtain relief against the consequences of an illegal practice committed by himself or an agent? One penalty of an illegal practice is—and it is the only one with which we are now concerned—the loss of the seat. Can this be averted in any case? It will be remembered that the qualified relief given under Section 22 of the Act of 1883 applies to illegal practices as well as to treating and undue influence, when they are committed by any person except the candidate

The possibility of relief.

The possi-  
bility of relief.

Under Section  
22.

personally or his election agent. Therefore, if any one of the illegal practices mentioned in this chapter is committed by any of the candidate's agents (except his election agent), relief against the forfeiture of the seat may be given under Section 22.

But the next section—viz., the 23rd—would seem to carry the *possibility* of relief still further, and even to extend it to cases where the illegal practice has been committed by the *candidate himself or his election agent*. This section is in the following terms:—

Under Section  
23.

“Where, on application made, it is shown to the High Court or to an election court, by such evidence as seems to the court sufficient:

“(a) That any act or omission of a candidate at any election, or of his election agent, or of any other agent or person, would, by reason of being a *payment, engagement, employment or contract in contravention of this Act, or being the payment of a sum or the incurring of expense in excess of any maximum amount allowed by this Act, or of otherwise being in contravention of any of the provisions of this Act be, but for this section, an illegal practice, payment, employment, or hiring; and*

“(b) That such act or omission arose from inadvertence or from accidental miscalculation, or from some other reasonable cause of a like nature, and in any case did not arise from any want of good faith; and

“(c) That such notice of the application has been given in the county or borough for which the election was held as to the Court seems fit:

and under the circumstances it seems to the Court to be just that the candidate or such election or other agent or person, or any of them, should not be subject to any of the consequences under this Act of the said act or omission, the Court may make an order allowing such act or omission to be an exception from the provisions of this Act, which would otherwise make the same an illegal practice, payment, employment or hiring, and thereupon such candidate, agent,

Provisions of  
Section 23.

or person shall not be subject to any of the consequences under this Act of the said act or omission."

When, in Chapter IV., we treat of illegal practices generally, the majority of the offences pointed at by the above section will appear; but the words "contract in contravention of this Act" seem clearly to cover the three classes of acts mentioned in Section 7, and the general words of the section are sufficient to cover the offences struck at in Section 28. If this be so, the result is that there is no case of an *illegal* practice (as distinguished from a *corrupt* practice), where the unlawful act of a candidate's agent, whether the election agent or any other agent, *necessarily* means the forfeiture of the seat. For an illegal practice committed by the election agent there is the possibility of relief under Section 23, if it is shown on application to the High Court or the Election Court that the act or omission arose from inadvertence, or from accidental miscalculation, or from other reasonable cause of a like nature, and "not from any want of good faith." On the other hand, for an illegal practice committed by an agent (other than the election agent), there would seem to be the possibility of relief both under Section 22 and under Section 23.

No case of an illegal practice where election necessarily avoided.

In the case of an application for relief made to the High Court under the latter section, the applicant is not, in so many words, required affirmatively to prove the facts which are conditions precedent to relief under the former section, but it is entirely in the discretion of the Court whether it makes an order under Section 23 or not, and it is probable that it would not do so unless the applicant satisfied it that—(a), the offences committed were of "a trivial, unimportant, and limited character;" (b), that the candidate and his election agent took all reasonable means for preventing the commission of corrupt and illegal practices; and (c), that in all other respects the election was free from any corrupt or illegal practice on the part of such candidate and of his agents.

Terms on which relief under Section 22 will be granted.

## CHAPTER III.

THE CANDIDATE'S AGENTS WITHIN THE MEANING OF  
THE RULES LAID DOWN IN CHAPTERS I. AND II.

Candidate  
always liable  
for act of his  
agent.

It has been the law from the earliest times that no matter how well a member may have conducted his election, no matter how clear his character from any imputation of corrupt practice, yet, if any agent of his has been guilty of a corrupt act, the election cannot be upheld. "The amount of the injury done by the agent is immaterial. If an agent bribes one voter with 2s. 6d., and the voter taking the 2s. 6d. with the purpose, expressed or implied, of voting accordingly, should break his promise and vote for the other side, still the election is void." (Per Willes, J., in the *Blackburn Case*, 1 O'M. & H., 202; 20 L.T., n.s., 826.) In these circumstances, the question, what constitutes a person a candidate's agent within the meaning of this rule, is obviously one of the greatest importance. It is, moreover, one of great delicacy and difficulty. Learned judges have again and again stated that it is impossible to give a precise and exhaustive definition of agency which may be safely applied to the infinite variety of cases which arise; and the legislature itself has designedly refused to attempt anything in the nature of a definition, on the ground, no doubt, that if a hard-and-fast rule were laid down the ingenuity of electioneers would soon evade it, and so the laws against corruption be made of no effect. Parliament, it is true, has in the recent Act defined accurately enough *one class* of the candidate's agents and made him liable to the very fullest extent for their acts; but it cannot be too clearly stated, that while a candidate is responsible for the acts of the agents created by and mentioned in the Act of 1883, his liability is not limited to a responsibility for their acts, and he is still liable for the misconduct of a large number of other persons whom the law in certain circumstances will regard as his agents.

Impossible to  
give precise  
definition of  
agent.

Responsibility  
not limited to  
acts of elec-  
tion agent.

It will probably be more convenient when, in a later chapter, we proceed to deal in detail with the functions of the election agent, there to set out the full text of the sections creating his office. It is sufficient to say here, that by the 24th and 25th Sections of the Act of 1883 a candidate is empowered, though not compelled, to appoint, for the purposes of the election, one election agent in each borough constituency, and, in the case of counties, in addition to the election agent, one sub-agent for each polling district. The name and address of the election agent must be declared in writing by the candidate on or before the nomination day, and it is the duty of the returning officer forthwith to give public notice of it. Where sub-agents may be appointed, the election agent is required, one clear day before the polling day, to declare in writing their names and addresses; and there is this most important provision as to the extent to which sub-agents bind the candidate in their own districts, which it is essential to remember in the present connection: "As regards matters in a *polling district*, the election agent may act by the sub-agent for that district, and anything done for the purposes of this Act by or to the sub-agent shall be deemed to be done by or to the election agent, and any act or default of a sub-agent which, if he were the election agent, would be an illegal practice, or other offence against the Act, shall be an illegal practice and offence against this Act committed by the sub-agent, and the sub-agent shall be liable to punishment accordingly; and the candidate shall suffer the like incapacity as if the said act or default had been the act or default of the election agent." The full significance of this section will be realised when we come to deal with those illegal practices which avoid the election when committed by the candidate or his election agent, because it is presumed that the effect of the above words is to make every sub-agent, *while acting within his own district*, an election agent within the meaning of the sections then to be discussed.

The election agent.

Sub-agents.

Extent of their authority in their own district

The first schedule of the new Act (Part I.) provides that except the election agent, and in the case of counties the sub-agents, and a strictly limited number of polling agents, clerks

Any number  
of voluntary  
agents may  
be appointed.

But if ap-  
pointed,  
candidate  
liable for their  
acts.

Candidate  
liable for act  
of all his  
agents.

Authority to  
canvass con-  
stitutes  
agency.

and messengers, no other persons shall be employed in connection with any election *for payment*. It is not, however, the design of the Act to prohibit the employment of *voluntary* agents to take a part in the conduct of the election ; and in that respect the law is entirely unaltered. But if a candidate or his authorised agents do appoint persons to take a part in the management of the election and depute authority to them, they make those persons, while performing the particular class of duties entrusted to them, the candidate's agents within the meaning of the rule that a corrupt practice by a candidate or any one of his agents defeats the election. The fact that the agents are not paid makes no difference whatever, for it has long been settled that a candidate is as much bound by the acts of his agents who give their services for nothing as by the acts of those who are paid. (*Bewdley Case*, 1 O'M. & H., 17 ; 19 L.T., n.s., 677.) The only question is, Have they, in fact, received authority from the candidate or some undoubted agent of his to do acts of a certain class for the furtherance of his elections? If they have, then the candidate is liable for any corrupt or illegal act which they may be led into committing while engaged in performing the particular duties assigned to them. Thus, in the common case of an organised canvass in a constituency where a number of persons are selected by the candidate, or, as happens much more frequently, by his principal agents, to canvass each district, there can be no doubt that all those persons are, by express appointment, the candidate's agents while engaged in canvassing the particular districts allotted to them (the *Dublin Case*, 1 O'M. & H., 272), for "authority to canvass constitutes a person an agent while he is canvassing, and authority for the general management of the election involves authority to canvass." (Per Willes, J., in the *Windsor Case*, 19 L.T., n.s., 613 ; 1 O'M. & H., 2 ; also the *Norwich Case*, 19 L.T., n.s., 617.)

In this connection, however, an important limitation of responsibility must be borne in mind. An agent appointed with express powers can only bind the candidate within the scope of his authority—*i.e.*, while he is actually performing (though in an improper and unlawful way) the particular



work assigned to him. An agent appointed to do work of one kind does not bind the candidate if he officiously assumes duties of an entirely different kind, and while he is doing the latter commits a corrupt act. Thus, a person commissioned to do subordinate work, as a mere messenger (whether paid or not), and having no authority expressed or implied to do anything except act as a messenger, is not an agent for all purposes so as to fix the candidate with liability for acts done by him while carrying on an unauthorised canvass. (*Windsor Case*, 19 L.T., n.s., 613; 1 O'M. & H., 2; also the *Durham Case*, 2 O'M. & H., 137.) "There are many persons who are employed at an election, and who, in one sense, are agents of the candidate, but who are not agents in the sense that the election would be considered void by their misconduct." (Per Willes, J., in *Bodmin Case*, 1 O'M. & H., 119; 20 L.T., n.s. 989.) So, when a person is asked to canvass a *particular class* of voters—as a master to canvass his workmen (*Westbury Case*, 1 O'M. & H., 47; 20 L.T., n.s., 17; *Blackburn Case*, 1 O'M. & H., 199; 20 L.T., n.s., 823), or a landlord his tenants (*North Norfolk Case*, 1 O'M. & H., 236; 21 L.T., n.s., 264), he is an agent only while he is engaged in canvassing them, and the candidate is not bound by his unauthorised acts at other times, and while canvassing other persons. Equally, where a person is authorised to canvass in a *particular district*, and there is nothing to show he had authority, express or implied, to canvass anywhere else, the candidate is not bound by his acts in other districts. (*Harwich Case*, 3 O'M. & H., 69; 44 L.T., n.s., 189; *Durham Case*, 2 O'M. & H., 136.)

Limitations  
of agent's  
authority.

But if it be shown that the agent at the time when he committed the corrupt act was engaged upon the particular kind of work assigned to him, the candidate is not exonerated from the consequences of his agent's act by merely proving that the latter in doing the corrupt act in question was acting against his express instructions and in defiance of his honest wishes. (The *Harwich Case*, 3 O'M. & H., 69; 44 L.T., n.s., 189.) This rigorous rule involves no little hardship to an honest candidate, and in this respect the liability of a principal for the act of an agent is carried

Candidate  
bound though  
agent dis-  
obeys his  
instructions.

much beyond the ordinary maxims of the common law ; but it is founded on a principle of public policy, that no election which is tainted by the corrupt act of any agent of the sitting member can stand.

Distinction  
between cases  
where candi-  
date bound  
and not  
bound.

The distinction which does exonerate a candidate, where his agent at the time he offends is acting beyond the scope of his authority, in the sense that he has assumed duties which do not belong to him, but which binds him, when the agent, while keeping within the general line of his duty, disobeys his express instructions to the extent of committing a corrupt act, as he thinks to further the candidate's interest, is somewhat fine, but is now well settled. A very simple illustration of how it works is this : A is specifically authorised to canvass street X, and he has no other authority, express or implied, to act in any other way in connection with the election. He bribes a voter in street P. The candidate is not bound. A is authorised to canvass in street X, and expressly instructed in writing by the candidate, who honestly wishes his election conducted fairly, not to commit any corrupt act. Nevertheless A, in street X, bribes, or treats, or intimidates a voter. The candidate is bound and the seat is forfeited.

When agent  
actually ap-  
pointed only  
question is  
extent of his  
authority.

So far we have dealt with the comparatively simple case, where it is proved that the persons who are charged with some corrupt act were expressly appointed by the candidate, or his authorised agents, to take some part in the election, and then the only question can be, Was the agent at the time he offended acting within the scope of his authority ? But we now come to the much more difficult and more common case in election inquiries, where there is no evidence of any direct appointment by the candidate or his authorised agents, but where the alleged agent is proved to have been more or less openly and actively working in the candidate's interest. There the question arises—Are the circumstances such that the Court can *imply* he had authority from the candidate, or has the latter approved and ratified his action on his behalf ?

Implied  
agency.

Lush, L.J.,  
upon agency.

“ The difficulty,” said the late Lord Justice Lush, in the *Harwich Case* (quoted *supra*), “ always is when there is no

express appointment, to determine whether the wrongdoer did or did not stand in the relation of agent to the candidate in respect of the particular matter of the complaint. An agent is a person employed by another to act for him and on his behalf, either generally or in some particular transaction. The authority may be actual or *it may be implied from circumstances*. It is not necessary, in order to prove agency, to show that the person was actually appointed by the candidate. If a person not appointed were to assume to act in any department of service as election agent, and the candidate accepted his services as such, he would thereby ratify the agency. So that a man may become the agent of another in either of two ways—by actual employment or by recognition and acceptance. The next question is, if agent, what is he agent for ; what is he appointed to do, or what does he profess to do ? If a person were appointed or accepted as agent for canvassing generally, and he were to bribe or treat any voter, the candidate would lose his seat. But if he were employed or accepted to canvass a particular class—as if a master were asked to canvass his workmen, and he went out of his way and bribed a person who was not his workman, the candidate would not be responsible, because this was not within the scope of his authority. And for the same reason, if a person whom the candidate had not in any way authorised to canvass at all for him were to take upon himself to bribe a voter, the candidate would not be responsible for that wrongful act. No candidate could ever secure a seat if he were made answerable for the acts of unauthorised persons.”

Agent either  
by employ-  
ment or  
recognition.

Candidate not  
liable for acts  
of unautho-  
rised persons.

“No one,” said the present Lord Blackburn, in the *Burdley Case* (1 O’M. & 17 ; 19 L.T., n.s., 677) “can lay down a precise rule as to what would constitute evidence of being an agent. Every instance in which it is shown that, either with the knowledge of the candidate himself, or to the knowledge of his agents, a person acts at all in furthering his election *is evidence*, tending to show that the person so acting was authorised to act as his agent. It is by no means essential that it should be shown that a person so employed,

Agent need  
not be paid.

in order to be an agent for that purpose, is paid in the slightest degree. And, I take it, that the question for the Court sitting to try the case comes ultimately to be, whether upon the *aggregate of all these things taken together*, of which each in itself is little, but is certainly some evidence, the person is shown to have been employed to such an extent as to make him an agent for whom the candidate would be responsible. I take it that in each case the judge must bring common sense to bear upon it, and satisfy himself whether it is sufficient or not."

Agency a question of fact.

It will be observed that the question, whether the alleged briber was the candidate's agent at the time of the offence, is treated by the learned judges entirely as a question of fact, to be determined by a reference to the circumstances of the cases before them. Such facts as proof that the alleged agent was canvassing in the candidate's interest, that he had a canvass book with him, that he spoke at the candidate's meetings, that he was seen in the candidate's company in the street, are *evidence*, but no more than evidence, that he had authority to canvass and bind the candidate.

Mere fact of canvassing not enough.

The *mere fact* that a person is actively working for the candidate does not necessarily make him an agent. "I cannot concur in the opinion that any supporter of a candidate who chooses to ask others for their votes and to make speeches in his favour can force himself upon the candidate as an agent, or that the candidate should be held responsible for the acts of one from whom he actually endeavours to dissociate himself." (*Londonderry Case*, 1 O.M. & H., 278; 21 L.T., n.s., 709. *Staleybridge Case*, 1 O.M. & H., 67; 20 L.T., n.s., 75.) The circumstance that a person canvassing on behalf of a candidate had a canvass book with him would not be sufficient to make him an agent. (The *Bolton Case*, 2 O.M. & H., 141; 31 L.T., n.s., 194) unless, of course, it could be proved he got it from an authorised agent of the candidate, which would be the strongest evidence of his appointment to canvass.

Mere fact of canvassing does not prove agency.

Nor does the *mere fact* that a person is one of a large committee whose names are published as the General

Committee, but which committee is purely ornamental and has no part whatever assigned it in the conduct of the election, make him an agent. This was first decided by the late Baron Martin in the *Westminster Case* (1 O'M. & H., 89; 20 L.T., n.s., 238), when, at the same time, he took care to point out that if the Committee, to which the alleged agent belonged, had been more than a nominal one, had been in fact a committee within the ordinary meaning of the term to which some portion of the management of the election had been confided, the decision would have been the other way. In the *Westbury Case* (20 L.T., n.s., 24), Willes, J., acted upon the *Westminster Case*, but he added "If I see a person's name on the committee from the beginning, if I find that he attended meetings of the committee, that he canvassed and his canvass was recognised so far as it went, I shall require considerable argument to convince me he is not an agent." (See also the *Windsor Case*, 2 O'M. & H., 89.)

Nor mere fact that person is one of large Committee.

Again, the bare act of accompanying the candidate on his canvass is not sufficient evidence of agency to make a candidate liable for bribery committed by such person at another time. (See judgment Hawkins, J., in the *first Salisbury Case*, 3 O'M. & H., 131; 44 L.T., n.s., 193; also *second Salisbury Case*, 4 O'M. & H., 21; *Harwich Case*, 3 O'M. & H., 69; 44 L.T., n.s., 189; *Shrewsbury Case*, 2 O'M. & H., 36.) It must be observed, however, that the recognition of a person involved in inviting him to accompany the candidate on his canvass is an important link in the chain of facts which go to make up agency, and combined with very little more would no doubt in most cases be held to establish it. It need hardly be said that any corrupt act done by a person accompanying a candidate *and in his presence* is strong evidence against the candidate unless repudiated by him at the time. (See *Salisbury Case*, *supra*; *Bewdley Case*, 1 O'M. & H., 17.)

Nor bare act of accompanying candidate.

But while the law seems to be that if a person, no matter how zealous a partizan he may be, is acting entirely of his own motion, the candidate is not bound by what he does, on the other hand, if he is found carrying on his operations in concert with the candidate's organisation, or if the Court is

What is sufficient evidence of agency.

satisfied that the candidate, or any one of his principal agents, has full knowledge of his efforts and approves and sanctions them—then he is an agent.

Is mere non-interference sufficient?

In the *second Taunton Case* (2 O'M. & H., 74), Mr. Justice Grove intimated that *mere non-interference* by the candidate with persons who were to his knowledge actively exerting themselves in his interest would not be enough to constitute agency. But this ruling must be considered with reference to the particular facts before his lordship, because the decision of the present Lord Blackburn in the *first Taunton Case* (1 O'M. & H., 181; 21 L.T., n.s., 169) shows that there are cases where *mere non-interference* with the notorious action of partizans will make the latter the candidate's agents. It is obvious that if a candidate, knowing that certain persons are actively working in his behalf, lies by, and accepting the full benefit of their services, does nothing to repudiate them, it will take a very slight additional circumstance to lead to the conclusion that he sanctioned their proceedings. Especially is this so where the persons who are so acting are proved to have been working in close concert with him in political matters immediately prior to the election. It is suggested that an intelligible distinction which will reconcile the two Taunton cases (quoted *supra*) and make them accord with the *Harwich Case* (3 O'M. & H., 6, 69; 44 L.T., n.s., 189) is this: Where the alleged agents are found in intimate communication with the candidate prior to the contest and during the contest work in his interest openly, but apparently independently, they are *prima facie* his agents unless he repudiates them; but where no privity is established between the candidate and the alleged agents either before or during the election, the mere fact that he does not repudiate them *taken by itself* will not make them his agents.

Suggested law on this point.

Cases where agency held to be proved.

In the *Teukesbury Case* (3 O'M. & H., 99; 44 L.T., n.s., 192) the alleged agent was seen frequently in the candidate's committee-room, going out of it in the company of bodies of men who divided themselves and canvassed in different districts. He had a canvass book, and on one or two occasions (though not at the times when the corrupt acts were com-

mitted) had canvassed in the candidate's company. It was held in these circumstances that his agency was established.

In the *Hereford Case* (1 O'M. & H., 195) it was proved that the person who was charged with bribery had, at the request of an agent, canvassed two voters, that on one occasion he canvassed in the respondent's company, and that after the election was over he *received a letter of thanks for his exertions from the respondent*. It was held that the agency was established.

Cases where agency held to be proved.

In the *Stroud Case* (3 O'M. & H., 11) the alleged agent was proved to have canvassed three times a week, though he did not have a regular canvass book, he was attending continually at the committee-room, and was bringing up voters on the polling day, and after the election he was employed in connection with the petition. It was proved that the respondent's principal agent had told the alleged agent that he would not employ him in connection with the election, but inasmuch as the learned judge was satisfied on the facts that other agents of the respondent, working side by side with the principal agent, had countenanced and employed him, the decision was that he was an agent for whose acts the candidate was responsible. His lordship laid down the law of agency in the terms in which it has generally been expressed. "It is clear that a person is not to be made an agent by his merely acting, that is not enough; he must act in promotion of the election, and he must have authority, *or there must be circumstances from which we can infer authority*." Here he held there were circumstances.

A person who is an agent may have implied authority to appoint sub-agents necessary to carry out the work assigned to him, and in that case the candidate is bound by the acts of those sub-agents, though he may never have seen them or had any communication with them. (*The Bewdley Case*, 1 O'M. & H., 17; 19 L.T., n.s., 677.) On this principle, when the wife of an agent bribed, it was held that inasmuch as an agent may use the instrumentality of another, the candidate was bound. (*The Cashel Case*, 1 O'M. & H., 288.) In the *Westminster Case* (1 O'M. & H., 89; L.T., n.s., 238) the son

Agent may act by sub-agent.

of an agent bribed and it was held the candidate was not bound. These two cases have been quoted in at least one work of authority as sustaining the proposition that a candidate is bound by the act of his agent's wife, but not of his agent's son. It is submitted they give no support to such a distinction. The wife as well as the son can only bind on the principle of delegated authority; and all that the two cases quoted above show is that on the facts the Court was satisfied that in one case authority had been conferred and in the other it had not.

Liability of candidate for acts of political associations.

The *Blackburn Case*.

Liable when he adopts committee of association as his election committee.

A very important question next arises, to what extent is a candidate liable for the acts of political and other associations in sympathy with his candidature, and exerting themselves to promote it. It need not be said that at the present time this is a subject of increasing interest; and its practical importance warrants some examination of the authorities. When the candidate adopts the committee of the association as his committee, avails himself openly of its organization, and carries on the work of the election in concert with it, no question can arise. In such a case the authorised agents of the association are to the fullest extent his agents. This was what happened in the *Blackburn Case* (20 L.T., n.s., 823; 1 O'M. & H., 198). There a month before the election a circular was issued by the Conservative Association, addressed to every millowner, manager and overlooker, calling upon them to use personal efforts to secure the return of the respondents. This circular was afterwards adopted by the respondents, and the association which had issued it was accepted by them in place of a committee for the management of the election. Mr. Justice Willes held that the circular must be taken to be the act of the respondents just as much as if each of them had written a letter to the same purport to the persons mentioned in it. And as to its effect he said: "It appears to me that the effect of this circular was to make an agent of every person having authority, down to the last grade, that of overlookers over the hands, and to request, and therefore authorise each such to influence the hands who were under him for the purpose of inducing them to vote for the candidates upon whose



behalf this document was issued; and any overlooker, and consequently anybody in that or any higher grade, who *bonâ fide* took up the Tory side, and who acted upon this circular, and did canvass for the sitting members, became their agent, and his acts did bind them to the extent and under the circumstances which I have already explained."

In the great majority of cases, however, the operations of the association are carried on independently of the candidate's organization; and then the material points to be considered in determining the question of agency would seem to be the previous relations of the candidate with the association, the source whence it derives its funds, and the extent or character of the connection between it and the candidate during the course of the contest.

Liability of  
candidate for  
political  
associations.

The *Westminster Case* (1 O'M. & H., 89; 20 L. T., n.s., 238) is a somewhat curious case, and, opposed as it seems to be to the current of authority, it is respectfully doubted whether it is now law. There it was proved that the alleged agent was an official of an association which had actively exerted itself in the respondent's interest. The latter had been its president, and he and his partners supplied a very large portion of its funds. During the progress of the contest the canvass books of the association (*which had been supplied by the respondent's election agent*) were compared with the canvass books kept at the respondent's committee-rooms, and there was an interchange of information in relation to the election between the two organizations. On these facts Baron Martin held that the officials of the association engaged in the election were *not* the respondent's agents. It is obvious that if this case were a governing authority on the subject there would be an open door to the most flagrant evasions of the law against corruption.

*Westminster Case.*

Submitted it  
is not law.

In the *Westbury Case* (3 O'M. & H., 78) bribery was suggested on the part of the responsible agents of a political association in sympathy with the respondent, but inasmuch, though he was invited to stand by this association, no communication whatever was established between him and it during the election, it was held that its acts did not bind him.

*Westbury Case.*

*Wigan Case.* In the *Wigan Case* (1 O'M. & H., 188; 21 L. T., n.s., 122) it was proved that *some months before the election* a sub-agent of a political association of which the respondent was a member, and to the funds of which he subscribed, was guilty of a corrupt act. It was held that there was no such privity between the respondent and the association as would avoid the election.

*Harwich Case.* The *Harwich Case* (3 O'M. & H., 69; 44 L.T., n.s., 189) is an instructive one. There it was proved that a political association (1) invited the respondent to contest the seat; (2) its committee considered and revised his election address; (3) it met during the election from time to time at rooms for which the respondent paid; and (4) several of its leading members attended him in his canvass. It was suggested that one of the latter had been guilty of bribery, and the question of the relation established between the respondent and the association became material. The Court held that the facts above stated afforded *prima facie* evidence of the agency of the association, but upon the respondent proving that at the outset of the contest he *bonâ fide* declared his determination to canvass the constituency personally without the aid of committees, and announced that determination, the ultimate decision was that the proof of agency failed. This case is an authority for the proposition that a candidate can protect himself against the misdeeds of persons whom the law would otherwise construe as his agents by taking the whole burden of the management of the election upon himself, and expressly forbidding all other persons to take any part in it upon his behalf.

When candidate takes conduct of election himself, not bound.

Turning to the cases where a candidate has been fixed with responsibility for the acts of a political association, the first case in order of time carries the liability a long way. In the first *Taunton Case* (1 O'M. & H., 181; 21 L.T., n.s., 169) it was proved that there had been formed in the borough a body called "The Conservative Association," for the purpose of conducting the registration in September, and the election in the following November; that during the election people met at the rooms of the association, and that papers and cir-

*Taunton Case.*

culars were sent out from it ; that the association canvassed actively and did all those things which would be commonly done by a committee for promoting an election, and that they were done openly and over a considerable time ; that at the time of the registration the agents of the respondent were aware of the association and acted in concert with it, and that both the respondent and his agents knew that the association was actively canvassing in the respondent's behalf. The acts of bribery suggested were, that about the first week in November and on the eve of the election, the association gave 5s. a piece to a number of voters who attended the registration in September, as a day's pay for their loss of time in so doing, and that these sums were practically paid to everyone who came forward and asked for them without precautions being taken that those who got the money had done anything to earn it. In these circumstances the learned judge (the present Lord Blackburn) held, that the association was the agent of the respondent, and the latter was unseated accordingly. "When things," said his lordship, "are thus openly done, which would not be done in the ordinary course of things, except with the cognizance of a candidate, *who sanctioned them*, the natural inference in the absence of proof to the contrary would be, that they were done by a person acting as agent for the candidate. The respondent and his agents might have shown that they *had had no communication* with that body, that they repudiated it, and if that repudiation was *bonâ fide* they would not have been responsible for its acts. The respondent might have shown that a body, acting in such a way as this body acted, was acting officiously for him, as I may call it, that it was not with his consent and against his will ; but the presumption does arise, I think, that it was done in his favour, done for him, unless there be something to show the contrary. I think, in this case, such a degree of benefit was derived from their assistance, that their assistance was so important to the candidate that it fairly establishes this, that if he took their assistance and did not hold them off, or repudiate them, he must abide the consequences and be

Liability of candidate for political associations.

*Taunton Case.*

Where *bonâ fide* repudiation, candidate not liable.

responsible for their malpractice." Lord Blackburn must not be understood as laying down as a matter of law, that when an association is acting openly on behalf of a candidate he is necessarily liable, unless he publicly repudiates it. All he held was, that having regard to the facts of the case before him, and the very intimate connection which subsisted between the candidate and the association immediately prior to the election, that there was, in the absence of evidence of repudiation, in fact, a presumption that he sanctioned what was being done. So regarded, the decision is in full conformity with the more recent *Harwich Case* already quoted.

Effect.

*Wakefield Case.*

In the *Wakefield Case* (2 O'M. & H., 102) the facts were, that the respondent was a vice-president of a political association, that he spoke at meetings of the association, that many of the members of the association were to his knowledge actively canvassing on his behalf, and that the committee-rooms of the association were placarded with his election bills, *and used for the purpose of promoting his election*. Mr. Justice Grove held that these facts *prima facie* brought the case within the law of agency and were (in the absence, of course, of evidence of *bonâ fide* repudiation) sufficient to satisfy the Court that the respondent "had put himself, or allowed himself to be in the hands of certain persons, or had made common cause with them."

using rooms of association.

*Londonderry Case.*

In the *Londonderry Case* (21 L.T., n.s., 709) the alleged briber was a principal official of the Liberal Registration Association. It was proved that the respondent was the adopted candidate of the association, and had subscribed largely to its funds. The work of registration, with the respondent's approval, had been conducted by the association, and when the revision was completed, the funds and staff of the society, with Peacock (the alleged briber) as the principal of the staff were, with the respondent's assent, used for the purpose of promoting the election. The learned Judge held upon these facts, that the respondent was clearly liable for the acts of the association.

*Gravesend Case.*

In the *Gravesend Case* (44 L.T., n.s., 64), where it was

proved that the respondent gave a political association a sum of money, large in proportion to its normal funds, and this money was spent by the association in treating. Mr. Justice Denman intimated that the agency of the association was established.

Liability of  
candidate for  
political  
associations.

The *Bewdley Case* (3 O'M. & H., 145; 44 L.T., n.s., 283.) is an important case on this subject. There it was proved: (1.) That an association had been formed before the election to promote the candidature of the respondent; (2.) That it was in constant communication with the respondent's chief election agent; (3.) That the chief election agent supplied it with minute books and communicated with its secretary as to its progress, and reported the progress of the respondent's candidature to it; (4.) That during the progress of the contest he used in common with it a marked register containing an account of the favourable, adverse, and doubtful voters. The Court (Denman & Lopes JJ.) held that the agency of the association had been established and in giving judgment the latter learned judge made the following pertinent remarks. "I desire shortly to allude to one matter, I mean the position of political associations and the liability of candidates. There appear to be persons who think that a candidate may escape the responsibility attaching to the acts of an agent by the employment of the active members of a political association, instead of an individual or individual agents; if this could be done the Corrupt Practices Act would become a dead letter. There may be, doubtless, in a borough a political association existing for the purpose of a political party, advocating the cause of a particular candidate and largely contributing to his success, yet in no privity with the candidate or his agents—an independent agency, and acting in its own behalf. To say that the candidate should be responsible for the corrupt acts of any member of that association, however active, would be unjust, against common sense, and opposed to law. There may on the other hand be a political association in a borough advocating the views of a candidate of which that candidate is not a member, to the funds of which he does not subscribe, and with which

*Bewdley Case.*

Judgment of  
Lopes, J.

he personally is not ostensibly connected, but at the same time in intimate relationship with his agents, utilised by them for the purpose of carrying out his election, interchanging communication and information with his agents respecting the canvassing of voters and the conduct of the election, and largely contributing to the result. To say that the candidate is not responsible for any corrupt acts done by an active member of such an association would be repealing the Corrupt Practices Act, and sanctioning a most effective system of corruption."

Result of the  
authorities.

The result of the cases would seem to be this : The mere fact that a political association in sympathy with the respondent is actively working in his favour does not, *taken by itself*, establish agency ; but, though there was no original request to the association to give its services, if the respondent or his principal agents, knowing what it is doing, approve and sanction its proceedings, then agency is made out. It is not necessary to show that the approval or sanction was ever given in so many words. The court will generally infer it from the fact that communications in relation to the election have passed between the respondent and the association during the contest ; and where the connection between the two was very intimate immediately before the election, and the services rendered at the latter are real and public, it may even infer it without proof of actual communication after the contest began. On the other hand, it is open to the respondent to exonerate himself by showing that he never had any connection with the association, and that it was acting officiously, or that he *bonâ fide* repudiated its action at the time.

An organiza-  
tion of the  
clergy may be  
agents.

The principles which have been laid down with reference to the responsibility, under certain conditions, of a candidate for the acts of a political association in sympathy with him apply equally to every other kind of association or combination which may espouse the cause of a candidate and render him active assistance which he accepts and adopts. In this connection the *Limerick Case* (21 L.T., n.s., 567 ; 1 O'M & H. 262) is worth consulting. There Baron Fitzgerald intimated a strong opinion that if the clergy in a given con-

stituency make the cause of a candidate their own, and if the latter represents that his cause is identical with that of the clergy, and publicly gives out that the question between him and his adversaries is whether the clergy shall be put down or raised up, and if he is accompanied in his canvass by certain of the clergy—in such a case the organisation of the clergy in the various districts of the constituency is an agency of the candidate.

Another question that presents itself is the extent to which, where two or more candidates coalesce and stand together, as it is called, the agents of the one candidate bind the other. The law on this point was laid down in the clearest terms by Lord Blackburn in the *North Norfolk Case* (1 O'M. & H., 240; 21 L.T., n.s., 264.) “It happens that in this case the respondents have stood jointly. They have chosen to what we commonly call coalesce. They united in a canvass, and, in fact, have made each an agent for the other, and they have chosen to stand or fall together; consequently if any corrupt act is shown to be done by an agent appointed by one member it will affect both. Such are the consequences of a coalition. If, therefore, a corrupt act is brought home to one, both are unable to hold their seats.” In a later case, the *Norwich Case* (2 O'M. & H., 39), it was suggested that in giving a particular bribe the agent of one of two candidates who had coalesced, gave the bribe exclusively in the interest of his immediate principal. Upon this contention Mr. Justice Keating observed: “I think if it were clearly established that Ray (the agent) had gone to a voter and, wishing to exclude the respondent, had said, ‘I give you this bribe to vote for Sir W. R., but not to vote for T., because my object is that you should not vote for T,’ it might be successfully argued that he was thereby determining the joint agency and no longer acting in the bribery as the respondent’s agent. But that has not been proved.” It may be taken therefore, that during the continuance of a joint candidature, each candidate is liable to the fullest extent for the misdeeds of the duly-authorised agent of the other. But it is otherwise with respect to acts committed by agents prior to the commence-

Agency in case of joint candidature.

Agency where joint candidature.

ment of the coalition. In the *Tamworth Case* (1 O'M. & H., 82 ; 20 L.T., n.s., 181), it was decided that joint attention to the registration by two persons, who subsequently became candidates, did not necessarily imply joint action at the election ; and in *Malcolm v. Parry* (L.R. 10, C.P., 168 ; 44 L.J., 121 C.P. ; 31 L.T., n.s., 845 ; 23 W.R., 322) the full Court of Common Pleas decided that where a candidate has been guilty of bribery through his agent, and *subsequently* to such acts of bribery another candidate coalesces with him, in ignorance of any previous corruption, and having no reason to suspect its existence, the latter is not liable by reason of the joint candidature to be unseated in respect of such acts of bribery. As to what will constitute evidence of a joint candidature, where it is denied, see the *Bridgewater Case* (1 O'M. & H., 113).

Candidate not  
liable for a  
treacherous  
agent.

It has been stated already that a candidate is liable for the acts of those persons whom the law construes to be his agents, although he has expressly forbidden them to commit any corrupt act, and though in committing it they are flying in the teeth of his honest wishes in the matter. But while this is so, it has been decided, for the necessary protection of candidates against treachery, that the candidate is not liable where the corrupt act was done by the agent with the view of betraying his principal. This is the effect of Lord Blackburn's judgment in the *Stafford Case* (1 O'M. & H., 231 ; 21 L.T., n.s., 210), when he said, "I wish to point out the distinction which I make, that according as the law stands at present, if a member employs an agent, and that agent, contrary to his wish and contrary to his direction commits a corrupt act, the sitting member is responsible for it, but where he employs an agent and the agent treacherously or traitorously agrees with the other side, then if he does a corrupt act it would not vacate the seat unless it is proved that the corrupt act was at the special request of the member himself or some untainted and authorised agent of the member, who directed the act to be done. I say if Machin was a treacherous agent he loses the power of upsetting the seat by reason of his unauthorised acts of corruption, as it would require actual proof of authority. It is a very different affair if a man, being

*Stafford Case.*



an agent, has been tricked by the other party into committing a corrupt act, he himself honestly still intending to act as agent."

The last point we need consider is this: When does the authority of an agent to bind the candidate begin and cease? Where the agent has been expressly appointed, in the great majority of cases the appointment will itself fix the time over which the authority extends. But with regard to the agency which the law will infer from active service in promotion of a candidature sanctioned by the candidate, it would seem that it begins with the rendering of the services which afford the evidence of the agency, and this whether at the time the election contest has actually begun or not (the *Youghal Case*, 1 O'M. & H., 294). Just as a candidate may himself be guilty of a corrupt act before the occurrence of the vacancy in respect of which the election is held, so is he responsible at the like time for the corrupt act of any person who in fact is his agent. (*Ibid.*) And if a person is guilty of bribery, or any corrupt act, before he is expressly or implied appointed an agent, and afterwards, the candidate, *with knowledge of his misconduct*, appoints him an agent, his appointment relates back to the corrupt act or acts so as to make the candidate responsible for them. Agency may be terminated in various ways, chief among which are the following: (1.) Express repudiation and withdrawal of authority (*Harwich Case* and first *Taunton Case*); (2.) An act of deliberate treachery on the part of the agent (*Stafford Case*, quoted *supra*); (3.) In the case of a joint candidature, where it is shown the agent of one candidate has acted solely in the interest of his principal and *against the interest* of the other candidate (*Norwich Case*, 1 O'M. & H., 10); and (4.) The termination of the election. Baron Martin first decided in the *Salford Case* (1 O'M. & H., 133; 19 L.T., n.s., 120) that the authority of an agent came to an end with the termination of the election, and that a corrupt act committed the day after the polling, did not affect the sitting member; and this decision was acted upon by Mr. Justice Willes in the *Southampton*

Commencement of agency.

When agency ceases.

When agency  
ceases.

*Case* (1 O'M. & H., 222). "The agency at the election," said the present Lord Blackburn, giving his decision to the same effect in the *North Norfolk Case* (21 L.T., n.s., 270; 1 O'M. & H., 243), "which was solely from the canvassing before the election, expires with the election."

It must be borne in mind, however, that if the bribe was given after the election, in pursuance of a promise made or an understanding arrived at *during the election*, then the act of bribery is committed at the latter period, and while the candidate is bound by the misdeeds of the agent; and of course if the act of bribery is committed even after the election by *the express direction* of the candidate, that would confer a fresh authority upon the agent, independent of his previous employment.

## CHAPTER IV.

## ILLEGAL PRACTICES WHICH AVOID THE ELECTION, IF COMMITTED BY THE CANDIDATE OR THE ELECTION AGENT.

The general provision of Section 11 of the Act of 1883 is, that any illegal practice committed by the sitting member, or any of his agents, will avoid the election. The four classes of acts dealt with in Chapter II., come under that rule. But in addition, numerous other offences are created by the Act of 1883, which the legislature has thought right to say shall only become illegal practices when committed by the candidate or his election agent, or which, through illegal practice, by whomsoever committed, only affect the validity of the election when brought home to the candidate personally, or to his election agent. Those offences are scattered with little method all over the Act. We group them together in this chapter, and for greater clearness it is proposed to divide them, as above indicated, into, first, offences which only become illegal practices when committed by the candidate or his election agent; and secondly, offences which are illegal practices *ab initio*, but which only avoid the election when committed by the candidate or his election agent.

Division of  
illegal prac-  
tices.

## SECTION I.—OFFENCES WHICH BECOME ILLEGAL PRACTICES WHEN COMMITTED BY THE CANDIDATE OR THE ELECTION AGENT.

A. Section 13 of the Act of 1883 enacts that where any person knowingly provides money for any payment which is contrary to the provisions of the Act, or for any expenses incurred in excess of the maximum allowed by the Act, or for replacing any money expended in any such payment or expenses, except where the same may have been previously allowed in pursuance of this Act to be an exception, such person shall be guilty of *illegal payment*. *Illegal payment* is

Illegal pay-  
ment.

a new term, and generally falls short of *illegal practice* ; but by Section 21 (Sub-section 2) a candidate or the election agent of a candidate who is personally guilty of an offence of illegal payment, employment, or hiring, shall be guilty of an illegal practice. Therefore, an illegal payment becomes an illegal practice when committed by the candidate or his election agent, and it avoids the election. The object of Section 13 is in keeping with the main design of the Act of 1883, which is to discourage profusion at elections, and to restrain the cost of a contest within the narrowest limits. As will be shown at greater length hereafter, a sliding scale of maximum expenditure, regulated by the number of electors and the character of the constituency, is contained in the first schedule ; and to enforce compliance with it, and other provisions of the Act directed against prodigality, Section 13 is framed. Section 8, to be presently mentioned, forbids a candidate, or his election agent, to pay or incur any expense whatever above the maximum amount allowed. The section under consideration is of somewhat wider scope. It forbids any person to do what the candidate and his election agent have already been prohibited from doing, and it also prohibits any person from providing money for any payment contrary to the provisions of this Act, though it be within the maximum allowed.

Illegal  
payment.

Illegal hiring.

Letting,  
lending or  
employing  
hackney  
carriages.

B. The first sub-section of Section 14 makes it an *illegal hiring* for any person to *let, lend or employ*, for the purpose of the conveyance of electors to or from the poll, any public stage or hackney carriage, or any horse or other animal kept or used for drawing the same, or any carriage, horse or other animal which he keeps or uses, for the purpose of letting out for hire, where he knows that the same are to be used for the conveyance of voters to or from the poll ; and by the second sub-section any person who hires, borrows or uses, for the purpose of the conveyance of voters to or from the poll, any carriage, horse or other animal which he knows the owner thereof is prohibited by this section to let, lend or employ for that purpose, is also guilty of *illegal hiring*. By Section 21, Sub-section 2, a candidate, or an

election agent of a candidate, who is personally guilty of an offence of illegal payment, employment or *hiring*, shall be guilty of an illegal practice. The prohibitions in Section 14 are threefold. It is an offence either to (1) *let* or *hire*, (2) to *lend* or *borrow*, or (3) to *use* or *employ* a horse or carriage *which is kept for the purpose of being let out to hire*. So far as regards the prohibition against letting or hiring, it has already been pointed out that Section 7, Sub-section 1, which makes it an illegal practice to make, or contract to make, any payment with or to any person on account of the conveyance of electors to or from the poll, amply provides for the mischief sought to be restrained by this section, unless it be held that the effect of Section 14 (Sub-sections 1 and 2) is to take out of the operation of the former section the class of persons mentioned in the latter. It is difficult to think this was intended. On the other hand, why were the words “let” or “hire” introduced into the section? However, this much is certain: It is, *at least*, an illegal hiring, and it may be an illegal practice for jobmasters and others who keep horses and carriages which they let out to hire to let any of them for the purpose of conveying voters to or from the poll, except under the circumstances allowed in Sub-section 3. By the latter it is enacted: “Nothing in this Act shall prevent a carriage, horse or other animal being let to or hired, employed or used by an elector, or several electors at their joint cost, for the purpose of being conveyed to or from the poll.” But for this proviso it would hardly have been safe for any jobmaster to have had a single cab on the stand on the polling day, and it would certainly have been an offence for an elector to go to the poll in a hansom at his own expense. The sub-section authorises the latter proceeding, but it is submitted that it will be an illegal act for a person who has hired a cab to pick up another elector on the way and give him a lift to the poll, unless the latter shares the cost of the cab. “Joint cost” is the expression used in the Act. There is no definition of this term given, and it seems open to doubt whether if three electors drive up to the poll in a hackney cab the failure of any one of them

Three prohibitions in Section 14.

Illegal to *hire* any hackney carriage.

Proviso as to hiring.

“Joint cost.”

to make up his quota of the fare, though he pay something, will render the whole three electors and the owner of the cab guilty of an illegal hiring. Probably if the Court was of opinion that there was a *bonâ fide* intention to share the cost, and each elector paid a substantial part of it, such a case would be held to be within the protection of the sub-section. On the other hand, if it were shown that a number of electors went together to the poll in a conveyance hired from a livery stableman, and that the fare was really paid by one or two of them, the others contributing a nominal sum, there can be little doubt that it would be held that such a case was not protected by Sub-section 3.

Illegal to *lend*  
a hackney  
carriage.

Section 14 also prohibits the *lending* of any horse or carriage which is kept for the purpose of being let out to hire. It must be observed that the general use of conveyances in connection with the bringing up of voters to the poll is not forbidden by the Act of 1883; it is the employment of *hire*d conveyance which is struck at. As a rule, a candidate or his agent may accept the loan of horses and traps from any quarter where he can get them; but this section introduces an exception to this rule. It expressly prohibits the persons mentioned in it from lending their horses and carriages. Livery stablemen are certainly within the scope of the section. No matter how keen and disinterested their partizan-ship may be, they are forbidden to lend the horses and carriages used in the way of their business for the purpose of conveying voters to and from the poll. But the section is not limited to livery stablemen. The prohibition is against lending "any carriage, horse or other animal which any person keeps or uses for the purpose of letting out for hire." Whether these words would cover the case of a person who kept a horse or trap, which he generally used for his own purposes, but which he occasionally let out for hire, may well be doubted; but it would certainly comprehend the case of a publican who, it may be, keeps a single horse and trap for the purpose of letting it out.

As a rule  
candidate  
may use  
borrowed  
traps.

Exception to  
that rule.

Illegal to *use*  
a hackney  
carriage.

The section not merely forbids the lending of a horse or carriage of the description mentioned, it also prohibits its *use*

or *employment* in the conveyance of voters to and from the poll. A horse or trap kept for the purpose of being let out for hire must not, under any circumstances, be used on the polling day to bring up voters, unless in the cases excepted by the 3rd sub-section. Thus, a job master cannot himself, or by his servants, convey voters to the booths, nor can he give a friend or acquaintance a lift. Section 48, it should be mentioned here, allows voters to be conveyed *by sea* to and from the polling place at the candidate's expense under certain circumstances. "Where the nature of a county is such that any electors residing therein are unable at an election for *such county* to reach their polling place without crossing the sea, or a branch or arm thereof, this Act shall not prevent the provision of means for conveying such electors *by sea* to their polling place, and the amount of payment for such means of conveyance may be in addition to the maximum amount of expenses allowed by the Act." The result is, that with regard to the conveyance of voters, it is still legal to carry them in *borrowed* carriages unless the carriages or horses employed are usually let out for hire; but it is in no case lawful to *hire* conveyance or any other means of carrying voters, except some means of *sea* carriage in the cases within Section 48.

Illegal to *use* any hackney carriage in an election.

Legal to pay for *sea* carriage in some cases.

C. Section 15 provides that any person who corruptly induces or procures any other person to withdraw from being a candidate at an election in consideration of any payment or promise of payment shall be guilty of illegal payment, and any person withdrawing in pursuance of such inducement or procurement shall also be guilty of illegal payment. This clause speaks for itself, and there can be little difficulty in determining the cases that fall within it. An illegal payment, it need not be repeated, becomes an illegal practice when committed by a candidate or his election agent.

Illegal to *corruptly* induce a candidate to retire.

D. By Section 16 all payments, or contracts for payments, on account of bands of music, torches, flags, banners, cockades, ribbons, or other marks of distinction are forbidden, where they are made for the purpose of promoting the return of a candidate, and all persons concerned in making such pay-

Illegal to pay for bands, ribbons, &c.

ments or in receiving them are declared guilty of an illegal *payment*. It is, perhaps, somewhat difficult to say why payments or contracts for payment on account of exhibiting placards constitute an illegal practice, and the class of payments in the section under consideration are only illegal payments; but it must be observed that the distinction is made.

Illegal to *pay*  
agents in  
excess of the  
number  
allowed.

E. Section 17 declares that no person shall, for the purpose of promoting or procuring the election of a candidate at any election be engaged or employed for *payment* or *promise of payment* for any purpose or in any capacity whatever except as authorised by the schedule of the Act, and if any person is engaged before, during or after an election in contravention of this section the person engaging or employing him shall be guilty of an illegal *employment*, and the person so engaged or employed shall also be guilty of illegal employment, if he knew that he was engaged or employed contrary to law. It becomes, therefore, material to enquire what persons can be legally employed and *paid* in connection with an election, and here care must be taken to distinguish the case of county from the case of borough constituencies.

Number of  
agents  
allowed.

Schedule I. (Part 1) in the case of *counties* allows:—

One election agent.

One sub-agent in each polling district;

One polling agent in each polling station.

One clerk, and }  
One messenger } for the central committee-room when  
the number of electors does not exceed 5,000, and  
where it does exceed 5,000, one additional clerk  
and messenger for each complete 5,000, and if  
there is a number of electors over and above any  
complete 5,000 or 5,000's, then another clerk and  
messenger may be employed for such number,  
although not amounting to a complete 5,000. In  
addition,

One clerk, and }  
one messenger } for each polling district, and when  
the number of electors exceed 500 in any polling  
district one clerk and one messenger for every

In counties.



complete 500 or complete 500's of electors, with this provision, that if there be a number over and above a complete 500, one clerk and one messenger shall be allowed for such number.

Suppose a county constituency with 11,000 voters, and polling districts A, B, C, D and E, having respectively 2,000, 3,000, 300, 700, and 5,000 voters, and twelve polling stations. It is submitted the allowance of paid agents will be as follows: The election agent, five sub-agents, twelve polling agents, three clerks and three messengers for the central committee-room; four clerks and four messengers in polling district A; six clerks and six messengers in B; one clerk and one messenger in C; two clerks and two messengers in D; and ten clerks and ten messengers in E. It may be stated here that there is a proviso in the schedule that the number of clerks and messengers so allowed in any county, may be employed in any polling district where their services may be required.

In the case of *boroughs* generally, the number of paid agents allowed is less, viz.:—

One election agent.

One polling agent in each polling station.

One clerk and one messenger for *every* complete 500 electors, and if there is a number over and above any complete 500, or complete 500's of electors an additional clerk and messenger may be employed.

Although this is the general rule with regard to boroughs, the Act specially provides that certain boroughs, viz., East Retford, Shoreham, Cricklade, Much Wenlock and Aylesbury, no doubt in consideration of the great area they cover, shall have allowed to them the provision of paid agents applicable to counties.

An illegal employment, by Section 21, is made an illegal practice when committed by the candidate, or his election agent. It must be noted that this section is merely directed against the employment of any *paid* agents in excess of the number allowed. The employment of volunteers is perfectly legal under the new law.

Illustration.

Number of paid agents allowed.

In boroughs.

Legal to employ volunteers.

F. Section 7, Sub-section 3, it has been already stated, makes it an illegal practice to *pay for* any committee-rooms in excess of the number allowed in the schedule. That section, however, did not place any restrictions upon committee-rooms which are *lent* to the candidate. The section we now proceed to discuss, viz., Section 20, does, and it adds to the restrictions upon those hired, by forbidding certain premises being used as committee-rooms, without reference to the question of whether they are lent or hired. Section 20 prohibits the *hire* or *use* as a committee-room for the purposes of an election of (1) any premises on which the sale by wholesale or retail of any intoxicating liquor is authorised by license (whether the license be for consumption on or off the premises), or (2) any premises where any intoxicating liquor is sold, or is supplied to members of a club, society, or association *other than a permanent political club*, or (3) any premises whereon refreshment of any kind, whether food or drink, is ordinarily sold for consumption on the premises, or (4) the premises of any public elementary school in receipt of an annual Parliamentary grant; provided that nothing in the section shall apply to any part of such premises which is ordinarily let for the purpose of chambers or offices, or the holding of public meetings, or of arbitrations, *if such part has a separate entrance, and no direct communication with any part of the premises in which any intoxicating liquor or refreshment is sold or supplied as aforesaid*. Any breach of this section, whether on the part of a person hiring or using any of the prohibited premises, or on the part of the person letting, is made an illegal *hiring*. The object of the greater part of the section is to discourage treating by diminishing the facilities for it. And no doubt those facilities are lessened in view of this rigorous prohibition against having committee-rooms on licensed premises, or in clubs other than *permanent political* clubs, or in any place where refreshments are sold. All hotels, inns, grocers' licensed premises, temperance hotels, refreshment-rooms, eating-houses, coffee and cocoa taverns, social, literary, or professional clubs, will come within the prohibition of the

Restrictions  
upon Com-  
mittee rooms.

Not to be  
held—

(1) On licensed  
premises,

(2) nor any  
premises  
where drink  
sold except  
political club,

(3) Or where  
refreshment  
sold,

(4) Or school-  
room.

statute. The section contains an absolute prohibition against the use of any such places as committee-rooms, and the penalty when the candidate or his election agent is a party to the breach of the law, is the loss of the seat.

SECTION II.—ILLEGAL PRACTICES WHICH ONLY AVOID THE SEAT WHEN COMMITTED BY THE CANDIDATE OR HIS ELECTION AGENT.

A. By Section 8 of the Act of 1883, no sum shall be paid and no expense incurred by a candidate at an election or his election agent in respect of the conduct and management of the election in excess of the maximum amount specified in the schedule and applicable to the particular constituency, and if any candidate or his election agent, knowingly acts in contravention of this section he is guilty of an illegal practice. It has been stated already, that one of the ways in which the Act strikes at corruption is by prohibiting profusion. This section and Section 13, given before, are auxiliary to this object, and they forbid all persons interested in the election to exceed the maximum sums allowed in the schedule. It will be observed, that by the express words of the section only the candidate or his election agent can be guilty of this particular illegal practice.

Illegal to pay anything in excess of maximum.

B. The first sub-section of Section 9 makes it an illegal practice for any person to himself vote or to induce or procure any other person to vote at an election, knowing that he or such person is prohibited from voting whether by this Act or any other Act. In view of this provision it becomes important to inquire what persons are prohibited from voting within the meaning of this section. And first as to persons prohibited by the Act itself. They are as follows :—

Illegal to vote where prohibition against voting.

(1.) “Every person who, in consequence of *conviction* or of the *report* of any Election Court or Election Commissioners under the Act of 1883, or under the Corrupt Practices (Municipal Elections) Act, 1872, or under Part IV. of the Municipal Corporations Act, 1882, or under any other Act for the time being in force relating to corrupt practices at

Persons prohibited from voting by the Act of 1883.

any election for any public office, has become incapable of voting at any election, whether a Parliamentary election or an election to any public office, is now prohibited from voting at any such election" (Section 37).

Section 37.

(2.) "Every person guilty of a corrupt or illegal practice, or of illegal employment, payment or hiring at any election is prohibited from voting at *such* election" (Section 36). It will be observed that there is a material difference between the prohibitions enacted in Sections 36 and 37. In the case of a corrupt practice, &c., committed *at* a pending election, the elector committing it comes *at once*—as soon as he is guilty of the act and before he is convicted of it—under the prohibition against voting at *such* election; but where the corrupt practice has been committed at some *other election* the prohibition does not come into operation until he has either been convicted of the offence or reported by an Election Court or Election Commissioner.

Section 36.

Paid agents  
forbidden to  
vote.

(3.) The election agent, sub-agents, polling agents, clerks and messengers authorised by the 1st Schedule, *where they are paid*, are forbidden to vote at the election (1st Schedule, Part I).

Persons prohibited by other Acts of Parliament from voting include—

(1.) Metropolitan policemen (the 10 Geo. IV., c. 44, s. 18.)

(2.) Borough constables (19 & 20 Vic. c., 69, s. 9).

(3.) County policemen (2 & 3 Vic. c. 93, s. 9), and see also last section.

Persons pro-  
hibited from  
voting by  
other Acts.

(4.) Any elector who, at or within six months before the election shall have been retained, hired, or employed for any of the purposes of the election for reward (30 & 31 Vic. c. 102, s. 11).

(5.) Any convict, until his term of punishment has expired, or he has obtained a free pardon (by the 33 & 34 Vic., c. 23, s. 2; and also at common law).

(6.) Persons under the age of twenty-one years (7 & 8 Will. IV., c. 8).

There may be other cases of statutory prohibition. The above is not given as a necessarily exhaustive list.

There are two classes of persons who, perhaps, *ought not to* vote, who apparently are not struck at by this section, viz., persons disqualified from voting by the common law of Parliament, and persons whose names are on the register though their qualification has ceased. The former class include peers of England and of Scotland, peers of Ireland, when not members of the House of Commons (*Lord Rendlesham v. Haward*, 43 L.J., C.P. 33; 9 C.P., 252), women, aliens, and probably some others; the latter include paupers and persons who have ceased to reside within the proper distance. The register, it has been held, is conclusive as to the right of the persons last mentioned to vote, and if they do vote their names cannot be struck off on a scrutiny (*Stowe v. Jolliffe*, L.R. 9, C.P. 734, 43 L.J., C.P. 265, 30 L.T. 299, 22 W.R. 946); but if persons disqualified by the common law of Parliament vote, their votes do come off on a scrutiny (*ibid*). However, it is not an illegal practice for either of the above classes to vote, nor is it an offence to induce them to do so.

Who are not prohibited from voting.

But if any one who is prohibited by statute votes, or induces anybody else who comes under a statutory prohibition, *knowing* that such person falls within any of the above prohibitions, an illegal practice is committed. The knowledge referred to must be not a knowledge of the statute which creates the disability, because every person is supposed to know the law, but a knowledge of the *facts* in relation to the person's status or past conduct which bring him within the statute. When the illegal practice mentioned in this section is committed by a candidate or his election agent, the election is avoided; but when it is committed by any other person, though he may be an agent of the candidate to bind him by any corrupt act, the election is not defeated (Sub-section 2 of the 9th Section).

C. By the 2nd sub-section of the 9th Section it is enacted that any person who, before or during an election, knowingly publishes a false statement of the withdrawal of a candidate at such election, for the purpose of promoting or procuring the election of another candidate, is guilty of an illegal practice, and if it is committed by the candidate or his

Publishing false statement of withdrawal of a candidate.

election agent, but not otherwise, the election is avoided. The essence of this offence is—(*a*), the publication of the false intelligence, knowing that it is false; and (*b*), publishing it with the object stated in the section—viz., to promote the return of another candidate.

D. “Every bill, placard, or poster having reference to an election shall bear upon the face thereof the name and address of the printer and publisher thereof; and any person printing, publishing, or posting, or causing to be printed, published or posted, any such bill, placard, or poster, as aforesaid, which fails to bear upon the face thereof the name and address of the printer and publisher, shall, if he is the candidate or the election agent of the candidate, be guilty of an illegal practice” (Section 18). This section is directed against anonymous libels, but election agents will require to take great care that every bill and placard they issue in connection with the election, no matter how innocent and businesslike it may be, complies with the provisions of the law.

E. By Section 29, Sub-section (2), it is made an illegal practice for an election agent to pay any claim against a candidate arising out of the election, which is barred by not being sent in within the time specified in the Act, and by Sub-section 4 the election agent is forbidden to pay any claim after the time specified by the Act, under the penalty of being guilty of an illegal practice. But for the protection of an honest candidate, Sub-section 6 provides that where the Election Court reports that any payment made by an election agent in contravention of this section was made without the sanction or connivance of the candidate, the election shall not be void, and the candidate shall be subjected to no incapacity. The whole duties and functions of the election agent are treated of in Chapter VII., and it will be more convenient to leave until then the fuller discussion of the circumstances under which disobedience of Section 29 on the election agent's part will constitute an illegal practice.

F. An election agent is required by the 33rd Section

Illegal to  
issue bill  
without  
printer's  
name

Illegal to pay  
election bills  
except within  
specified time.

Illegal not to  
make return

to make a return of the election expenses within a certain time, accompanied by the declaration given in the schedule. By Sub-section 6, failure to comply with any of the requirements of Section 33 is made an *illegal practice*; on the other hand, by the following sub-section, knowingly to make a false return or a false declaration is a *corrupt practice*. of expenses within specified time.

It has already been explained, in treating, in Chapter II., of the illegal practices which avoid the election when committed by any agent, that there is the possibility of relief against the consequences of such acts under Section 22 as well as Section 23 of the Act of 1883. The possibility of relief. In regard to the illegal practices described in both sections of this chapter, Section 22 has no application; but, in a proper case, the Court may grant relief under Section 23. Section 23. Candidates and election agents cannot, however, be too emphatically warned against any reckless expenditure or employment in reliance upon the chance of indulgence being extended to them under it, because, on its plain reading, it is only to apply where the slip has been the result of inadvertence or accidental miscalculation, and where the applicant has not been wanting in good faith.



## CHAPTER V.

THE EMPLOYMENT BY THE CANDIDATE PERSONALLY  
OF A CORRUPT AGENT.

The enactment on the subject.

Section 44 of the 31 & 32 Vic., c. 125, provides: "If on the trial of any election petition under this Act any candidate is proved to have *personally engaged* at the election to which such petition relates, as a canvasser or agent for the management of the election, any person, *knowing that such person has*, within seven years previous to such engagement, been found guilty of any corrupt practice by a competent legal tribunal, or been reported guilty of any corrupt practice by a Committee of the House of Commons, or by the report of the judge upon an election under this Act, or by the report of Commissioners appointed in pursuance of the Act of the Session of the fifteenth and sixteenth years of the reign of her present Majesty, chapter 57, *the election of such candidate shall be void.*"

Personal employment of a corrupt agent.

The employment of a person as agent who has within seven years of his employment been scheduled for any corrupt practice only avoids the election where the candidate, knowing that he is a scheduled person, employs him personally. That is what the section says; but the authorities establish that the word "personally" is not to be taken in a too literal sense, and that a candidate's liability is not limited to the case where he actually appoints the agent by word of mouth or by direct writing to him. The *North Norfolk Case* (21 L.T., n.s., 265; 1 O.M. & H., 238) was the first case in which this section came under discussion. There a person who had been scheduled in connection with corrupt practices at Yarmouth was proved to have taken a prominent part in the election on behalf of the respondents. He acted as chairman of a district committee; but the respondents denied that they knew he held this position, though it was admitted that one of them asked him to propose him on the

Meaning of "personally" in Act.

*North Norfolk Case.*



nomination, and he did so. The present Lord Blackburn held that the act of asking another to propose you at the election does not constitute an employment for the purpose of the management of the election, and that though an appointment as chairman of a district would be such an employment, there was no evidence that either of the respondents personally made it. His lordship, in the course of his judgment, laid down (1) that it was not necessary that the appointment should be personal in the sense that the candidate must have an interview with the agent, it was sufficient if it was proved that the appointment was made by another "with the knowledge and consent of the candidate;" (2) that the agent need not be a *paid* agent; (3) that he need not be an agent for the management of the *whole* election, it was enough if he was actually employed to manage a *portion* of it; and (4) if it were proved that the candidate had reason to believe that a scheduled person would be appointed, and wilfully shut his eyes in order that he should know as little as possible, that would be equivalent to actual knowledge.

Judgment of  
Lord Black-  
burn.

In the *Norwich Case* (2 O'M. & H., 38) Mr. Justice Keating fully adopted the construction placed upon the statute in the *North Norfolk Case*. In this case it was proved that a person who had been scheduled for bribery five years before took a public and ostentatious part in forwarding the respondent's candidature. The learned judge held that the circumstances in evidence were such that, but for the fact that the respondent was called and swore that he had no knowledge whatever of the efforts made by the alleged agent on his behalf, and that he never intended to recognise him as an agent, he would have held that the case was made out.

In the second *Galway Case* (2 O'M. & H., 196) the facts were that two years before the election the Roman Catholic Bishop of Galway was reported by an election court as guilty of a corrupt practice, viz., undue influence. It was proved that shortly before the election, the return at which was in question, the respondent called upon the bishop, who said that his hands were tied by the report of the election

*Galway Case.*

court, and that he would not have act or part in the election; at the same time, he did not conceal his approval of the respondent's candidature. The clergy of the city, who lived in the same house with the bishop, and over whom it was admitted he had the fullest control, however, met, and, adopting the respondent as their candidate, organised a canvass in his behalf. It was not proved that the canvassing was by the direct order of the bishop, but it was clear that he was aware of and fully approved it. There was evidence likewise that a letter, written by one of the clergy with the view of driving the petitioner out of the field, was revised and corrected by the bishop before it was issued. The learned judge (Mr. Justice Lawson), though he said he was satisfied that the bishop was at the bottom of the whole movement in favour of the respondent, and could have stopped the canvassing of the clergy at any moment, and though affairs were so arranged that the public were led to understand that the bishop approved of everything which was being done in the respondent's interest, did not think there had been such a personal engagement of the bishop as brought the case within the section.

It will be noted that a person scheduled for corruption is only under disability for seven years. After the expiry of that time it is no offence for the candidate to employ him in connection with the management of the election. (See the first *Galway Case*, 2 O'M. & H., 51.)

## CHAPTER IV.

### GENERAL CORRUPTION.

An election will be avoided by the existence of general bribery, general treating, or general intimidation, or undue influence, although there be no evidence whatever that the candidate returned, or any of his agents, is in any way responsible for any corrupt practice. An election must be free, and when it takes place amidst general corruption it ceases to be free, and is bad at common law, independent of any statute. General corruption.

“If there were general bribery, no matter from what fund, or by what persons, and although the sitting member and his agents had nothing to do with it, it would defeat an election, on the ground that it was not a proceeding pure and free, but that it was corrupted and vitiated by an influence which, coming from no matter what quarter, had defeated it, and shown it to be abortive.” *Per Willes, J. (Lichfield, 1 O’M. & H., 22; 20 L.T., 11); and at Bradford (1 O’M. & H., 30), Martin, B., said, “If it had been proved that there existed in this town generally bribery to a large extent, and that it came from unknown quarters, but that people were bribed generally and indiscriminately; or if it could be proved that there was treating in all directions on purpose to influence voters—that houses were thrown open where people could get drink without paying for it; by the common law such election would be void.”* It is no answer that the general corruption took place some time before the election. (*Sligo, 1 O’M. & H., 309*). In order to avoid an election for general bribery, general treating, or general intimidation, it is not necessary to show that a majority of those who polled, or a majority of the constituency was so corrupted. It is enough to show an organised system of bribery, treating, or intimidation, “spreading over such an extent of ground, and per- General bribery.  
General treating.

meating through the constituency to such an extent that freedom of election has ceased to exist in consequence.” (*Drogheda*, 1 O’M. & H., 252 ; 21 L.T., 402.) General drunkenness at or about the time of the election is cogent evidence of general treating. (*Tamworth*, 1 O’M. & H., 75 ; 20 L.T., 181. *St. Ives*, 3 O’M. & H., 13). In the *Longford Case* a considerable sum of money was spent in giving drink to non-voters, related to voters. In some cases the electors participated in these free drinks. As one witness, a publican, put it : “ Anybody might have had the drink without distinction.” The election was declared void (2 O’M. & H., 7). In the *Drogheda Case* (21 L.T. 403, 1 O’M. & H., 252), the same principle was enunciated by Keogh, J. “ Take, then,” he said, “ the case of an organised system of treating. I am speaking now of cases in which nothing could be traced to the candidate or his agents. But suppose that at the head of every street, food and drink were provided in large quantities, and places for eating and drinking opened, as to which it was known that every voter who wished to go thither, and seek for food or for drink, would receive it, provided he was on the side of a particular candidate, and that there was an organised system for the purpose of debauching the voters of a particular borough, though all the while not traceable to the member or his agents, so as to disqualify him at future elections, is it to be supposed for a moment that that organised system would not defeat the election ? ” Such a case could admit of no doubt, but we think that much less bribery or treating than the learned judge there described would be equally fatal. The test must always be, has the corrupt practice prevailed to such an extent as to affect the result of the election ? If it has, it is fatal. The observations of Willes J., in the *Tamworth Case* (1 O’M. & H., 75 ; 20 L.T., 181), do not contravene this proportion. The learned judge did not deny that the same rule applies to general treating as to general bribery. He only insisted that the treating should be shown to be operating upon the minds of the electors at the time of the poll. See the *Norwich Case* (19 L.T., 615, 1 O’M. & H., 8.) If that condition be complied with, it

What is the test.

seems that lavish treating by publicans themselves, without any reason for expecting payment, would be sufficient to avoid the election. (*Poole*, 31 L.T., 171., 2 O'M. & H., 123.)

As to general intimidation, it may perhaps, in extreme cases, be allowable to organize a band of stalwart persons to protect voters against the violence of strangers introduced by the other side; but it must always be a dangerous thing to do (*Longford*, 2 O'M. & H., 7); such a course is always to be avoided. (*Limerick*, 21 L.T., 567; 1 O'M. & H., 260.) (*Salisbury*, 4 O'M. & H., 25; *Salford*, 20 L.T., 120.) And it would be an answer to a petition that all the violence and rioting was instigated by the petitioner or his agents, 'and that the result was not affected. But where not the unsuccessful candidate but an elector complains of general rioting, it is no answer to say that the defeated party were chiefly responsible for it. (*Dudley*, 2 O'M. & H., 115.)

As to the amount of the violence and rioting, it is very material to observe the state of the poll. If it is a close poll, less violence may justify an election court in avoiding the election than would be the case if it were quite clear that the rioting and violence had not affected the result. (*North Durham*, 2 O'M. & H., 152, 31, L.T., 383.) If the rioting were local and partial, and the majority large, the election would not be set aside (*ibid*). "But where it is of such a general character that the result *may have been* affected, it is no part of the duty of a judge to enter into a kind of scrutiny to see whether possibly, *or probably even*, or as a matter of conclusion upon the evidence, if that intimidation had not existed, the result would have been different. What the judge has to do in that case is to say that *the burden of proof is cast upon the constituency* whose conduct is incriminated, and unless it can be shown that the gross amount of intimidation *could not possibly have affected the result* of the election, it ought to be declared void." (*Per Bramwell, B., at North Durham, ibid.*) And it must be declared void if it is *uncertain* whether the result was affected (*ibid.*).

General  
intimidation.

Its effect on  
the poll.

General  
intimidation

In order to affect the election, the rioting must be serious. It must be such as to deter ordinary men, of ordinary courage, from recording their votes. (*Nottingham*, 1 O'M. & H., 245. *Galway*, 2 O'M. & H., 196. *Salford*, 1 O'M. & H., 133; 20 L.T., 120).

The general rioting and violence in the *Drogheda* case were too great to allow the case to be profitably discussed. The general intimidation there went far beyond that proved in the *North Durham* case, *infra*. But the former case establishes the proposition that if voters are deterred from voting by a prevailing terror, but without undue influence being brought to bear upon them personally, the election will be declared void. It was said for the respondent in that case, that he went to voters who were opposed to him and offered to give them his escort to the poll, they being afraid to go, notwithstanding there were military and constabulary in the streets, but the Court considered that this was conclusive evidence out of the respondent's own mouth, that there was not freedom of election in the borough.

## CHAPTER VII.

## THE OFFICE AND DUTIES OF THE ELECTION AGENT.

## SECTION I.—HIS APPOINTMENT.

The Act of 1883 creates a new officer, the election agent, with difficult and important duties, upon the due fulfilment of which the validity of the election largely depends. This officer bears no resemblance to any other agent known to the law, except the agent for election expenses, created by the statute 26 & 27 Vict. c. 29, s. 2, whose duties and many others he will have to discharge. He is not to be confounded with the person who has hitherto borne the name of the election agent, meaning thereby the person to whose experience and intelligence the management and control of the election have hitherto been confided. In future, "the election agent," using the phrase in its statutory sense, may or may not be the person who plans and directs the operations of the campaign. As the election agent is to make all contracts relating to the election, and as the measure of the candidate's responsibility for his acts is greater than that for the acts of any other agent, it will be found safer, though perhaps inconvenient, to dis sever these offices in future. A candidate will be at some disadvantage who imposes upon his chief counsellor and manager the very anxious and difficult duties which the Act of 1883 thrusts upon "the election agent." If the offices should be dis severed, the person who manages the election for the candidate must do so gratuitously. He cannot be legally employed for payment. (Schedule I., Part I. and Section 17). It is proper to add that "the election agent" need not even be a solicitor, but, in view of the direct and immediate responsibility of the candidate for his acts and omissions, it can hardly be doubted that any candidate will do well to avail himself of the professional caution and legal

The election agent.

Should be a person of business habits and conversant with the law.

training of a solicitor, if he can induce a solicitor to accept the office. If the candidate choose he may be his own election agent. In that event he will have only himself to blame for any slip on the part of the election agent. But, whether he choose to be his own election agent, or to appoint some other person, it is of urgent necessity that the election agent should be a person of business habits, and of experience in the conduct of elections, and intimately conversant with the provisions of the election law.

The object of  
the legislature

The object aimed at by the Legislature in requiring the appointment of an election agent, through whose hands all money shall pass, and by whose hands all accounts shall be paid, is the regulation and diminution of election expenses. The evil of excessive expenditure at elections has been struck at by many statutes, beginning with the 7 & 8 Will. III. c. 4, which was directed against "the excessive and exorbitant expenses, contrary to the laws and in violation of the freedom due to the election of representatives for the Commons of England in Parliament, to the great scandal of the kingdom, dishonourable, and may be destructive to the constitution of Parliament." The statute, 17 & 18 Vict. c. 102, with the same view, provided for the appointment of election auditors; but the fruit being no sweeter than the tree, these were found useless; and the Act of 1883 would imply a similar condemnation upon the agents for election expenses who were called into existence by the Act 26 & 27 Vict. c. 29, and through whom all payments for election expenses, other than the candidate's personal expenses, were to be made, under pain of fine and imprisonment.

When election  
agent to be  
named.

The appointment of the election agent is regulated by Section 24 of the Act of 1883. The section does not prescribe any particular form of appointment, which should, however, be in writing; but it provides that on or before the nomination day the election agent shall be *named* by or on behalf of the candidate. As contracts relating to the election are to be made, and polling agents and clerks appointed by the election agent (Section 27), it is obviously



desirable that the election agent should be appointed and named as soon as the candidate takes the field. What will happen if the candidate should not name himself or some other person as election agent on or before the nomination day is not very clear; but any inquiry on the subject is idle, for so flagrant a violation of the Act of Parliament would involve the candidate in many difficulties and considerable danger, any payments made by him, except through an election agent, being illegal practices avoiding the election. If the candidate prefers to be his own election agent he must name himself as such, and thereupon he will be subject to the liabilities imposed by the Act on election agents, as well as to those imposed upon candidates. If a candidate be nominated in his absence, or without his consent, the election agent is to be named "on his behalf." One of the nominators or seconders had better name the election agent in such a case.

In regard to naming the election agent, it is provided by Section 24, Sub-section 3, of the Act of 1883, that on or before the day of nomination the name and address and the office of the election agent of each candidate shall be declared *in writing* by the candidate, or some other person on his behalf, to the returning officer, and the returning officer shall *forthwith* give public notice of the name and address of every election agent so declared. Notice of his appointment.

The "public notice" to be given by the returning officer is regulated by Section 62 of the Act of 1883, and the Ballot Act, 1872, Schedule I., Rule 46. He may give the notice "by advertisements, placards, handbills, or such other means as he thinks best calculated to afford information to the electors."

A candidate can only appoint one person to be his election agent; but any appointment, whether of the candidate himself or of any other person, can be revoked. If any appointment is revoked, or the election agent die before, during, or after the election, the candidate must *forthwith* appoint a new election agent, and *in writing* declare his name and address and office to the returning officer, who will imme- Changing the election agent.

diately give public notice of the fact. (Sub-section 4 of Section 24.)

Sub-agents in  
counties and  
certain  
boroughs.

In counties, but not in boroughs, except East Retford, Shoreham, Cricklade, Much Wenlock, and Aylesbury (Schedule 1, Part 1), the election agent may, and apparently nobody else may, appoint a deputy or sub-agent to act within each polling district. The number of these sub-agents is regulated by the first schedule of the Act of 1883.

Risks of  
appointing  
sub-agents.

But the wisdom of appointing sub-agents at all seems extremely doubtful when Section 25, sub-section 2 of the Act of 1883 is read by the light of the fact that the candidate is responsible, and the return may be avoided for many acts done by the election agent which, if committed by any other agents, would not affect the seat. For the purpose of avoiding the seat every sub-agent, *acting in his own district*, is placed in the position of the election agent. If a remote sub-agent should employ and pay an assistant in excess of the number allowed, or issue a bill without the printer's name appended, the candidate's seat might not be worth an hour's purchase. In such a case the better opinion would seem to be that the candidate could have no relief under Section 22 of the Act of 1883; but in some instances he might have relief under Section 23 of the Act. Section 25, Sub-section 2, enacts: "As regards matters in a polling district, the election agent may act by the sub-agent for that district, and anything done for the purposes of this Act by or to the sub-agent *in his district* shall be deemed to be done by or to the election agent, and any act or default of a sub-agent which, if he were the election agent, would be an illegal practice or other offence against this Act, shall be an illegal practice and offence against this Act committed by the sub-agent, and the sub-agent shall be liable to punishment accordingly; and the candidate shall suffer the like incapacity as if the said act or default had been the act or default of the election agent." If, notwithstanding these dangers, the candidate should direct the election agent to appoint sub-agents, and in counties it is not easy to do without them, he should satisfy himself of the caution and ability of the persons to be

The candi-  
date's liability  
for sub-agent's  
acts.

appointed, and their knowledge of the law, and the election agent *must* at least two days before the polling declare *in writing* to the returning officer the name and address of each sub-agent and his office within his district, just as in the case of the election agent himself. The returning officer will then give public notice of the appointments in the usual way.

It would seem from the language of Section 29, Sub-section 1, of the Act of 1883, that the authority of the sub-agent does not come to an end with the poll or with the return. This view is strengthened by Section 25, Sub-section 2, which places him in the position of the election agent, so far as the candidate's liability for his acts is concerned. But it would be prudent on the part of the election agent to revoke the appointment of the sub-agents as soon as the poll has closed. By Section 25, Sub-section 4, it is provided—"The appointment of a sub-agent shall not be vacated by the election agent who appointed him ceasing to be election agent, but may be revoked by the election agent for the time being of the candidate, and in the event of such revocation or of the death of a sub-agent another sub-agent may be appointed, and his name and address shall be forthwith declared in writing to the returning officer who shall forthwith give public notice of the same."

Revocation of  
sub-agent's  
appointment.

Although there is no express provision on the point, it would be well to give the returning officer immediate notice in writing of the revocation.

The election agent and sub-agents must have offices. By Section 26, Sub-section 1, it is provided that an election agent at an election for a county or borough shall have within the county or borough, or within any county of a city or town adjoining thereto, and a sub-agent shall have within his district, or within a county of a city or town adjoining thereto, an office or place to which all claims, notices, writs, summons, and documents, may be sent, and the address of such office shall be declared at the same time as the appointment of the said agent to the returning officer, and shall be stated in the public notice of the name of the agent.

Offices of the  
election  
agent and  
sub-agent.

Service of  
notices.

Service of any claim or document or notice by delivery at the office and addressed to the election agent or sub-agent, will be equivalent to personal service on the election agent or sub-agent, as the case may be, and if the agent should make himself personally liable to be sued by any person in respect of any matter connected with the election, then (Section 26) he may be sued in any court having jurisdiction in the county or borough in which the office is.

Polling  
agents, clerks,  
and mes-  
sengers to be  
appointed by  
election agent

Every polling agent, clerk and messenger employed for payment on behalf of the candidate is to be appointed, and every committee-room hired in his behalf is to be hired by the election agent, acting by himself or his sub-agent. It would not be a corrupt practice, nor apparently would it necessarily be an illegal practice, for some other person *to appoint* a polling agent, clerk or messenger, or to hire a committee-room, provided the statutory number was not exceeded; but *to pay* the person appointed or the lessor of the committee-room, except through the election agent, would be an illegal practice. And no such contract could be enforced against the candidate. Persons asked to give credit in connection with an election have public notice of the names of the persons who can pledge the credit of the candidate, and they give credit to other persons at their peril. By Section 28, Sub-section 2, it is provided that a contract whereby any expenses are incurred on account of or in respect of the conduct or management of an election shall not be enforceable against a candidate at such election, unless made by the candidate himself or by his election agent, either by himself or by his sub-agent; provided that the inability under this section to enforce such contract against the candidates shall not relieve the candidate from the consequences of any corrupt or illegal practice having been committed by his agent. The word agent in the last line means any agent, constructive or otherwise.

and to be  
paid by him.

## SECTION II.—THE NATURE AND AMOUNT OF THE ELECTION EXPENSES

The statute insists on all payments for election expenses being made by or through the election agent. The candidate may himself pay his personal expenses up to £100, and any person authorised *in writing* by the election agent may pay “any necessary expenses for stationery, postage, telegrams and other petty expenses,” but only to the amount named in the authority. Subject to these exceptions, neither the candidate nor any agent (except the election agent acting personally or through a sub-agent) may pay any election expenses, under pain of the consequences of an illegal practice, affecting the seat as well as the individual. Section 28 of the Act of 1883 provides : (1.) “Except as permitted by or in pursuance of this Act, no payment and no advance or deposit shall be made by a candidate at an election, or by any agent on behalf of the candidate, or by any other person at any time, whether before, during or after such election, in respect of any expenses incurred on account of or in respect of the conduct or management of such election, otherwise than by or through the election agent of the candidate, *whether acting in person or by a sub-agent*; and all money provided by any person other than the candidate for any expenses incurred on account of or in respect of the conduct or management of the election, whether as gift, loan, advance or deposit, shall be paid to the candidate or his election agent, and not otherwise :

All payments to be made by the election agent.

Exceptions.

Money provided to pay expenses.

“Provided that this section shall not be deemed to apply to a tender of security to or any payment by the returning officer, or to any sum disbursed by any person out of his own money for any small expense legally incurred by himself, if such sum is not repaid to him. (2.) A person who makes any payment, advance or deposit in contravention of this section, or pays in contravention of this section any money so provided as aforesaid, shall be guilty of an illegal practice.”

The candidate and the election agent ought, at the begin-

Candidate should esti-

mate his  
election  
expenditure.

What are  
election  
expenses.

What need  
not be in-  
cluded in the  
estimate.

(a) Costs of  
taking votes  
by sea.

(b) Returning  
officer's  
expenses.

ning of the election to estimate their election expenditure, and regulate the expenditure by the estimate, otherwise there will be some danger of the maximum expenditure allowed by the Act of 1883 being exceeded. But it is not to be assumed that only such expenses as are incurred after the dissolution or after the creation of a vacancy in the representation are election expenses within the meaning of the Act. The provisions of the Act limiting expenditure would be a nullity if contracts could be entered into and expenses incurred for the purpose of promoting the return of an intending candidate before the dissolution or creation of a vacancy, and no account taken of them in the return of election expenses. There is a remarkable dearth of authority upon the section of the old Act, which provided for all election expenses being returned by an expense agent. There is, however, authority for saying that, in some circumstances, even registration expenses ought to be returned as election expenses, although ordinarily they need not be (*Penryn*, 1 O'M. & H., 127), and the language of the new Act does not point to their being included in the return of the election agent. But there is no doubt that the time at which an expense is incurred is a very material consideration in deciding whether it is an election expense. It is safe to say that any expense incurred after the dissolution or the creation of a vacancy for the purpose of promoting the return of a candidate or intending candidate, is, if it is defrayed by the candidate, or is one for which he or his election agent might be sued at law by the person to whom it is incurred, an election expense. In estimating the expenses of the election, no account need be taken of the personal expenses of the candidate, or of the charges of the returning officer, nor yet of the conveyance of voters by sea, where, under Section 48, that is allowed. They have to be included in the returns made by the election agent, but they are not included in the maximum sums allowed by the Act (Schedule I., Part IV.). But it would be illegal to pay to the returning officer any larger sum than is allowed by the earlier statute (38 & 39 Vic. c. 84). The expression "personal expenses," as used with respect to the

expenditure of a candidate in relation to an election, includes (Section 64 of the Act of 1883) his *reasonable* travelling expenses, and the *reasonable* expenses of his living at hotels or elsewhere for the purposes of and in relation to the election. We think that it would be also held to include the *reasonable* travelling expenses of his family and servants, and the *reasonable* hotel expenses of his family and servants, and, perhaps, the *reasonable* hotel expenses of any guest invited by the candidate to stay with him during the whole or part of the election.

(c) Personal expenses.

The chief heads of expense to be taken account of are those indicated and limited by Schedule I to the Act, Parts I. and II. They are:—

Heads of election expenses.

- (1.) The remuneration of persons legally employed for payment: only one election agent may be employed, but in counties one sub-agent to act within each polling district, may be also employed. The number of clerks and messengers who may be employed, has already been discussed (pp. 92 and 93).
- (2.) The expenses of printing, the expenses of advertising, and the expenses of publishing, issuing, and distributing addresses and notices.
- (3.) The expenses of stationery, messages, postage, and telegrams.
- (4.) The expenses of holding public meetings.
- (5.) In a borough the expenses of one committee-room, and if the number of electors in the borough exceeds 500, then of a number of committee-rooms not exceeding the number of one committee-room for every complete 500 electors in the borough; and if there is a number of electors over and above any complete 500 or complete 500's of electors, then of one committee-room for such number, although not amounting to a complete 500.
- (6.) In a county the expenses of a central committee-room and in addition of a number of committee-rooms, not exceeding in number one committee-room for

each polling district in the county, and where the number of electors in a polling district exceeds 500, one additional committee-room may be hired for every complete 500 electors in such polling district over and above the first 500.

The number of committee-rooms allowed has already been discussed (pp. 61 and 62). It may be said here that in a borough an extra committee-room is allowed for any fraction of 500 electors, but in a county an extra committee-room is not allowed in any polling district for any fraction of 500 electors, but only for each complete number of 500 electors after the first 500.

- (7.) Miscellaneous expenses (not exceeding £200 in all), and not incurred in respect of anything prohibited by any Act of Parliament.

Prohibited  
payments.

For instance (Section 16), payments for bands, torches, flags, banners, cavalcades or ribbons are prohibited. Payments for chairing the candidate, or for horses and carriages for conveying voters, or for railway or steamboat passes, or for a right to exhibit placards, made to an elector, except to an ordinary advertising agent, or to persons to hold up their hands for the candidate at the nomination, when the show of hands was held, have also been prohibited.

The candidate and the election agent, in mapping out their expenditure, will do well to leave a margin for contingencies, otherwise they may find they have exceeded the maximum expenditure allowed by the Act and so come within the perils of Section 8 of the Act of 1883.

The maxi-  
mum expendi-  
ture.

The maximum expenditure allowed is stated in the first schedule, Part IV., to the Act of 1883. It is to be remembered that, in all cases, the candidate's personal expenses and the returning officer's charges, and the costs of conveying voters by sea under Section 48 are payable in addition. The scale is regulated by the number of electors enumerated on the register, and no deductions are to be made for dead men, double entries, or the like



The words of the Act (Schedule I., Part IV.), limiting the maximum expenditure as to boroughs are these :—

If the number of electors on the register—

Does not exceed 2,000 . . . . .	£350.
Exceeds 2,000 . . . . .	£380, and an additional £30 for every complete 1,000 electors above 2,000.

The maximum amount shall be—

Provided that in Ireland, if the number of electors on the register—

Does not exceed 500 . . . . .	£200.
Exceeds 500, but does not exceed 1,000 . . . . .	£250.
Exceeds 1,000, but does not exceed 1,500 . . . . .	£275.

The maximum amount shall be—

The words of the same schedule in regard to the maximum expenditure in counties are these :—

If the number of electors on the register—

Does not exceed 2,000 . . . . .	£650 in England and Scotland and £500 in Ireland.
Exceeds 2,000 . . . . .	£710 in England and Scotland, and £540 in Ireland; and an additional £60 in England and Scotland, and £40 in Ireland, for every complete 1,000 electors above 2,000.

The maximum amount shall be—

The following is the scale in boroughs where the candidate stands alone, and not jointly with another candidate :—

Scale in all English and Scotch boroughs and in Irish boroughs with over 1,500 electors.

Number of Electors on the Register.	Maximum amount allowed.	Number of electors on the Register.	Maximum amount allowed.
2,000 or under . . . . .	£350	11,000 to 11,999 inclusive	£650
2,001 to 2,999 inclusive	£380	12,000 to 12,999 ..	£680
3,000 to 3,999 ..	£410	13,000 to 13,999 ..	£710
4,000 to 4,999 ..	£440	14,000 to 14,999 ..	£740
5,000 to 5,999 ..	£470	15,000 to 15,999 ..	£770
6,000 to 6,999 ..	£500	16,000 to 16,999 ..	£800
7,000 to 7,999 ..	£530	17,000 to 17,999 ..	£830
8,000 to 8,999 ..	£560	18,000 to 18,999 ..	£860
9,000 to 9,999 ..	£590	19,000 to 19,999 ..	£890
10,000 to 10,999 ..	£620	20,000 to 20,999 ..	£920

and so on, adding to £380 an additional £30 for every 1,000 electors above 2,000 enumerated on the register.

This scale applies to all boroughs except to Irish boroughs having less than 1,500 electors, as already stated, and except the five boroughs, East Retford, Shoreham, Cricklade, Much Wenlock and Aylesbury.

The following is the scale in counties where the candidate stands alone, and not jointly with another candidate :—

Scale in  
counties.

Number of electors on the Register.	Maximum amount allowed in England and Scotland.	Maximum amount allowed in Ireland.
2,000 or under . . . . .	£650	£500
2,001 to 2,999 inclusive . . . . .	£710	£540
3,000 to 3,999 „ . . . . .	£770	£580
4,000 to 4,999 „ . . . . .	£830	£620
5,000 to 5,999 „ . . . . .	£890	£660
6,000 to 6,999 „ . . . . .	£950	£700
7,000 to 7,999 „ . . . . .	£1,010	£740
8,000 to 8,999 „ . . . . .	£1,070	£780
9,000 to 9,999 „ . . . . .	£1,130	£820
10,000 to 10,999 „ . . . . .	£1,190	£860
11,000 to 11,999 „ . . . . .	£1,250	£900
12,000 to 12,999 „ . . . . .	£1,310	£940
13,000 to 13,999 „ . . . . .	£1,370	£980
14,000 to 14,999 „ . . . . .	£1,430	£1,020
15,000 to 15,999 „ . . . . .	£1,490	£1,060
16,000 to 16,999 „ . . . . .	£1,550	£1,100
17,000 to 17,999 „ . . . . .	£1,610	£1,140
18,000 to 18,999 „ . . . . .	£1,670	£1,180
19,000 to 19,999 „ . . . . .	£1,730	£1,220
20,000 to 20,999 „ . . . . .	£1,790	£1,260

and so on, adding, in England or Scotland, to £710, an additional £60 for every 1,000 electors over 2,000, and adding, in Ireland, to £540, an additional £40 for every 1,000 electors above 2,000.

Certain  
boroughs to  
be considered  
as counties.

In regard to the scale of maximum expenditure, and to the number of agents and other persons who may be legally

employed for payment, and to the number of committee-rooms which may be paid for, the boroughs of East Retford, Shoreham, Cricklade, Much Wenlock and Aylesbury are to be considered as counties. (Schedule I. Part V., 1.)

It will frequently happen that candidates will stand jointly. In that case (Schedule I., Part V., 3) the maximum expenditure allowed to each is to be reduced, if there are two joint candidates, by *one-fourth*, and if there are more than two joint candidates by *one-third*.

Further restrictions on expenditure in case of joint candidature.

Having regard to that enactment, it is important to notice what constitutes a joint candidature for this purpose. What is a joint candidature, so that one candidate shall be bound by the corrupt or illegal practices of the agents of another candidate is a very different inquiry.

But for the purpose of ascertaining whether the scale of expenditure to be allowed to each candidate is to be reduced, a case of joint candidature arises (Schedule I., Part V., 4), when *any one* of the following events happen :—

What is a joint candidature.

- (a.) Two or more candidates appoint the same election agent.
- (b.) Two or more candidates by themselves *or any agent* hire *or use* the same committee-room or rooms for the election.
- (c.) Two or more candidates by themselves *or any agent* employ *or use* the services of the same sub-agents clerks, messengers, or polling agents at the election. It would seem that for both candidates *by any agent* to use, *e.g.*, *one* committee-room or one messenger in common, although in all other respects the rooms used and persons employed by each candidate were different and separate, would constitute a joint candidature for the purposes of this section.
- (d.) Two or more candidates by themselves *or any agent* publish a joint address, or joint circular, or joint notice at the election.

The severity of this enactment is modified by a provision which however affects (b) and (c) only. If the employment

or use of the same committee-room, sub-agent, clerk, messenger, or polling agent is (1) accidental or casual, *or* (2) of a trivial and unimportant character, a case of joint candidature will not be thereby created. (Schedule I., Part V., 4—*a*.)

Severance  
of a joint  
candidature.

Candidates may at any time cease to be joint candidates, in which case they had better give public notice of the fact. In the event of a candidate ceasing to be a joint candidate or becoming a joint candidate after having begun to conduct his election as a separate candidate, he will occupy an anomalous position in regard to the maximum amount of expenditure allowed to him. It would seem that his election expenditure is to be regulated as if he had been a joint candidate throughout the election. But he may get relief under the provisions of the Act of 1883 (Schedule I., Part V., 4—*c*), for any excess of expenditure above the amount allowed to a joint candidate if his total expenses do not amount to what the Act would have allowed him as a separate candidate. That clause 4 (*c*) provides: "Where any excess of expenses above the maximum allowed for one of two or more joint candidates has arisen owing to his having ceased to be a joint candidate, or to his having become a joint candidate after having begun to conduct his election as a separate candidate, and such ceasing or beginning was in good faith and such excess is not more than under the circumstances is reasonable, and the total expenses of such candidate do not exceed the maximum amount allowed for a separate candidate, such excess shall be deemed to have arisen from a reasonable cause within the meaning of the enactments respecting the allowance by the High Court or election court of an exception from the provisions of this Act which would otherwise make an act an illegal practice, and the candidate and his election agent may be relieved accordingly from the consequences of having incurred such excess of expenses."

Case of candi-  
dature partly  
joint and  
partly  
several.

Evidence on  
application  
for relief.

The candidate who applies for relief under this clause must therefore prove to the Court the following things:—

- (1.) That the excess of expenditure has arisen from the candidate having ceased to be a joint candidate *or*

from his becoming a joint candidate after having been a separate candidate, *and*

- (2.) That he began or ceased to be a joint candidate in good faith and without any intention to evade the provisions of the Act, *and*
- (3.) That his expenses do not exceed the maximum amount allowed to a separate candidate.

If the application is made to the High Court, it must be by motion or by a judge's summons at chambers before a judge or judges on the rota for the trial of election petitions. Such previous notice of the application as the Court may direct must be given in the constituency.

Under Section 28, requiring all moneys provided for the election expenses to be paid to the election agent, it would seem to be necessary that a fund raised by subscriptions to defray A's election expenses must be paid to A himself or to his election agent.

Subscriptions  
to pay candi-  
date's  
expenses.

The proviso in Section 28 only amounts to this, that if any person, not intending to corrupt an elector, disburses any trifling sum for any small expense incurred *by himself* without thinking of repayment, and without the fact of repayment, no harm is done. If B, a partisan of A's, hires and pays for a carriage to enable him to canvass for votes for A, that is unobjectionable. But still the amount disbursed must be small, otherwise the first sub-section of Section 28 would be nullified. By sub-section 2 of Section 28, contravention of the section by any agent, constructive or otherwise, would avoid the seat.

Petty expen-  
diture by  
partisans  
not to be  
repaid.

### SECTION III.—THE PAYMENT OF ELECTION EXPENSES.

Subject to the trifling exceptions mentioned in Section 28, it is the business of the election agent to make all payments. He will do well to postpone the making of these payments, except in the rare cases in which credit is refused, until 14 days after the declaration of the result of the election, when he will know what are the total claims upon his candidate.

By the elec-  
tion agent.

Advertising  
for claims.

There is nothing in the Act to make it obligatory on the election agent to advertise for creditors to send in their claims. Creditors have public notice of the election agent's appointment, and they must be presumed to know the law, that their bills must be sent in to the election agent within 14 days next after the declaration of the result of the election. But it may sometimes be convenient to advertise for claims, and there is nothing in the Act to forbid an advertisement.

When claims  
to be sent in.

Every claim against a candidate at an election, or his election agent (which in counties includes sub-agents acting in their own districts), in respect of any expenses incurred on account of or in respect of the conduct or management of the election, must be sent in to the election agent by a bill, stating the particulars of the claim, within fourteen days next after the day on which the candidates returned are declared elected (Sec. 29 of the Act of 1883). The time will run from the nomination day if there is no poll, and if there is a poll, from the day on which the returning officer declares the result of the poll. In the case of petitions against the return for corrupt practices, the time runs from the day on which the return comes to the hands of the clerk of the Crown so that he can act upon it. As the Act speaks of the claims being "sent in," and not of the time of their receipt, it would seem that if the returning officer declares the result on the 1st of a month, the claims may be posted or otherwise "sent" at any time, so that in the ordinary course of the post or other usual means of transmission adopted they will be delivered at the office of the election agent on or before the 15th of the month, *i.e.*, within the fourteen days.

Account of  
candidate's  
personal  
expenses to  
be sent in.

It is to be remembered, that although a candidate is allowed (Sec. 31) himself to *pay* his personal expenses not exceeding £100 in connection with the election (which by Sec. 64 includes "the reasonable travelling expenses of such candidate and the reasonable expenses of his living at hotels or elsewhere for the purposes of and in relation to such election"), yet the candidate *must*, within fourteen days after the returning officer has declared the result of the election, send to the election agent a written statement of the *amount* of

the personal expenses paid by him. Seemingly, the particulars of the amount need not be stated. Any excess on account of personal expenses over £100 *must* be paid by the election agent (Sec. 31), and any person authorised under Section 31, Sub-section 2, to make petty disbursements for stationery, postage, telegrams and other expenses, *must* within the same time, send to the election agent a statement of the *particulars* of the payments made by him, and he must also send in a receipted bill vouching the payment (Sub-sec. 3). The Act applies, so far as circumstances will admit, to the claims by the election agent for his remuneration and payment. He can hardly be bound to send his claim in to himself, but he would do well to give notice of his claim within the fourteen days next after the declaration of the result to his candidate. His claim must then be satisfied by the candidate within the next fourteen days (Sec. 32), otherwise it will become a "disputed claim," and be dealt with accordingly. Compare Section 29, Sub-sections 7 and 8 and Section 30.

Personal expenses over £100 to be paid by the election agent.

Particulars of petty disbursements.

Remuneration of election agent.

The returning officer *must* transmit to the election agent, within *twenty-one* days after the return, an account of the charges claimed by him. (Sec. 32, Sub-sec. 2). The account need not be sent to the candidate or anybody else, Cf. the statute, 38 & 39 Vict., c. 84. As to the power of the returning officer to require security for the payment of his charges and the amount of the security which can be required, and the amount of the charges, see the statute 38 & 39 Vict., c. 84.

Returning officer's charges.

If a claim be not "sent in" within the proper time, the creditor will be barred of all right of action against the candidate or the election agent. They are prohibited from paying any late claim, and if the election agent should pay any such claim he would be guilty of an illegal practice. But certain relief against this somewhat severe enactment may be obtained upon conditions, under Sub-sections 6 and 9 of Section 29 of the Act of 1883, which will be dealt with presently.

Late claims barred.

The election agent having received the claims against his

Examination  
and payment  
of claims.

candidate will examine them, and separate those which are in respect of contracts made or expenses incurred by the candidate or the election agent acting by himself or by a sub-agent. These, except in cases in which the candidate's liability is admitted, but the amount claimed is disputed, *must* be paid within a second period of 14 days, *i.e.*, within 28 days of the day on which the candidates returned were declared duly elected. To pay them afterwards would be an illegal practice. By Sub-section 4 of Section 29 of the Act of 1883, it is enacted: "All expenses incurred by or on behalf of a candidate at an election, which are incurred on account of or in respect of the conduct or management of such election, shall be paid within the time limited by this Act and not otherwise; and subject to such exception as may be allowed in pursuance of this Act an election agent who makes a payment in contravention of this provision shall be guilty of an illegal practice."

Time of  
payment.

Probably it would be held that a payment was made in good time if the money or cheque were posted or despatched to the creditor in such time that in the ordinary course of the post or other means of transmission it would be delivered at his address within the 28 days. It would not matter, we think, that the payment was by a crossed cheque, which could not be cleared until after the 28 days had expired.

All claims sent in within the proper time, *disputed* by the election agent, or which the election agent *refuses or fails* to pay within the 28 days, because "*disputed*" claims within the Act, and are to be dealt with as such. Section 29, Sub-section 7.

Relief against  
payments out  
of time.

The election agent may, by inadvertence or otherwise, commit the illegal practice of paying a claim after the 28 days, or of paying a claim sent in after the 14 days. In that case, probably, he might be relieved under the provisions of Section 23 of the Act of 1883. The candidate may also be relieved. The High Court, under the powers of Section 23, might excuse him from the consequences of the Act, and thereupon it might stay a petition



presented against his return, and based on the election agent's illegal practice in so paying, and (Sub-section 6) the judges *at the trial* of the petition *may* report, in a proper case, that the payment made by the election agent in contravention of the section, was made *without the sanction or connivance* of the candidate. If they do so report, the election will not be void on account of that payment, nor will the candidate be subject to any incapacity, but he may have to pay the costs of the petition.

As to all disputed claims, the election agent should await the action of the persons making the disputed claims. Action in disputed claims.

If the claimant has made a slip by sending in his claim too late, or sending it to the candidate personally, he should apply to the High Court, by a master's summons served on the candidate, for an order giving leave for the payment of the claim. The application should be supported by an affidavit of the facts. The claimant will then be in the same position as if he had sent in his claim to the proper person and within the proper time. As the claimant's slip occasions the application, it seems reasonable that he should pay the candidate's cost of appearing upon it. The candidate or the election agent may himself make the application if he think fit to do so. When the order has been made, the sum specified in the order of leave may be paid *either* by the candidate or his election agent, and when paid in pursuance of the order of leave is to be deemed to have been paid within the time limited by the Act. Order of leave to pay irregular claim.

Any claimant whose claim is disputed, or left unpaid, if he has duly sent in his claim, or obtained such an order of leave, may, if he thinks fit, bring an action against the candidate; or the election agent, if the latter has made himself personally liable (Section 29, Sub-section 8). If the candidate is the defendant, the action may be brought in any court having jurisdiction, which will generally be the High Court or the County Court holden in the district. If the election agent is the defendant, he may be sued in any court having jurisdiction in the county or borough in which his Action for a disputed claim.

appointed office is (Section 26, Sub-section 2), or in the High Court.

When the action is brought it will proceed like any other action. It will be no defence to it that if the candidate were to allow or pay the claim he would thereby exceed the maximum amount of expenditure allowed him by the Act of 1883 (Sec. 19), unless when the contract was made the plaintiff was aware that it contravened the Act. If, therefore, a judgment or order goes against the defendant, ordering him to pay a sum of money to the plaintiff, although any sum paid in pursuance of the judgment or order is to be deemed (Section 29, Sub-section 8) to be paid within the time limited by the Act of 1883 (28 days after the declaration of the return), and to be an exception from the provisions of the Act requiring all claims to be paid by the election agent, yet any excess thereby caused over the maximum expenditure allowed is nevertheless an illegal practice.

If amount  
only disputed  
may be  
referred to  
taxation.

If in the action the plaintiff's right of action is not disputed, but only the amount of his claim, the question is to be referred to taxation, unless the Court, on a master's summons taken out by the plaintiff or on the plaintiff's motion, otherwise directs. Section 30 of the Act of 1883 directs :—  
“If any action is brought in any competent court to recover a disputed claim against a candidate at an election, or his election agent, in respect of any expenses incurred on account or in respect of the conduct or management of such election, and the defendant admits his liability, but disputes the amount of the claim, the said amount shall, unless the Court, on the application of the plaintiff in the action, otherwise directs, be forthwith referred for taxation to the master, official referee, registrar or other proper officer of the court, and the amount found due on such taxation shall be the amount to be recovered in such action in respect of such claim.”

#### SECTION IV.—THE RETURN AND DECLARATION OF ELECTION EXPENSES.

The duties of the election agent do not end with the examination and payment of the claims sent in. Within seven days after the last day allowed for payment of the claims—that is to say, within 35 days after the declaration of the result of the election—he *must* transmit to the returning officer a return of his candidate's election expenses.

The return of expenses.

The return must contain (Section 33, Sub-section 1)—

Contents of the return.

- (a) A statement of all payments made by the election agent, together with all the bills and receipts (which bills and receipts are included in the expression “return respecting election expenses”).
- (b) A statement of the amount of personal expenses, if any, paid by the candidate.
- (c) A statement of the sums paid to the returning officer for his charges, or, if the amount is in dispute, of the sum claimed and the amount disputed.
- (d) A statement of all other disputed claims of which the election agent is aware.
- (e) A statement of all the unpaid claims, if any, of which the election agent is aware, in respect of which application has been or is about to be made to the High Court.
- (f) A statement of all money, securities, and equivalent of money received by the election agent from the candidate or any other person for the purpose of expenses incurred or to be incurred on account of or in respect of the conduct or management of the election, with a statement of the name of every person from whom the same may have been received.

The words of the section give only a faint idea of the particularity and exactness required in the return. This will be appreciated by a perusal of the form of return contained in

Particulars required.

the Second Schedule to the Act, given in the Appendix. In each case the name and description of the person paid, and particulars of the goods, work, labour or services in respect of which he is paid, must be set out.

Declaration  
verifying  
return.

At the same time, the election agent *must* send to the returning officer, accompanying the return, a declaration to be made by him *before a justice of the peace*, verifying the return. The declaration *must* be in the form set out in the second Schedule to the Act. But if the candidate has had no election agent, but has been his own election agent, the declaration provided in the schedule for an election agent is not to be used. But, instead of it, the candidate *must* make and transmit the declaration by the candidate respecting election expenses, as specified in the second Schedule to the Act. (Section 32, Sub-section 3.) In any case, and whether the candidate has had an election agent or not, he *must*, at the time when the return of election expenses is transmitted to the returning officer, *or within seven days afterwards*, transmit to the returning officer a declaration, made *before a justice of the peace*, respecting election expenses, and of general purity (Section 33, Sub-section 4). For the form, see Schedule II. in the Appendix.

Declaration  
by candidate.

Where candi-  
date abroad.

It may happen that the candidate is out of the United Kingdom when the election agent sends in his return and declaration. In such a case, the time for the candidate to make his declaration will be extended until the expiry of 14 days after he returns to the United Kingdom, within which time it *must* be made. If the candidate were cruising in a yacht, and touched at a port in the United Kingdom, that would probably be held to be a "return" to the United Kingdom within the meaning of the section (Section 33, Sub-section 8). The candidate's absence confers no right on the election agent to delay the transmission of his return and declaration for an hour, and when the candidate on his return has made the required declaration, the latter *must* be *forthwith* transmitted to the returning officer. (*Ibid.*)

Return con-  
cerning

By Section 33, Sub-section 9, it is provided that when after the date at which the return respecting election

expenses is transmitted, leave is given by the High Court for any claims to be sent in or paid (as to which, see Section 29, Sub-section 8) *the candidate or* his election agent shall *within seven days* after the payment thereof, transmit to the returning officer, a return of the sums paid in pursuance of such leave, *accompanied* by a copy of the order of the court giving the leave, and in default, he shall be deemed to have failed to comply with the requirements of the section without authorised excuse, *i.e.*, he will thereby become guilty of an illegal practice, avoiding the election. We think that if the returning officer has ceased to be such since the election, and before a return or declaration is sent in, the proper person to whom to send the return or declaration will be the late returning officer, and not his successor. The latter would seem to be a stranger to the election. The safest course would be to transmit the return and declaration to both, and if the late returning officer has died, then to transmit them to his successor.

irregular  
claims paid

The penalties for any omission or failure to comply with the requirements of the law regarding the making and transmission of a proper return and declarations are very severe. In the first place, the omission or failure is an illegal practice, which, on a petition, avoids the seat (or, if the candidate has been unsuccessful at the election, he incurs the ordinary penalties imposed for an illegal practice). In the second place, even though no petition be presented, if the return and declarations are not transmitted within the proper time, the candidate shall not (Section 33, Sub-section 5), after the expiration of that time, sit or vote in the House of Commons for the constituency until (*a*) the returns and declaration have been transmitted, *or* (*b*) until the allowance by the court of an "authorised excuse" for the failure to transmit them. If the candidate do so sit or vote, he is to forfeit the sum of £100 for every day he so sits or votes, to any person who cares to sue for it. The action might be maintained by a common informer. (*Bradlaugh v. Clarke*, 8 App. Cas., 354.)

Penalties.

If the candidate *or* the election agent should *knowingly*

Willful false  
declaration.

make the declaration falsely, he would commit a corrupt practice. (Section 33, Sub-section 7). For such an offence the candidate could have no relief under Section 23, or otherwise, because, for a corrupt practice, other than treating or undue influence, there can be no relief under any section. In addition, the persons, whether candidate or election agent, who actually made the false declarations would be liable, on conviction, to the punishment of wilful and corrupt perjury, which may be *seven years' penal servitude*.

Relief on  
innocent  
mistake.

The Court has power to relieve a candidate or an election agent from the consequences of an *innocent* mistake, either when the returns and declarations have not been transmitted as required by the Act, or when, being transmitted, they contain some error or misstatement. (Section 34 of the Act of 1883). The way to obtain the relief, in the Act called an "authorised excuse," and the conditions on which it is granted, are treated of hereafter under the title of "Procedure," Section I. The same section (34) indicates the course to be adopted when the candidate and election agent cannot make the requisite return and declarations, owing to the default of some sub-agent. (See also *infra*.)

Or default of  
sub-agent.

No sub-agent is required to send any return or declaration to the returning officer.

## CHAPTER VIII.

## PRACTICE AND PROCEDURE.

## SECTION I.—ON APPLICATIONS FOR RELIEF.

Many candidates will probably discover, during or after the election, that more or less by inadvertence, illegal practices, payments, employments, or hirings, have been done, made or entered into by themselves or their agents. As soon as the discovery is made, application should be made to the High Court (or, if the election court is sitting, to that court), under the proper section of the Act of 1883, to be relieved against the consequences and penalties incurred, as well in regard to the election as to the individuals. The procedure will usually be, until new rules of court have been made, to apply *ex parte* at chambers for directions as to the notice of the intended application to be given in the constituency. After these directions have been followed, the substantive application for relief will be made upon the appointed day by summons at chambers, or by motion in court, before a judge on the rota for the trial of election petitions, or in cases in which a master has jurisdiction before a master at chambers. (Section 56 of the Act of 1883). The application, if under Section 23, must be supported by evidence that the act or omission in question arose from inadvertence, or from accidental miscalculation, or from some other reasonable cause of a like nature, and not from any want of good faith. (Section 23, Sub-section (b)). The provision in the section as to notice would seem to imply that, upon the application, any candidate or elector may be heard. Certainly, if a petition has been presented or is threatened, it would seem highly convenient to adjourn the application generally, or to refer it to the election court, which will hear all the witnesses. Any intending petitioner should oppose the application for relief. We think he is entitled to be heard before an order largely affecting his rights is made.

Applications to the Court to relieve against illegal acts.

How made.

Upon what evidence.

Parties to be heard.

If the illegal practice, payment, employment, or hiring amount to bribery, no relief can be given to the candidate or other applicant.

Applications for default concerning the return of expenses and declarations.

By Section 33, Sub-section 6, of the Act of 1883, if a candidate, or his election agent, fails to comply with the requirements of Section 33, as to the making and transmitting of the return and declarations concerning the election expenses, he shall be guilty of an illegal practice, and the candidate's election will be avoided; and if the return and declarations are not made and transmitted within the time provided by the statute, the candidate returned may not sit or vote in the House until they have been transmitted. (Section 33, Sub-section 5).

As soon as any such failure or delay is discovered, the candidate affected should apply to the High Court to be allowed an "authorised excuse" for the failure to transmit the return and declaration, or for any error or false statements. (Section 34 of the Act of 1883.) The order allowing an "authorised excuse" will prevent the omission or error being an illegal practice, and save the election in that respect, and protect the candidate (whether returned or not) and his agent against penalties. An election court has jurisdiction to make the order; but if a candidate applies to an election court for this relief, he will probably have to pay the costs of the petition in any event. On the other hand, by an immediate application to the High Court, he may stall off a petition; at all events, he will take a powerful weapon out of the hand of any petitioner, and save a great deal in the costs of litigation.

Applications should be made without delay.

Notice of the application.

Such notice of the application must be given in the constituency as the court may prescribe, and the application must be supported before the court or a judge at chambers by evidence (1) that due notice has been given; (2) of the applicant's good faith; and, if the applicant was a candidate, (3) that the failure to transmit the return and declarations, or any of them, or any error or false statement in them, has arisen by reason of his illness, or of the absence, death, illness, or misconduct of some agent or agent's clerks, or by reason of inadvertence, or of some reasonable cause of a like

Evidence in support.



nature—*e.g.*, by a slip—and not by reason of any want of good faith on the part of the candidate.

If the applicant be an election agent anxious to be relieved from the consequences of an illegal practice, he must give evidence in support of his application to the effect that his failure or error was caused by his own illness, or the death or illness of any prior election agent of the candidate, or the absence, death, illness, or misconduct of some sub-agent clerk or officer of an election agent, or by inadvertence or other reasonable cause, and not by want of good faith on the part of the applicant. (Section 34 of the Act of 1883.)

If the evidence satisfy the Court or the judge, the order will then be made allowing an authorised excuse for the failure to transmit the return and declaration, or for the error or false statement in question.

If the return and declaration cannot be made and transmitted, owing to the refusal or failure of the election agent or a sub-agent, the Court, before making an order allowing an authorised excuse, will order the defaulter to attend before the Court, and unless he successfully show cause to the contrary, will, on his attendance, order him to do his duty by making the return and declaration, or by giving the necessary particulars, or may order him to be examined on oath. In default of compliance, the defaulter might be fined £500, and probably imprisoned for contempt of court. (Section 34, Sub-section 2, of the Act of 1883.)

Procedure  
where sub-  
agent in  
default.

In any case, if the candidate proves that the act or omission of the election agent regarding the return or declaration was without the candidate's connivance, and that he took all reasonable means to prevent it, the Court *must* relieve the candidate from the consequences of the election agent's act or omission. (Section 34, Sub-section 3, of the Act of 1883.) In such cases the candidate may obtain relief without satisfying the stringent conditions which are precedent to the granting of relief against treating and undue influence, and other illegal practices by agents, under Section 22 of the Act of 1883; but the Court, before exercising its

When Court  
must relieve.

discretion in other cases, may require similar evidence to that necessary under Section 22.

Any order made under Section 34 may make the allowance of an authorised excuse conditional upon the making of the return and declaration in a modified form, or within an extended term, or upon other terms being complied with. (Sub-section 3.)

To whom  
applications to  
be made.

As to the practice, when relief is sought by a candidate against the consequences of an excess of expenditure caused by the candidate having been a joint candidate (see p. 120 *infra*).

Applications to the High Court, under the jurisdiction conferred by the Act of 1883, may be made (Section 56)—

“(a.) In criminal proceedings, to any judge of the Queen’s Bench Division ;

“(b.) In other matters, (1) to any judge on the rota for the trial of election petitions, and either in court or at chambers ; or (2) to a master, subject to appeal ;”

Limits of  
master’s  
jurisdiction.

except that a master has no jurisdiction at all on applications under Section 23, Section 34 ; that is, in regard to applications for (1) orders declaring any act or omission to be an exception from the provisions of the Act with respect to illegal practices, payments, employments, or hirings ; or (2) orders allowing an “authorised excuse” in regard to the return or declaration of expenses. A master may make orders allowing the withdrawal of election petitions.

## SECTION II.—ON ELECTION PETITIONS.

Election  
petitions.

The practice upon election petitions is now regulated by the Parliamentary Elections Act, 1868, and the rules thereunder of Michaelmas term, 1868, March, 1869, and January, 1875, and the Act of 1883, all of which are contained in the appendix hereto.

To what  
Courts  
presented.

An election petition, which lies in England to the Queen’s Bench Division of the High Court of Justice, in Scotland to the Court of Session, and in Ireland to the Court of

Common Pleas, may be presented by any one or more of the following persons :—

- (1.) Some person who voted, *or* who had a right to vote at the election to which the petition relates ; *or* Who may petition.
- (2.) Some person claiming to have had a right to be returned or elected at such election ; *or*,
- (3.) Some person alleging himself to have been a candidate at such election, *i.e.*, one who has been nominated as, or has declared himself a candidate at such election.

It is safer to join several petitioners, lest there should turn out to be some objection to one petitioner. The respondent or respondents will be the person or persons whose return is impeached ; but a person who claims to have been elected and acts as such may also be made a respondent. (*Yates v. Leach*, L.R., 9 C.P., 605 ; 43 L.J., C.P., 337 ; 30 L.T., 790.) Several persons should join.

An election petition abates by the death of the petitioner or of the survivor of several petitioners, but not by the death of the respondent. Upon the respondent's death another person may be substituted as respondent. (*Morton v. Galway*, 9 Ir.R., C.P., 173 ; 3 O'M. & H., 20.) How petition abated.

A petition may be presented, although the candidate returned die after the return and before presentation of the petition. (*Ibid.*)

A dissolution of Parliament brings a petition to an end. (*Carter v. Mills*, 9 L.R., C.P., 117 ; 43 L.J., C.P., 111 ; 22 W.R., 318.) But the successful party was declared entitled to his costs where the dissolution took place after the decision of the petition, but before the judge's certificate reached the speaker. (*Marshall v. James*, 9 L.R., C.P., 702 ; 43 L.J., C.P. 281 ; 30 L.T., 559, 22 W.R., 738.)

The petition must be signed by all the petitioners.

If the petition question the return on the ground of corrupt practices, or on any other ground than an allegation of "illegal practices" under the Act of 1883, it must be presented within 21 days after the return has been made to the Clerk of the Crown, "unless it question the return or election upon an allegation of corrupt practices, and specifically Within what time to be presented.

alleges a payment of money or other reward to have been made by any member or on his account, or with his privity, since the date of such return, in pursuance or in furtherance of such corrupt practices, in which case the petition may be presented at any time within 28 days after the date of such payment." (Parliamentary Elections Act, 1868, Section 6, Sub-section 2. As to subsequent illegal practices, see Section 40 of the Act of 1883.) The 21 days begin to run when the return has come to the hands of the Clerk of the Crown so that he can act on it. Where, therefore, it was left at his office with a housekeeper, on the evening of February 4, and was received by the Clerk of the Crown from the housekeeper on the morning of the 5th, the time began to run from the 5th. (*Hindle v. Waring*, L.R. 9, C.P., 435; 43 L.J., C.P., 209; 30 L.T., 329; 22 W.R., 735.)

When the time begins to run.

Sundays do not count in any of the periods allowed for filing petitions. (*Pease v. Norwood*, L.R., 4, C.P., 235; 38 L.T., C.P., 161.) (Section 40, Sub-section 5 of the Act of 1883.)

When the corrupt act is after the election.

The provision that a petition may be presented within 28 days of a corrupt payment made *after* the return, seems to apply only where the corrupt payment is made by the member, or with his privity. (*Salford*, 20 L.T., 120; 1 O'M. & H., 133.) Whether on such a petition the petitioner would be confined to evidence of such corrupt payments made after the return, or would be allowed to charge and prove corrupt practices at or before the return is doubtful. (*Galway*, 1 O'M. & H., 303; *Kiddermminster*, 2 O'M. & H., 170.)

These rules as to the limit of time for the presentation of a petition for corrupt practices, irregularities at the poll, miscounting or improper return, are untouched by the Act of 1883. By Section 40 of that Act it is declared that that section shall apply where the illegal practice amounts to a corrupt practice. But as Sub-section 2 shows that the 21 days' rule is preserved in regard to petitions under the Act of 1868, it would seem that the limit fixed by Section 40 applies not in cases of corrupt practices generally but only when the illegal practice charged—as, for instance, paying for the exhibition of election addresses—turns out to have

been done with the intent to corrupt the payee or some elector.

If this view is correct, a petition which might have been presented had the Act of 1883 not been passed, must still be presented within the 21 days. But if a petition is presented for an "illegal practice" done under the new Act, it will be in time if presented before the expiration of 14 days after the day on which the returning officer receives the return and declarations respecting election expenses by the member to whose election the petition relates.

Time for presenting petition for an offence against the Act of 1883.

If the 21 days from the return be allowed to slip by, a petition subsequently and duly presented, complaining of an "illegal practice," may not charge any of the common corrupt practices chargeable under the Act of 1863. A petition should generally therefore be presented within 21 days after the return, and if any illegal practice be discovered within the 14 days after the returning officer receives the returns and declarations, the High Court may within these 14 days amend the petition. (Section 40.) The application for leave to amend should be by motion or by summons at chambers to a judge on the rota (Section 56) or a master, upon notice to the other side and an affidavit speaking generally to the facts. Just as in regard to corrupt practices, so in regard to illegal practices, if (Section 40) the election petition specifically alleges a payment of money or some other act to have been made or done since the day when the returning officer received the returns and declarations, by the member *or any agent* of the member, or with the privity of the member or his election agent, in pursuance or in furtherance of the illegal practice alleged in the petition, the petition may be presented at any time within 28 days after such payment or other act.

What such a petition may charge.

Time for petition in respects of acts done after the return of expenses.

The time for presenting a petition for illegal practices counts, when the returns and declarations are received on different days, from the last of these days, or where there is "an authorised excuse" or excuses for failing to send in the returns and declarations, from the date of the "allowance of the excuse," or the date of the allowance of the last excuse

How the time is reckoned under Act of 1883.

(Section 40, Sub-section 4.) By Section 34, Sub-section 4, of the Act of 1883, the date of the allowance of the excuse is the date of the order allowing it, or if conditions are to be complied with, the date at which they are fully complied with; and by Sub-section 5, for the purposes of Section 40, time is to be reckoned just as it reckoned for the purposes of the Parliamentary Elections Act, 1868, that is to say, the first day does not count, nor any Sunday, but the last day does count.

Practice on  
filing petition.

*If circumstances likely to invalidate an election transpire, and it is decided to present a petition, get the petition settled by counsel, fair copied, and signed by all the petitioners. Draw the recognizance (Gen. Rules, Parl., 1875, R. 19, contains the form post, Appendix), and get it acknowledged by all the sureties. Within the 21 days (or 14 or 28 days, as the case may be) leave the original petition and a fair copy thereof, and the recognizance, and an affidavit by each of the sureties that he is possessed of property above what will satisfy his debts of the clear value of the sum for which he is bound, at the office of the master (the election petition office in the Royal Courts of Justice), and take the receipt of himself or his clerk for the petition; at the same time leave a notice in writing of the name and address (within three miles of the General Post Office) of the petitioner's agent.*

Filing  
petition  
during  
holidays.

Note that if the last day for filing a petition (or anything else required to be filed in a given time) fall on a holiday, the petition must be put into the letter box at the master's office on that day (or earlier), and an affidavit, stating when it was so delivered, must be filed on the first day after the expiration of the holidays. (Rule 4, 1875.)

*The respondent does not enter an appearance, but before service of a petition or at any time within a week after service, he or his agent must leave a similar notice in writing of the name and address of his town agent.*

The recognizance must be acknowledged before a judge at chambers or the master in town, or a justice of the peace in the country. A London magistrate in town will not do. (*Shrewsbury*, 19 L.T., 499.)

Service of  
petition.

*Within five days after presentation of the petition, serve a copy.*

*of it personally on the respondent or on his town agent if he has appointed one. If service cannot be effected then within such five days apply to the judge at chambers for an order for substituted service. As to the necessary affidavit, see General Rules (Parliament), 1875, r. 14. A notice of the nature of the proposed security is to be served in like manner.*

Immediately after service of the petition and notice of the nature of the security given, *file with the Master an affidavit of the time and manner thereof* (Rule 2, 1875).

If the petition is what may be called demurrable, the respondent should move the Court, or apply by summons at chambers, that it may be taken off the file or all proceedings under it stayed.

Demurrable  
petition.

Although the petition be against two or more respondents, one surety for £1,000 will suffice (*Hereford* 49, L.J., 686). Under no circumstances can security for more than £1,000 be required. (*Pease v. Norwood*, L.R., 4, C.P., 235, 38 L.J., C.P. 161., 19 L.J., 648 ; *Thomas v. Wylie*, 19 L.T., 498.)

Security for  
costs.

If the respondent has any objection to the recognisance, *notice in writing of the objection, stating the grounds of it, must within five days after service of the petition be served on the petitioner's agent and left at the Master's office. At the same time, take out a Master's summons to declare the security insufficient, and support the summons by affidavits or witnesses. Give the petitioner's agent notice to produce the sureties for cross-examination.*

Objections to  
the recogniz-  
ance.

*If the Master's decision is adverse, within five days appeal to the judge at chambers by summons, and support the appeal in the same way. An appeal will lie from the judge to the Court. (Kingston-upon-Hull, 19 L.T., 648., 38 L.J., C.P. 161.)*

If the security be declared insufficient, the order will declare the amount of the insufficiency. *Within five days from the date of the order, not including the day of the date, the petitioner's agent must pay that amount into the Bank of England, to the account of "The Parliamentary Elections Act, 1868, Security Fund."*

If successful,  
payment into  
Court to be  
made.

The petition will then be at issue.

The Master will give all parties 15 days' notice of trial.

Formal  
objections.

It is provided by General Rules (Parliament), 1868, r. 60, that no proceeding under the Act shall be defeated by any formal objection, but it would be very unwise for any party to rely upon this provision. However, where the petition complained of the conduct of the returning officer, but no notice of the petition was given to him, nor did the petitioner name any town agent at all, the Court refused to strike the petition off the file. (*Shrewsbury*, 19 L.T., 499.)

Amendment  
of the petition.

In the course of the proceedings new facts may come to the knowledge of the petitioner, making it desirable to amend the petition. The Court, or a judge at chambers, may allow the amendment, where it relates to a matter discovered upon the inspection of the ballot papers, or to a corrupt payment by the respondent or with his privity after his return. (*Pickering v. Startin*, 23 L.T., 111.) But it seems that in other cases, except as provided by Section 40 of the Act of 1883, the Court has no jurisdiction to allow new charges to be made, for that would be in effect to allow a new petition to be presented after the expiration of the proper time. (*Maude v. Lowley*, L.R. 9, C.P. 165, 43 L.J., C.P. 105, 30 L.T., 168; *Clark v. Wallond*, 52 L.J., 321, 31 W.R., 551.) It is competent to the Court to amend an election petition at any time by striking out allegations therein where it is satisfied that no injurious result, or a beneficial one, will follow, but the Court will not amend by striking out, after the lapse of the time limited by the Act for presenting it, that part of the prayer which claims the seat for the petitioner and the allegations applying to a scrutiny which would be dependent thereon, for that would affect the rights of the constituency. (*Aldridge v. Hurst*, 1 C.P.D., 410, 45 L.J., C.P. 431, 35 L.T., 156; 24 W.R., 708.)

In any case in which it is sought to amend, the procedure is by motion before a judge on the rota, or by summons before such a judge or a Master at Chambers, in either case with affidavits in support.

Withdrawal  
of petition.

If it should become desirable to withdraw the petition, the petitioner's agent must leave a signed notice of the applica-



*tion for leave to withdraw at the Master's office, and serve a copy upon the respondent and the returning officer.*

The notice must state the grounds of the application. (General Rules (Parliament,) 1875, r. 45.) Not less than a week after the notice has been left with the Master, the Court will hear the application. The application must be supported by the affidavits of all the parties to the petition, and all their solicitors, that the withdrawal has not been brought about by any corrupt bargain (Section 41 of the Act of 1883). The Court may dispense with any affidavit.

How application for withdrawal to be made.

As to what the affidavits must state, see Section 41 of the Act of 1883, Sub-sections 2 and 3. Copies of the affidavits must be delivered to the Director of Public Prosecutions a reasonable time before the application for leave to withdraw is heard, and he will be heard upon the application, and the Court may receive the evidence of anybody whose evidence the Director of Public Prosecutions may consider material (Sub-section 5).

Copy affidavits to be left with Director of Public Prosecutions.

For the penalties for any corrupt bargain to withdraw a petition, see Sub-section 4. In addition, if the withdrawal be the result of any arrangement prohibited by the Act, the Court may direct the £1,000 security given by the petitioner to remain as security for any costs that may be incurred by any substituted petitioner, and to the extent of the sum named in the security the original petitioner will be liable to pay the costs of the substituted petitioner (Parliamentary Elections Act, 1868, s. 35). The Court reports to the Speaker whether the withdrawal is the result of any improper arrangement (Sub-section 7 of Section 41 of the Act of 1883). On principle, although not expressly named, an agreement to withdraw one petition in consideration of another petition not being presented, would be an illegal agreement.

Penalties for corrupt bargains for withdrawal.

It would seem that the new enactment as to the withdrawal of petitions does not apply to an Election Court. If such an application be made to an Election Court, it may either adjourn in order that the High Court may be moved under Section 41, or, finding no evidence

offered, declare the respondent duly elected. (*North Durham*, 3 O'M. & H. 2.)

Where there are more petitioners than one, no application to withdraw a petition can be made except with the consent of all the petitioners (Parliamentary Elections Act, 1868, s. 35.)

Notice of  
application  
essential.

Withdrawal  
at the trial.

The notice of intention to apply for leave to withdraw is of statutory obligation, and essential. Therefore, where at the trial the petitioner informed the Court that he intended to withdraw the petition, it was held there must be an adjournment of the trial in order that the statutory notice of withdrawal might be given, and other persons substituted for the petitioners if they so desired. (*Hartlepool*, 19 L.T., 821.) In the *Brecon Case* (2 O'M. & H., 33), where notice was given three days before the trial, the judge, when the case was called on and no evidence was offered in support of the petition, decided that the withdrawal must be in open Court, and lately, in the *Gloucester Case* (3 O'M. & H., 72), no adjournment was required, the petitioner simply saying that he offered no evidence. "There might possibly be cases in which a judge would not allow a petition to be withdrawn, and would, as far as he could, use his power to prevent it. He might, for instance, exercise the power which is given him of recommending the Court not to allow the deposit to be withdrawn without considerable explanation. The task, no doubt, would be an extremely difficult one, and the mode in which a judge is to compel parties to go on with a petition which they have determined to withdraw remains to be discovered." (*Per Grove, J. at North Durham*, 3 O'M. & H., 2, 3.)

*If the respondent cannot defend his return he should give notice that he does not intend to oppose the petition, by leaving notice thereof in writing at the Master's office six clear days before the day appointed for trial. The notice must be signed by the respondent, R. 52.*

The practice upon the withdrawal of a part of the petition (e.g., a claim to the seat) is similar to that upon the withdrawal of a whole petition. (*Aldridge v. Hurst*, L.R., 1 C.P. D. 410, 45 L.J., C.P., 431, 35 L.T., 156, 24 W.R., 708.)

A copy of every order and particular must be filed with the Master (Rule 1, 1875).

If the petition raises a question of law, and the facts are not in dispute, the Court (upon motion) or a judge at chambers (upon summons) Rule 37, will order a special case to be stated for the opinion of the Court, whose decision shall be final. Or, if the questions of law can be conveniently severed from the questions of fact, the questions of law may be decided upon a special case, and the questions of fact left for trial in the usual way. Parliamentary Elections Act, 1868, Section 11, Sub-section 16 (*Hereford*, 19 L.T., 702; *Salisbury*, 19 L.T., 528).

Stating a special case.

If the petition does not come to an end in any of these ways, either party may find it desirable to procure inspection of the ballot papers and counterfoils, as to which see pp. 150 & 151 *infra*. But in proceedings under an election petition, interrogatories cannot be administered (*Wells v. Wren*, 5 C. P. Div., 546; 49 L.J., 681), nor can any order be made for inspection or discovery of documents (*Moore v. Kennard*, 10 Q.B. Div., 290, 48 L.T., 236, 31 W.R., 610).

Discovery and interrogatories.

Evidence is not to be stated in the petition, but the Court will order the petitioner to give particulars (Rule 6). These should be applied for by a judge's summons at chambers, that the petitioner may be ordered to deliver to the respondent, 10 clear days before the day appointed for trial, particulars in writing of the names, addresses and numbers on the register of the persons alleged to have bribed or to have been bribed, or to have treated or to have been treated, or to have intimidated or to have been intimidated, or to have been guilty of undue influence, or to have incited any other person to personate any, and what elector, or to have personated any, and what elector, or to have practised, done or made any illegal practice, payment, employment or hiring, stating in each case by whom and where, and when and with what consideration, thing, threat, promise, or incitement, or by what other act, each person alleged to have been bribed, treated, intimidated, unduly influenced, or

Delivery of particulars.

Summons for delivery of particulars.

incited to personate, was so bribed, treated, intimidated or incited, and particulars with dates and items of such illegal practices, payments, employments and hirings, and that the petitioner may be precluded at the trial from giving in evidence any act, matter or thing not comprised in such particulars so to be delivered.

Time for  
delivery of  
particulars.

It is now the practice, in the absence of exceptional circumstances, to order particulars to be delivered seven clear days before the hearing. (*Lenham v. Barber*, 10 Q.B. Div., 293, 52 L.J., C.L., 312, 31 W.R., 428. *Clark v. Wallond*, 52 L.J., C.L., 321.) But as little as three days before trial has been ordered for the delivery of the particulars (*Beal v. Smith*, L.R., 4, C.P., 145; 38 L.J., C.P. 145), on the other hand, in the *Bewdley Case* (1880), as much as fourteen days was allowed. Sundays, Christmas Day and Good Friday do not count in the "so many days before the day appointed for trial." (Rule 3 of 1875.)

Settling the  
particulars.

In framing the particulars, two dangers are to be avoided. If they are made too voluminous and cases are introduced which fail of proof, the petitioner, although successful in the result, may have to bear the costs occasioned by the unsuccessful charges, or even the whole of his costs. (*Berwick*, 31 O'M. & H., 178, 44 L.T., 289. *Hereford*, 1 O'M. & H., 194, 21 L.T., 117. *Norwich*, 2 O'M. & H., 38.) On the other hand, the petitioner should mention in the particulars every case on which he means to rely at the trial, otherwise he may be precluded from giving evidence of any case omitted. Where it is sought at the trial to give evidence of cases not in the particulars, the judges usually require an affidavit, before allowing the amendment, that the facts have come to the knowledge of the petitioner's agent since the delivery of the particulars, and that all due and reasonable inquiry was made before the delivery of the particulars. (*Longford*, 2 O'M. & H., 7.) But the object of particulars is to prevent an unfair surprise upon the respondent, and therefore the judge's order precluding the petitioner from going into cases not in the particulars, may be disregarded at the trial, if the Court be satisfied that no in-

Amendment  
of particulars.

justice is thereby done to the respondent. (*Wigan*, 4 O'M. & H., 1, *per* Bowen, J.) We think that if the petitioner's agent discovers a corrupt or illegal practice not included in the particulars, he should immediately after the discovery notify to the respondent's agent that application will be made at the trial for leave to go into the matter so discovered.

Where the particulars were not delivered within the time limited by the order, *Martin, B.*, would neither permit the cases not mentioned in them to be gone into, nor an amendment. (*Yorkshire, S. W. Ridling*, 1 O'M. & H., 213.) But it is doubtful if this would be followed. It would seem to be more correct to adjourn the trial at the petitioner's expense if the omission has really damaged the respondent. (*Bristol*, 2 O'M. & H., 27, *per* Bramwell, B.)

It is submitted that where the seat is claimed and the respondent delivers a list of objections to the petitioner's election (under Rule 8 of 1868), the petitioner is entitled to similar particulars of such objections. Rules 6 & 7 are to be read together. (*Salford*, 19 L.T., 502.)

Particulars of objections.

The Court has jurisdiction to order the Post Office authorities to produce specified telegrams. (*Bolton*, 31 L.T., 191; 1 O'M. & H., 139; *Harwich*, 3 O'M. & H., 61, 44 L.T., 188; *Coventry*, 19 L.T., 742.)

Production of telegrams.

Before the trial, the usual notices to produce and admit should be given. The notice to produce should specify the documents intended to be referred to. It may be insufficient to refer to them in general terms. (*Westminster*, 1 O'M. & H., 89, 20 L.T., 238.)

Notice to admit and produce.

An order may be made for a commission to examine a witness alleged to be ill and unable to attend the trial on an affidavit that he is so ill and unable to attend and that he is a material witness. (*Staleybridge*, 19 L.T., 702.)

Commission to examine witness.

The witnesses should be subpoenaed in the usual way. Sometimes they require to be watched. Everyone who is familiar with election petitions is aware that important witnesses will mysteriously disappear shortly before the trial and fail to re-appear until after the trial. In such a case,

Procuring and compelling attendance of witnesses.

Lush, J., declared he would adjourn, if need be, for six months. (*Stroud*, 2 O'M. & H., 107.)

If a witness is in another part of the kingdom, he may be subpœnaed on the special order of the Court or a judge (17 & 18 Vict. c. 34, s. 1).

On proof of fruitless efforts to serve a subpœna the Court will issue an order for the attendance of a witness at the trial. (*Waterford*, 2 O'M. & H., 3.) To disobey such an order would be a contempt of Court (See rr. 41 and 42 of 1868).

But where it was stated that some persons had evaded service, Lush, J., said the Court had no power to issue a warrant for their apprehension. (*Chester*, 44 L.T., 286.) In the same case, evidence that the clerk of the respondent's solicitor had offered an inducement to one of the petitioners to leave the city, was rejected.

Taking proofs  
of witnesses.

In conducting election petitions, it has been usual for the solicitors engaged to interview persons able to throw light upon the matter in dispute, and to take down their statements, and to obtain the signatures of such persons to their statements. The practice is a very useful one, but in all cases evidence should be preserved that the witness was not threatened or unduly influenced when he signed the statement and was not ignorant of what he signed. In the *Wigan Case* (4 O'M. & H., 1), the Court disapproved of such statements being obtained after it was known that the witnesses were about to be called on the other side or, *during the trial*. (*Chester*, 44 L.T., 286.)

Rewards for  
evidence.

It would seem to be legal to offer rewards for evidence. (*Mallow*, 2 O'M. & H., 19.)

Trial *de die  
in diem*.

So far as practicable, the trial of an election petition proceeds *de die in diem*, and the jurisdiction of the judges trying the case is not affected by the expiration of the term of the judges on the rota (Sec. 42 of the Act of 1883).

The Act of 1883 has done something to lengthen the trial of election petitions, by directing new inquiries to be made upon the trial. But it is probable, that so far as these inquiries may not concern the parties to the petition, they

will not go to the expense of attending the Election Court while issues which may be indifferent to them are being considered.

By Section 38, before any person, not being a party to the petition or a candidate for whom the seat is claimed, is reported by an Election Court to have been guilty of any corrupt or illegal practice, he is to be summoned by the Court and heard in his defence, and any evidence he may call, heard. This probably means that he may be heard by his counsel or solicitor, by whom witnesses may be examined and cross-examined. Compare the language of Section 43. The interest of the petitioner in such an inquiry will generally be remote. As to appeals from the report and special punishments, see Section 38 and Part II. *infra*.

New inquiries  
at the trial.

By Section 43, the Director of Public Prosecutions, or his representative, is to attend at the trial of the petition, in order to summon and there examine such witnesses as the Court may direct, and of his own motion to summon witnesses and to examine them with the leave of the Court, and before the Court, there to prosecute any person who appears to him to have been guilty of any corrupt or illegal practice, whereupon the Election Court shall proceed to try any person so prosecuted, unless a trial before some other Court be ordered in the interests of justice. Except that the Court (Section 43, Sub-section 8) may order the costs of the Director of Public Prosecutions to be paid by any of the parties to the petition or may report any of the parties to the petition to the Speaker of the House of Commons, their interest in the action of the Director will generally be remote.

The Act of 1883, makes a complete amnesty in respect of the past. In future, no witness can be asked, or will be bound to answer, on the trial of an election petition or before Election Commissioners, any questions for the purpose of proving the commission of any corrupt practice at or in relation to any election prior to the passing of the Act (Sec. 49). But if at an election, after the passing of the Act, A should pay B a sovereign, there can be no doubt that evidence tending to show a bargain made before the passing

No inquiry  
into past  
elections.

of the Act, that A should pay a sovereign to B for his vote hereafter, would be admissible as showing what the transaction really was.

Procedure  
upon the  
relief sections  
of the Act of  
1883.

Upon nearly every petition based upon allegations of corrupt or illegal practices, the parties should be prepared with evidence at the trial upon the issues raised by Section 22 of the Act of 1883. By that section the Court trying the petition is enabled to uphold the election, although the agents of the respondent may be proved to have been guilty of (a) treating, (b) undue influence, (c) or illegal practices, or all of these offences. The Court has no power to relieve where these offences, or any of them have been committed by the candidate himself, or where his agents are proved guilty of bribery or of personation, or of instigating personation.

It is exceedingly likely that in cases in which relief is granted to a respondent under Section 22, he will be ordered, unless it appears that the petition was frivolous and vexatious, or that other special circumstances exist, to pay the petitioner's costs of the petition.

Conditions  
precedent to  
relief under  
s. 22.

It is important to observe how stringent are the conditions to be complied with by the party seeking relief before he can be assisted.

He must satisfy the Court—for the burden is upon him to prove affirmatively—

- (1.) That the offences were of a trivial, unimportant, and limited character; *and*
- (2.) That they were committed contrary to the orders, *and* without the sanction *or* connivance of the candidate, or his election agent.
- (3.) That no corrupt or illegal practice was committed at the election by the candidate *or* his election agent.
- (4.) That both the candidate and his election agent took all reasonable means to prevent corrupt and illegal practices.

It would seem that the candidate is not required to prove that he and his election agent took any means to prevent the commission of the offences of illegal



employment, payments, hirings by other agents of the candidate.

(5.) That in all other respects the election was free from any corrupt or illegal practice by the candidate, or of any of his agents.

Proof of freedom from illegal employment, payment and hiring, is not required.

It will be difficult for a respondent to satisfy these stringent conditions, but it would seem that when he does satisfy them, the Court has no discretion—the election is saved.

The petitioner, on his side, should be prepared with evidence to prove that the respondent cannot satisfy the statutory conditions.

When the respondent, finding the return cannot be supported, has surrendered, and the election is declared void for corrupt practices, it has been usual for him to go into the box and declare on oath his personal innocence of any corrupt practice. In one case the Court allowed the respondent's legal agents to declare their innocence on oath. *Wigan*, 4 O'M. & H., 1. But in the *Boston Case*, 44 L.T. 287, the Court held that the rule must be adhered to, that the sitting members only could be called after the seat had been vacated.

Respondent's declaration of personal evidence.

If on the trial of the election petition the two judges trying the petition should differ in opinion as to whether the respondent was duly elected, the respondent will retain his seat (42 & 43 Vict. c. 75). On the same principle, if the judges differ as to the subject of a report to the speaker, they are to certify the difference, and make no report on the subject in difference (*ibid.*).

Difference of opinion between the judges.

When the trial is concluded, the Registrar will ascertain and certify the amount to be paid to any witness whose expenses may be allowed by the Court (Rule 5 of 1875). The registrar's certificate is not conclusive as between the petitioner and the respondent. The registrar only taxes between the witness and the party who subpoenaed him. (*McLaren v. Home*, 7 Q. B. D. 477, 50 L. J., C. L. 658.)

Witnesses, expenses to be taxed by Registrar.

## SECTION III.—ON A SCRUTINY.

When a  
scrutiny is  
made.

A scrutiny takes place when the petition claims the seat for one or more of the defeated candidates as having been duly elected. The seat is not often claimed by a petition because of the difficulty in wiping off any but the most inconsiderable majority upon a scrutiny, the cost of a scrutiny and the fact that when the seat is claimed by the petition, it becomes permissible for the respondent to give recriminatory evidence against the candidate for whom the petition claims the seat (31 & 32 Vict. c. 53). Any person entitled to petition is entitled to claim a scrutiny of the votes given, upon an allegation that a candidate other than the person returned was duly elected. But after such a petition has been presented, the claim of the seat may be withdrawn with the leave of the Court on motion or a judge at chambers on summons (*Stroud*, 3 O'M. & H., 7). But, ordinarily, the Court will not allow the claim of the seat to be withdrawn (*Albidge v. Hurst*, 1 C.P.D., 410; 45 L.J., C.P. 431; 35 L.T. 156; 24 W.R. 708).

Who entitled  
to claim.

Withdrawal  
of claim.

Recrimina-  
tory case  
when  
excluded.

If the petitioner, at the trial, having established that the respondent's election was void for corrupt practices, should then abandon the claim of the seat, recriminatory evidence cannot be gone into (*Gravesend*, 44 L.T. 64; 3 O'M. & H., 81). Indeed, if once it be ascertained that there is no claim laid to the seat, even the account of the election expenses of the unsuccessful candidate sent to the returning officer could not be called for (*Thirsk*, 3 O'M. & H., 113\*).

Forms of  
petitions for  
scrutiny.

For forms of petitions in cases in which the seat is claimed see the General Rules (Parliamentary), 1868; r. 5, *Stroud*, 3 O'M. & H., 7, and *Berwick*, 3 O'M. & H., 178; 44 L.T., 289.

Inspection  
of ballot  
papers, &c.

In cases of scrutiny and whenever questions of the improper rejection or reception of voting papers arise, it is generally desirable, before trial, to obtain inspection of the rejected ballot papers, the counted ballot papers, and sometimes, of the sealed packet of counterfoils. A judge at

chambers may order inspection of the rejected ballot papers to be had, but only the Court can order inspection of the counted ballot papers and counterfoils. The Ballot Act, 1872, Section 1, rr. 40 & 41. The procedure is by summons or motion.

Any application for inspection must be supported by affidavit. The Court will jealously preserve the secrecy of the ballot. In the *Tyrrone Case*, 21 W.R. 627; 7 I.R., C.L., 190, the Court would not allow either party to see the counterfoils or the backs of the ballot papers, but only their faces. This was followed in *Stowe v. Jolliffe* (L.R. 9 C.P., 447; 43 L.J., C.P. 173, 30 L.T. 299; 22 W.R., 946), but in neither of these cases was it alleged that votes improperly marked had been received. In the *Berwick Case* (1880), the judge at chambers, by consent of both parties, ordered inspection of the counterfoils and all the ballot papers.

All the other documents forwarded by the returning officer to the clerk of the Crown, including the marked register, are open to public inspection, Ballot Act, 1872, Section 1 r. 42 (*James v. Henderson*, 43 L.J., C.P., 238; 30 L.T., 527). It is immaterial that a scrutiny is not prayed (*ibid.*).

The practice up to trial in scrutiny cases is similar to that in cases of ordinary petitions, except that the petitioner is bound, in addition to particulars, to deliver scrutiny lists, and the respondent must deliver scrutiny lists and a list of his objections to the election of the candidate for whom the seat is claimed.

Delivery of  
scrutiny lists  
and list of  
objections.

The rules are as follows :—

RULE VII. (1868.)—"When a petitioner claims the seat for an unsuccessful candidate, alleging that he had a majority of lawful votes, the party complaining of or defending the election or return, shall six days before the day appointed for trial deliver to the master and also to the address, if any, given by the petitioners and respondent, as the case may be, a list of the votes intended to be objected to and of the heads of objection to each such vote, and the master shall allow inspection and office copies of such lists to all parties concerned; and no evidence shall be given against the validity

of any vote nor upon any head of objection not specified in the list, except by the leave of the Court or judge upon such terms as to amendment of the list, postponement of the inquiry and payment of costs as may be ordered."

RULE VIII. (1868).—"When the respondent in a petition under the Act, complaining of an undue return and claiming the seat for some person, intends to give evidence to prove that the election of such person was undue, pursuant to the fifty-third section of the Act, such respondent shall, six days before the day appointed for trial, deliver to the master and also at the address, if any, given by the petitioner, a list of objections to the election upon which he intends to rely, and the master shall allow inspection and office copies of such lists to all parties concerned; and no evidence shall be given by a respondent of any objection to the election not specified in the list, except by leave of the Court or judge, upon such terms as to amendments of the list, postponement of the inquiry and payment of costs as may be ordered."

Application  
for par-  
ticulars.

If the respondent's list of objections is vague and general, the petitioner should apply at chambers for an order for particulars. The Court has probably jurisdiction to make such an order under Gen. Reg. (Parl.), 1868, r. 6.

Time for  
delivery of  
lists.

The scrutiny lists and list of objections must be delivered six clear days before the trial, exclusive of Sunday, and of the day of trial and of the day of service (*Joyce v. O'Donnel*, 22 W.R., 655); and if the lists are not delivered within the time the Court cannot allow evidence to be given against the validity of votes or allow a list to be subsequently delivered (*Nield v. Batty*, L.R. 9, C.P. 104, 43 L.J., C.P. 73, 29 L.T. 747, 22 W.R. 407). But if an imperfect list were delivered in proper time the Court could afterwards allow amendments in, or additions to, it to be made (*ibid. per Denman, J.*).

Order of pro-  
ceeding at  
the trial.

At the trial it has been most usual for the petitioner to open his general case against the respondent (without going into a scrutiny) with the view of disqualifying the respondent, whether he be in a majority or no. Then the respondent answers the case made against him, and proceeds to open his

general case against the unsuccessful candidate, which is then answered. Afterwards the scrutiny will, if necessary, be gone into. The reason for postponing the scrutiny is, that if both parties be disqualified (*e.g.*, for bribery by an agent) a scrutiny becomes useless. If the petitioner be so disqualified, his claim to the seat is gone, but the scrutiny may proceed for the purpose of unseating the other, by placing him in a minority, in which case there would be a new election. (*York, South-West Riding*, 10 O'M. & H. 213; *Southampton*, 1 O'M. & H. 222.) If the respondent be so disqualified, he may continue his resistance to the petitioner's efforts upon a scrutiny to place himself in a majority, and if the resistance be successful, there must of course be a new election. (*Norwich*, 19 L.T. 619, 1 O'M. & H. 8.)

The practice is not, however, invariable. In one case the petitioner, having withdrawn his general charges, proceeded with the scrutiny, and placed himself in a majority of three. Then the respondent proceeded with his general recriminatory charges and the scrutiny, and placed himself in a majority of three. (*Berwick*, 3 O'M. & H. 178, 44 L.T. 289.)

Practice not  
invariable.

When the scrutiny is opened it is for the petitioner to put himself (or the persons whom he alleges to have been duly elected) in a majority. For this purpose he may begin with any class of objections he likes, but it is usual to require him (and the respondent in his turn) to finish all his objections of the class he begins with before proceeding to any objection of another class. Thus, if the petitioner begins with a case of bribery, he finishes all the cases of bribery before opening any case of intimidation.

In the *Oldham Case* (20 L.T., 302, 1 O'M. & H., 151) there were four candidates standing on the poll in the following order, H., P., C. and S. The scrutiny proceeded in the first instance as between C. and P., on the understanding that when C. had been placed in a majority over P., the scrutiny should then be proceeded with as between S. and H.

Upon a scrutiny a voter, whose vote is attacked, has no *locus standi* as a party, and is not entitled to be heard by his

Elector has  
no *locus*  
*standi*.

counsel. (*Malcolm v. Parry*, L.R., 9 C.P., 614; 43 L.J., C.P., 331; 31 L.T., 331.)

The decision of the returning officer as to any question arising in respect of any ballot paper is final, subject to reversal on petition questioning the return. (The Ballot Act, 1872, Section 2.)

A petition may be presented on the sole ground that the returning officer has miscounted the votes, in which case the ballot papers will be re-counted in the presence of the Court. (*Renfrew*, 2 O'M. & H. 213.)

If the returning officer finds the votes equal, and he is a registered elector, he may, but he is not bound to, give a casting vote. (Ballot Act, 1872, Section 2.) If he gives no casting vote he will make a double return. As to the procedure where one of the candidates so returned is petitioned against and declines to oppose the petition see Section 40 of the Parliamentary Elections Act, 1868, Appendix.

Upon a scrutiny, only those persons whose names are on the register for the time being in force can be admitted as having been entitled to vote, and the register is conclusive of the right of any person upon it to vote although such person ought to have been struck off by the revising barrister. The Court, upon a scrutiny, will only strike off the votes of persons who ought not to be upon the register if from some inherent, or, for the time, irremovable quality in themselves, they have not the status of parliamentary electors—for instance, peers, women, persons holding certain offices or employments, and persons convicted of crimes which disqualify them from voting. (The Ballot Act, 1872, Section 7. *Stowe v. Jolliffe*, No. 2, 43 L.J., C.P. 265, L.R. 9, C.P. 734).

As votes perversely given for a candidate who is incapable of being elected after notice of his incapacity, are thrown away, they will be struck off upon a scrutiny, and so the candidate apparently in a minority may be returned. But if a candidate has been guilty of bribery he is not so incapacitated that votes given for him after notice of the bribery will be thrown away. It would be otherwise if notice were given that he had been found guilty of bribery. In order

Equality of  
votes.

On a scrutiny  
register  
generally  
conclusive.

Votes given  
after notice  
for a candi-  
date incapable  
of being  
elected.

that votes given after notice may be struck off, there must be something wanting in the candidate himself which cannot be supplied, the existence or non-existence of which is not dependent on argument or decision, but which the law insists shall exist in every one who puts himself forward as a candidate. (*Drinkwater v. Deakin*, L.R., 9 C.P., 626, 43 L.J., C.P., 355, 30 L.T., 832, not following *Trench v. Nolan*, Ir.L. Rep. 6 C.L., 464, or the *Norwich Case*, 19 L.T., n.s., 619, the *Clitheroe Case*, 2 P.R. & D., 276, 285 and *Moore v. Scully*, 9 Ir.L. Rep., C.L., 217.)

If a case arises for giving notice of the disqualification of a candidate, the notice should be express and positive, and it should be served personally upon as many electors as possible, and advertised generally. (*Yates v. Leach*, L.R. 9 C.P., 608, 609, 43 L.J., C.P., 377, 30 L.T., 790.)

Notice of  
candidate's  
incapacity.

Another class of votes which will be struck off upon a scrutiny is those given by ballot papers open to any of the following objections: (1) want of official mark; (2) voting for more candidates than entitled to; (3) writing a mark by which the voter could be identified; (4) unmarked or void for uncertainty. (Ballot Act, 1872, Schedule 1, r. 36.) On the other hand, ballot papers improperly rejected on any of these grounds may be added to the poll on a scrutiny. Generally, if the Court can infer that the voter intended to vote and gather for whom he intended to vote, the vote will be admitted. As to what marks on the ballot paper will render it good or bad, see *Wigtown*, 2 O'M. & H., 215, *Woodward v. Sarsons*, L.R., 10 C.P., 738, 44 L.J., C.P., 293, 32 L.T., 867, *Berwick*, 3 O'M. & H., 178, 44 L.T., 289. If the returning officer marked the paper with the voter's number on the register, as that might lead to identification of the voter, the vote would be bad. (*Woodward v. Sarsons*, *supra*.)

Ballot papers  
ill marked or  
defective.

The votes of the following classes of persons are also bad upon a scrutiny: (1) bribers; (2) persons bribed; (3) treaters; (4) persons treated; (5) persons guilty of using undue influence; (6) persons unduly influenced; (7) persons procuring personation; (8) personators; (9) paid agents

Votes struck  
off on a  
scrutiny.

employed for any of the purposes of the election, 30 & 31 Vict. c. 102, section 11; (10) returning officers; (11) persons convicted of corrupt practices (Parliamentary Elections Act, 1868, section 45); (12) infants; (13) women; (14) imbeciles and lunatics; (15) peers; (16) perhaps, aliens (see *Berwick*, 44, L.T., 289, 3 O'M. & H., 178, and *Oldham*, 1 O'M. & H., 151, 20 L.T., 302); (17) policemen; (18) traitors; (19) felons, and (20) the holders of certain offices the subject of statutory prohibitions.

Rule as to  
striking off  
votes for  
persons  
corrupted.

By the Ballot Act 1872, Section 25, "where a candidate on the trial of an election petition, claiming the seat for any person, is proved to have been guilty, by himself or by any person on his behalf, of bribery, treating or undue influence, in respect of any person who voted at such election, or where any person retained or employed for reward by or on behalf of such candidate for all or any of the purposes of such election, as agent, clerk, messenger, or in any other employment, is proved on such trial to have voted at such election there shall, on a scrutiny, be struck off from the number of votes appearing to have been given to such candidate, one vote for every person who voted at such election and is proved to have been so bribed, treated or unduly influenced, or so retained, or employed for reward as aforesaid." Rule 41 of the same Act seems to contemplate that the Court shall ascertain how the voter bribed did vote, and that his vote shall be struck off the poll of the candidate for whom he voted. The question becomes important where a voter bribed to vote for A votes for B. The section and the rule have been construed in the case of *Malcolm v. Parry*, L.R., 9 C.P., 610; 43 L.J., C.P., 331; 31 L.T., 331, with this result, that if a corrupt practice by a candidate, or his agent, is proved in regard to a voter, and that voter voted, upon a scrutiny, one vote in respect of such voter will be struck off the poll of such candidate without regard to the question whether the voter so corrupted voted for such candidate or for his opponent. If the corrupt practice was neither by a candidate nor his agent, the Court must look at the counterfoils to see how the voter voted, and strike a vote off the poll of the

When the  
ballot paper  
of the  
corrupted  
voter will be  
examined.



candidate for whom he voted. In each case proof that the voter acted corruptly is necessary.

Where on a scrutiny, one person (who voted) claims to be the person on the register, and it is alleged that another person who does not himself claim the vote, is the person on the register, the nature of the qualification may be inquired into for the purpose of deciding who is the elector—*Berwick*, 44 L.T., 289.

Two persons of the same name—one only on the register.

When a marked register shows that a voter has already voted, it is *primâ facie* sufficient for adding his subsequently tendered vote to the poll that he swears he did not previously vote, and that the marked register is wrong; and when the marked register shows that a voter did not vote, it is not conclusive on a scrutiny, but it may be proved that the voter did vote, and his vote, on a paper bearing the number of another elector, will be valid (*ibid.*).

Tendered votes.

If the judges differ in opinion on the question whether a vote ought to be *struck off* the poll, it remains on. If they differ on the question whether a vote ought to be *put on*, it is not put on. *Omnia presumuntur pro negantibus*. See *Berwick*, 3 O'M. & H., 178; 44 L.T., 287.

Difference of opinion between the judges.

#### SECTION IV.—THE EVIDENCE UPON ELECTION PETITIONS.

With some few exceptions, the rules of evidence on the trial of election petitions, are the same as those in force on the trial of actions at *nisi prius*. But the nature of the subject has caused the introduction of some special rules of evidence, and there are certain other exceptions to the general law derived from the practice of the House of Commons Committees which, until 1869, tried petitions against the returns of members. It is enacted by Section 26 of the Parliamentary Elections Act, 1868, "Until rules of court have been made in pursuance of this Act, and so far as such rules do not extend, the principles, practice, and rules on which committees of the House of Commons have heretofore acted in dealing with election petitions, shall be observed so

Generally the rules of the common law apply.

Exceptions.

far as may be by the court and judge in the case of election petitions under this Act." The rules (of 1868, 1869 and 1875) which are set out in the Appendix hereto, do not deal with the subject of evidence generally. The courts have faithfully followed the instructions contained in Section 26. One result, and that not a very happy result of the section, has been the refusal of the High Court to allow discovery of documents to be had or interrogatories administered on election petitions, following the practice of the committees of the House. The Act of 1883 makes no change in this respect, and indeed does not affect the rules of evidence heretofore observed by the Court.

As in other kinds of litigation, subject to the powers in the Court of amending the particulars, the petitioner must succeed *secundum allegata et probata*. Therefore, at *Greenock*, (10'M. & H., 247,) Lord Barcapple rejected altogether evidence of the polling booth having been placed in an illegal position, there being no specific allegation of that fact in the petition.

Witnesses  
ordered out  
of court.

The witnesses in the cause will be ordered out of court on the application of either side, but the agent of neither party will be ordered out of Court, although he may be charged with personal bribery. (*Knaresborough*, 3 O'M. & H., 141.)

If charges of personal misconduct are made against a candidate, the Court finds it "startling" if he is not called to deny them, and draws its own inference. (*Eresham*, 3 O'M. & H., 19.)

Formal proof  
of election.

It is not usual to require formal proof of the holding of the election and of the return. At *Coventry*, (20 L.T., 406, 1 O'M & H., 97,) Willes, J., said, "I shall not require the election to be proved in any of the cases. I know, as a matter of public notoriety, that there has been a general election, and therefore an election for the town of Coventry. There was a return for this borough. If the respondents were not returned at that election I ought to reject them. The poll books are here, and they tell me that an election was held."

Improper  
admission or  
rejection of  
evidence.

Perhaps no more important deviation from the common law, so far as regards the law of evidence, exists, than is to

be found in the fact that if the Election Court should erroneously admit or reject evidence, no appeal or new trial could be had (although the improper admission or rejection of evidence should have caused a miscarriage of justice) unless the judges should agree to reserve a case for the High Court under Section 12 of the Parliamentary Elections Act, 1868.

Again, as the trial of a petition is something more than a contest between the parties, and as the duties of the Court, especially under the Act of 1883, are in some sort inquisitorial, the rule at *nisi prius* that evidence tendered to contradict a witness upon some matter collateral to the issue is inadmissible, has not been adhered to in the trial of election petitions. In the *North Norfolk Case* (1 O'M & H., 239), Blackburn, J., admitted such evidence.

Discrediting  
and contra-  
dicting a  
witness.

Witnesses called by a petitioner are in most cases unfriendly, and often hostile. Therefore, where a witness is put into the witness-box to admit that he was bribed, has denied the fact, the party calling him has been allowed to put into his hands his previous written statement admitting the bribery, not for the purpose of discrediting him as a witness become hostile, under the Common Law Procedure Act, 1854, but—and the effect is much the same—for the purpose of testing and probing his memory. (*Chester*, 44 L.T. 285.)

But generally, the provisions of the Common Law Procedure Act, 1854, Section 22, are to be complied with. The circumstances connected with the making of the statement must be recalled to the witness's recollection, and he must, in the first instance, be proved to be hostile. (*Cheltenham*, 1 O'M. & H., 62; *Bradford*, 1 O'M. & H., 30.) That done, he may be cross-examined as to previous statements made by him, and inconsistent with his evidence in the box. The attempt to read a previous written statement to one's own witness and to put questions to him to show that the statement is true, has been discouraged by other judges.

Hostile  
witness.

And it was laid down in the *Wigan Case* (4 O'M. & H., 1) that these written statements, which it has been common to procure from witnesses before the trial, are of little value. If

Previous  
statement of  
witness.

a witness's signed statement is in direct conflict with his sworn testimony, the latter is not thereby invalidated. It is weakened, no doubt, but the judges must decide for themselves from the probabilities of the case, the demeanour of the witness, and the other circumstances proved, on which side the truth lies. In the same case, Grove, J., severely reprehended the practice of getting persons who were known to be witnesses on the other side, to sign statements at all. He made the same objections to the obtaining of such statements during the trial at all.

Admissions  
by witness.

Upon the principle of the *North Norfolk Case*, *supra*, where a man denied that he had been bribed, the Court allowed another person to be called to prove that the first had admitted the bribery in his hearing. (*Lichfield*, 1 O'M. & H., 22.) It is quite clear that the declarations of the petitioner against the character of his own witness are admissible against him (*Londonderry*, P. & K., 277; C. & R., 253; *Berwick*, June 30th, 1820); and as each voter is in a sense a party to the case when the seat is claimed, what the voter admits about his vote, showing that it was an invalid vote, is admissible upon a scrutiny. (*Tipperary*, 2 O'M. & H., 31.) But there is all the difference in the world between a scrutiny and an ordinary petition. Where it is sought to prove that a voter has made a statement of his having been bribed to a third person, and it is intended to fix the consequences of the bribery upon a person other than the voter himself, *e.g.*, the sitting member, the evidence of the person to whom the statement is alleged to have been made cannot be received until the voter himself has been called as a witness. (*Guildford*, 19 L.T., 733.)

Effect of the  
vote being  
claimed.

In the *Worcester Case* (3 O'M. & H., 135), in support of an allegation that the poll was improperly closed before four o'clock, a witness was called to prove that he was refused a ballot paper by the returning officer. He was asked in cross-examination "were you not bribed to vote?" but that question was disallowed. The Court considered his right to vote was concluded by the register, except where

the seat was claimed. (Acc. *King's Lynn*, 1 O'M. & H., 206.) Indeed, when the seat is not claimed, a witness may be put into the box to say: "A B gave me a sovereign to vote for C D," subject to this, that the Court may, in its discretion, require the agency of A B to be proved first. (cf. *King's Lynn*, 1 O'M. & H., 208; *Lichfield*, 1 O'M. & H., 22.) In the peculiar case of the death of the respondent before the trial of the petitioner and of the substitution of another respondent by the Court in his stead, it has been held that the admissions of the former respondent may be given in evidence against the substituted respondent. The latter steps into the shoes of the former. (*Tipperary*, 2 O'M. & H., 34.)

Court may require agency to be first proved.

In order to support a suggestion that the verdict of the constituency has been changed by bribery, the petitioner's election agent was called and asked what result was shown by the canvass books sent in to him by his sub-agents. The question has often been allowed without objection, but in this case it was objected to, and the objection was sustained. The evidence would clearly have been hearsay. The proper course was to call in the sub-agents to verify their canvass books and then to ask the chief agent, as an accountant, what the general result was. (*King's Lynn*, 1 O'M. & H., 206.) In the *Westminster Case* (1 O'M. & H., 95; 20 L.T., 238), a canvasser was allowed to be asked how many promises he had received, it being argued that his information on this point was, according to its character, likely or unlikely to discourage bribery by him.

Result of canvass.

The question, how a witness voted, cannot be put, for it tends to violate the secrecy of the ballot. On the same ground a witness cannot be asked, even in cross-examination, to what party he belongs. But there is some authority for saying that he may be asked to what party he holds himself out as belonging. (*North Durham*, 3 O.M. & H., 1; *Harwich*, 3 O'M. & H., 63.)

Secrecy of the ballot.

There has already been occasion to observe that the Act of 1883 proclaims an amnesty for past offences, and that a witness may not be asked as to any corrupt practices at an election

Acts done at previous elections.

before the passing of the Act. But evidence that the respondent had employed an agent convicted of bribery at a previous election would seem to be undoubtedly admissible still. Evidence that the respondent had employed persons whom on a previous petition he had charged with bribery is irrelevant. (*Taunton*, 2 O'M. & H., 68.) Even under the old law the court was very reluctant to connect the pending inquiry with what occurred at a previous election, and especially so where the respondent was not a candidate at that election. (*Windsor*, 1 O'M. & H., 95; 19 L.T., 615; *Westminster*, 20 L.T., 238.)

Corruption at  
municipal  
election.

But where it is suggested that bribery was committed at a municipal election in order to influence the voting at the parliamentary, evidence of the bribery at the municipal election is of course admissible. (*Beverley*, 20 L.T., 792, *Blackburn*, 20 L.T., 823; *Hastings*, 21 L.T., 234.)

\* It would seem that the proper court and time to try an objection to the *status* of the petitioner is not the election court, but the High Court, some convenient time before the day appointed for trial of the petition, but in the *Youghal Case* (21 L.T., 307), the election court admitted evidence to show that the petitioner had no *status* rather than imperil the legality and regularity of the trial by rejecting it.

Evidence of  
intimidation.

In a case of intimidation the respondent himself gave evidence that on the polling day he went to voters who were opposed to him and offered to give them his escort to protect them to the poll, they being afraid to go, although there were military and constabulary in the streets. This evidence had the contrary effect to what was intended, for the court treated it as conclusive evidence out of the respondent's own mouth to prove that there was not freedom of election in the borough. (*Drogheda*, 21 L.T., 402.)

The Stamp  
law.

An unstamped document may be given in evidence upon an election petition without paying the penalty. (*Windsor*, 1 O'M. & H., 6.)

Production of  
documents.

Documents in the possession of the other side, and particular notice to produce which has been given, may be called for, and when produced will generally be evidence. If not produced, secondary evidence of them may be given. (*Brad-*

*ford*, 1 O'M. & H., 30.) When the bank pass book of the respondent and that of his agent were called for it was held they must first be shown to be material to the issue. (*Tamworth*, 1 O'M. & H., 76); and when the respondent's canvass book was called for, Willes, J., said that any particular entry in it might be asked for. (*Northallerton*, 1 O'M. & H., 167.)

A candidate is not responsible for the acts of his election agents (other than the election agent appointed under the Act of 1883) done after the polling. (*North Norfolk*, 1 O'M. & H., 243; 21 L.T., 264; *Salford*, 1 O.M. & H., 133; 19 L.T., 120.) It would be otherwise if it were previously shown that the agent's act was done with the privity of the candidate. The relation of principal and agent, unless expressly continued, ends with the election; evidence of an act of bribery committed after the election may be admitted, but only for the purpose of shedding light on what took place before the election. (*Southampton*, 1 O'M. & H., 222.) On the general principle that the agency is terminated by the election, the declarations and admissions made by an agent after the election are not admissible in evidence against the candidate. (*Harwich*, 3 O'M. & H., 61; *Cheltenham*, 3 O'M. & H., 86.) In the *Dorset Case* (1 O'M. & H., 210), it was ruled that a witness might be asked what directions an agent gave him during the election, but not what statements the agent made. But query as to this.

Agency  
ceases with  
the poll.

Admissions  
by an agent.

Evidence of an intention by the respondent to pay bribes after the hearing of the election petition is also inadmissible, because in that case a fresh petition might be presented. (*Galway*, 1 O'M. & H., 303; Parliamentary Elections Act, 1868, Section 6.)

Evidence of  
intention to  
pay bribes.

By Parliamentary Elections Act, 1868, Section 32, it is enacted: "On the trial of an election petition under this Act, the judge may, by order under his hand, compel the attendance of any person as a witness who appears to him to have been concerned in the election to which the petition refers, and any person refusing to obey such order, shall be guilty of contempt of court. The judge may

Witnesses  
may be called  
by the Court.

examine any witness so compelled to attend, or any person in court, although such witness is not called and examined by any party to the petition. After the examination of a witness as aforesaid by a judge, such witness may be cross-examined by or on behalf of the petitioner and respondent, or either of them." Under this section witnesses were called by the Court in the *Salisbury Case* (3 O'M. & H., 134), but the prevailing opinion has been the duties of the judges are judicial and not inquisitorial. (*Chester*, 44 L.T., 287; *Stroud*, 2 O'M. & H., 107.) Now by the Act of 1883, Section 43, it is provided: "On every trial of an election petition, the Director of Public Prosecutions shall, by himself or by his assistant, or by such representative as hereinafter mentioned, attend at the trial, and it shall be the duty of such director to obey any directions given to him by the Election Court with respect to the summoning and examination of any witness to give evidence on such trial, and with respect to the prosecution by him of offenders, and with respect to any person to whom notice is given to attend with a view to report him as guilty of any corrupt or illegal practice. It shall also be the duty of such director, without any direction from the Election Court, if it appears to him that any person is able to give material evidence as to the subject of the trial to cause such person to attend the trial, and with the leave of the Court to examine such person as a witness." As the Director of Public Prosecutions will have little knowledge of the constituency, will be regarded with disfavour by the class of persons who can give evidence of corrupt practices, and will not be allowed to see the inside of counsel's briefs, it may be doubted whether this section will be found to be very efficacious or far-reaching in its operation.

And by leave  
by the Public  
Prosecutor.

#### SECTION V.—THE AWARDING AND TAXATION OF COSTS.

Costs in the  
discretion of  
the Court.

The costs of election proceedings are in the discretion of the Court, which will disallow any costs occasioned by "vexatious conduct, unfounded allegations, or unfounded objections," by



either party, and have regard to the "discouragement of any needless expense" by throwing the same on the author of it. Parliamentary Elections Act, 1868, Section 41. The general rule is that the costs follow the event, but "the event" may be distributive when the seat is claimed. Thus, where the petitioner succeeded in unseating the respondent and then withdrew his claim to the seat, he got no costs occasioned by the latter claim. *Graresend*, 44 L.T., 64, 3 O'M. & H., 81, and in the *Petersfield Case*, 2 O'M. & H., 94, where the charges of corrupt practices by agents failed, the petitioner had to pay the costs of those charges, irrespective of the result of the scrutiny.

Usually follow the event.

The petitioner, though successful, may be left to bear his own costs where (1) the petitioner is a man of straw, put up by others in order to avoid liability for costs (*Poole*, 2 O'M. & H. 123; 31 L.T., 171), but not where the petition is a *bonâ fide* petition by the petitioner, however poor he may be (*Wigan*, 4 O'M. & H., 1). (2) where the particulars were exceedingly voluminous, and made many charges which failed (*Westbury* 1 O'M. & H., 50; 20 L.T., 17; *Norwich*, 2 O'M. & H., 42). (3) where the petitioner has himself acted illegally or improperly. (*Wallingford*, 1 O'M. & H., 57; *Longford*, 2 O'M. & H., 7.)

Exceptions to the rule, where petitioner succeeds.

Or a successful petitioner may be ordered to bear a part of the costs. At *Beccles*, 44 L.T., 283, 3 O'M. & H., 145, he was ordered to pay the costs of unfounded charges of treating. At *Boston* (2) 44 L.T., 289, 3 O'M. & H., 150, he was ordered to pay the costs of charges which he withdrew, and no costs were allowed on either side in respect of charges not proven. At *Graresend*, 44 L.T., 64, 3 O'M. & H., 81, where the seat was claimed, and the election was avoided, and the claim to the seat abandoned, whereupon, by a mistake, the recriminatory charges were proceeded with, no costs of the recriminatory charges, or of the scrutiny, or of charges not proven, were allowed on either side.

A successful respondent has been deprived of his costs altogether, when there was reasonable and probable cause for presenting the petition. *Westminster*, 1 O'M. & H., 89;

Where respondent succeeds.

20 L.T., 228. *Coventry*, 1 O'M. & H., 97 ; 20 L.T., 405, or when the respondent and his agents had committed illegal acts. *Bolton*, 2 O'M. & H., 138 ; 31 L.T., 194. Where the respondent failed to prove some of his counter-charges, but was successful on the whole, the petitioner was ordered to pay two-thirds of his costs. (*Berwick*, 44 L.T., 289 ; 3 O'M. & H. 178.)

Where  
returning  
officer in  
fault.

Where the petition is caused by the errors of the returning officer, he is not, in the absence of wilful misconduct, ordered to pay costs. (*Hackney*, 2 O'M. & H., 77. *Wigtown*, 2 O'M. & H., 232. *Woodward v. Sarsons*, L.R., 10 C.P., 738 ; 44 L.T., C.P., 293 ; 32 L.T., 867. *Mayo*, 2 O'M. & H., 192.) Where the conduct of the returning officer is unsuccessfully impeached, the losing party will generally be ordered to pay his costs. (*Worcester*, 3 O'M. & H., 186.)

Agreement  
that no costs  
shall be asked  
for.

Effect has been given to an agreement between the parties that, whatever the result, neither shall ask for costs.

Guilty persons  
and con-  
stituencies  
may be  
ordered to  
pay costs.

The old rules relating to the incidence of costs were found to bear hardly upon innocent candidates, and the legislature has introduced a new rule, which will, in many cases, go far to relieve innocent parties of the burden of costs, and impose that burden on persons on whom it should in justice be placed.

By Section 44 of the Act of 1883, it is enacted :—

“(1.) Where upon the trial of an election petition respecting an election for a county or borough, it appears to the Election Court that a corrupt practice has not been proved to have been committed in reference to such election, by or with the knowledge and consent of the respondent to the petition, and that such respondent took all reasonable means to prevent corrupt practices being committed on his behalf, the Court may make one or more orders with respect to the payment either of the whole or such part of the costs of the petition as the Court may think right, as follows :—

When  
corruption  
general.

“(a.) If it appears to the Court that corrupt practices extensively prevailed in reference to the said election, the Court may order the whole or part of the costs to be paid by the county or borough ; and

“(b.) If it appears to the Court that any person or persons is, or are proved, whether by providing money, or otherwise to have been extensively engaged in corrupt practices, or to have encouraged or promoted extensive corrupt practices in reference to such election, the Court may, after giving such person or persons an opportunity of being heard by counsel or solicitor, and examining, and cross-examining witnesses to show cause why the order should not be made, order the whole or part of the costs to be paid by that person or those persons, or any of them, and may order that if the costs cannot be recovered from one or more of such persons, they shall be paid by some other of such persons, or by either of the parties to the petition, and

When individuals largely engaged in corruption.

“(2.) Where any person appears to the Court to have been guilty of the offence of a corrupt or illegal practice, the Court may, after giving such person an opportunity of making a statement to show why the order should not be made, order the whole or any part of the costs of, or incidental to any proceeding before the Court in relation to the said offence, or to the said person, to be paid by the said person.”

In solitary case of corrupt or illegal practice.

The order under this section may be made only by the judges who try the election petition, or by the High Court, if the matter comes before the High Court.—Section 64 of the Act of 1883. But there is no jurisdiction to make an order under Section 44 at all, unless two events, namely, that no corrupt practice, “by or with the knowledge of the respondent,” is proved, *and* that the respondent took all reasonable means to prevent corrupt practices. Apparently the jurisdiction would not be destroyed if the respondent had committed or encouraged illegal practices or illegal payments or the like, although in that event the Court would have little disposition to relieve an unsuccessful respondent of the liability to pay costs.

By what court.

When jurisdiction arises.

The jurisdiction conferred by the section is not large. If

corrupt practices extensively prevailed, the Court may throw the costs of the petition on the constituency. Having regard to the language of Sub-section 3 of Section 44, probably "costs of the petition" will be held to include the costs of both parties.

Inquiries  
precedent to  
order.

If the author of extensive corruption can be ascertained, the Court may order him to pay the costs of the petition, but only after the propriety of making the order has been tried out with all the machinery of counsel, solicitors, examination and cross-examination. In fact, after the petition has been heard there may be another trial to decide whether a third party is to pay the whole or any part of the costs, and as the petitioner and respondent will be deeply interested in the result of this latter trial, they must remain and see it out. In fact, being interested parties, they ought to be heard in or on it.

The last case is that in which it shall appear to the Court that some stranger to the petition has been guilty of a corrupt or *illegal* practice, in which case he may be ordered to pay, not the costs of the petition, but only the costs of any proceedings before the Court in relation to those offences, *e.g.*, of his prosecution before the Court. Such a person cannot be heard by his counsel as of right, or examine or cross-examine witnesses with a view of preventing the making of the order. He is only entitled to make a statement.

It is probable that in every case in which a respondent would have been ordered to pay the costs of a successful petition, he will still be ordered to do so in the event of a stranger to the petition ordered to pay them failing to comply with the order.

Expenses of  
witnesses.

As between a witness whose expenses were allowed by the judge and the party who subpoenaed him, the registrar, or if he is incapacitated, the judge of the Election Court will ascertain and certify the amount to be paid to the witness. Gen. Rules (Parl.), 1875, r. 5.

Enactments  
regarding the  
taxation of  
costs.

The taxation of costs is regulated by section 41 of the Parl. Elections Act, 1868, and by Section 44 Sub-section 3 of the Act of 1883. The former section enacts, "That all

costs, charges and expenses of and incidental to the presentation of a petition under this Act and to the proceedings consequent thereon, with the exception of such costs, charges and expenses as are by this Act otherwise provided for, shall be defrayed by the parties to the petition in such manner and in such proportions as the Court or judge may determine, regard being had to the disallowance of any costs, charges, or expenses which may, in the opinion of the Court or judge, have been caused by vexatious conduct, unfounded allegations, or unfounded objections on the part either of the petitioner or the respondent, and regard being had to the discouragement of any needless expense by throwing the burden of defraying the same on the parties by whom it has been caused, whether such parties are or not on the whole successful. The costs may be taxed in the prescribed manner, but according to the same principles as costs between attorney and client are taxed in a suit in the High Court of Chancery, and such costs may be recovered in the same manner as the costs of an action at law or in such other manner as may be prescribed." By Section 44 Sub-section 3 of the Act of 1883 it is enacted :—"The rules and regulations of the Supreme Court of Judicature with respect to costs to be allowed in actions, causes and matters in the High Court shall in principle and so far as practicable apply to the costs of petitions and other proceedings under the Parliamentary Elections Act, 1868, and under this Act, and the taxing officer shall not allow any costs, charges, or expenses on a higher scale than would be allowed in any action, cause, or matter in the High Court on the higher scale as between solicitor and client."

It would seem that Section 44, Sub-section 3, has not materially altered the principle on which the costs are to be taxed. "Charges and expenses" are still to be allowed, and the taxation is still to be as between solicitor and client. The only difference is that the costs are now expressly directed to be taxed on the higher scale, allowing, however, no more than would be allowed in an action of such importance, difficulty, and complexity as the petition.

Effect of the  
Act of 1883.

Costs as between solicitor and client, What are?

What is included in the expression, "Costs as between solicitor and client?" "Costs as between solicitor and client, payable by one party to another, will not include all costs to which the solicitor would be entitled as against his client. It is impossible to lay down with exactness any rule upon the subject, but generally it would seem that all such costs would be allowed as a solicitor would ordinarily incur in the conduct of his client's business, excluding those extraordinary costs which may have been occasioned, either by the default of the client, as by his incurring a contempt, or by his express instructions, as to employ an unusual number of counsel," *Morgan and Davey on Costs*, p. 4.

Costs to be taxed liberally.

Even as between party and party, a liberal scale of costs is to be allowed on taxation, when the action is one to which the higher scale is applicable, and, as between solicitor and client, there must be an extension of this allowance. This was the intention of the legislature. In a recent case the Court said—"It appears to us that the parties entitled to their costs under the orders were entitled to an indemnity for all costs that were reasonably incurred by them in the ordinary course of matters of this nature, but not to any extraordinary or unusual expenses incurred in consequence of over caution or over anxiety as to any particular case, or from considerations of any special importance arising from the rank, position, wealth, or character of either of the parties, or any special desire on his part to insure success. We think, also, that such extraordinary costs as an attorney would not be justified in incurring without distinct and special instructions from his client, ought not to be allowed, nor the costs of purely collateral proceedings upon which a party has failed, nor those which may have been occasioned by his default, negligence, or mistake." *Hill v. Peel*, L.R., 5 C.P., 180; 39 L.J., C.P., 89; 22 L.T., 98.

When court will review taxation.

If the taxing master, in taxing, proceeds upon a wrong principle, the Court will review his decision, but if he has not erred in principle, and has exercised his discretion so that it is only as to the amount to be allowed, the Court is generally unwilling to interfere. *Ibid.* 181.

As to the number of counsel to be allowed. In cases of unusual difficulty, complexity, or importance, three counsel may be allowed on taxation, *Wentworth v. Lloyd*, L.R., 2 Eq. 607, *Kirkwood v. Webster*, 9 Ch. Div. 239; 47 L.J., Ch. 880; 26 W.R., 812. But in petitions in which the evidence is not voluminous, and the trial is not likely to consume more than two or three days, it is usual to allow only two counsel. The costs of two counsel are always allowed. *Tillett v. Stracey*, L.R., 5 C.P. 185; 39 L.J., C.P. 93; 22 L.T., 101; 18 W.R., 631.

Number of  
counsel  
allowed.

As to the amount of counsel's fees. In the *Southampton Case* (L.R., 5 C.P., 174; 39 L.J., C.P. 89; 22 L.T., 98) the leading counsel received 200 guineas on his brief, and 50 guineas a day for refreshers, besides consultation fees. The junior received 150 guineas on his brief, and 30 guineas a day for refreshers, besides consultations. The master allowed just half of each of these fees, and disallowed the consultations. Looking at the difficulty and length of the case, the Court directed the taxation to be reviewed. Fees for consultations from day to day are to be allowed, *Tillett v. Stracey*, *supra*.

Amount of  
counsel's fees.

In the *Tamworth Case* (L.R., 5 C.P. 173; 39 L.J., C.P. 89; 22 L.T., 98) the leading counsel received 250 guineas with his brief, and 50 guineas a day for refreshers; and the junior 100 guineas with his brief, and 25 guineas a day for refreshers. The master allowed 100 guineas and 25 guineas a day refresher, and 75 guineas and 15 guineas a day refresher respectively. The case being one of an ordinary description, the Court declined to send the taxation back to the master to be reconsidered. In the *Penrlyn Case*, reported with the *Tamworth Case*, the master allowed each of the counsel 25 guineas extra on the brief, on account of the distance from town, and the Court declined to interfere. Cf. *Tillett v. Stracey*, L.R., 5 C.P. 185; 39 L.J., C.P., 93; 22 L.T., 101; 18 W.R., 631; *Hargreaves v. Scott*, 4 C.P.D. 21; 40 L.T., 35; 27 W.R., 323, a case of a municipal election.

The taxing master, in exercising his discretion as to the number of counsel, the amount of their fees, the number of

Regard to be  
had to  
circumstances  
of each case.

consultations, the amount of consultation fees and refreshers, and the expenses of subpoenas to witnesses, telegrams and messages, ought to have regard to the difficulty, magnitude and importance of the particular case. *Trench v. Nolan (the Galway Case)* 7 Ir.R., C.L., 445; 21 W.R., 640. In that case the Court held that the successful petitioner on taxation was entitled to—(1) The sums actually paid by him for copies of the shorthand writer's notes; (2) the expenses of witnesses *bonâ fide* summoned but not called (but compare *Tillett v. Stracey*, L.R., 5 C.P. 185; 39 L.J., C.P. 93; 22 L.T., 101; 18 W.R., 631); (3) the cost of an illustrated map of the county; (4) a retainer of 10 guineas paid to each of the two leading counsel; (5) the fees paid to the junior counsel on the hearing of a case reserved, as well as the fees of the leading counsel; and (6) the cost of proceedings to draw the fund deposited as security out of Court.

Instructions  
for brief and  
preliminary  
expenses.

As to instructions for brief and preliminary inquiries. In practice it will be found necessary, between the filing of the particulars and the delivery of the briefs, to make inquiries as to the evidence likely to be given, and generally to get up the case. In the *Tamworth Case*, *supra*, £105 were claimed for "instructions for brief," and £90 for money paid to a solicitor to prosecute the preliminary inquiries. The master disallowed the £90, and, the items making up the £90 not being before the Court, the Court refused to interfere. In the *Penrhyn Case*, *supra*, £105 were charged for "instructions for brief," and all the preliminary expenses in detail in addition. The master allowed £150 to include the preliminary expenses, and the Court would not interfere. In the *Southampton Case* £1,000 was charged for preliminary expenses, and the master allowed £105; but having regard to the circumstances of the case, the Court thought £105 insufficient, and sent it back to the master.

Master must  
examine the  
items.

The parties are entitled to have the master's judgment upon the particular items in the preliminary expenses, if they think fit, instead of their being included in the allowance of one sum in gross to cover the whole of what the Master may think right to be allowed (*Hill v. Peel*, L. R., 5 ;



C. P., 183; 39 L.J., C.P., 89; 22 L.T. 98). But the Master may allow a lump sum for instructions for brief, provided the items making up the lump sum have been brought before him, so as to enable him to judge whether it represents reasonable and proper charges (the *Barnstaple Case*, 44 L.J., C. P., 200).

If an excessive number of witnesses be subpoenaed, and the Master disallows the costs of some of them, the Court will not interfere (*Tillett v. Stracey*, *supra*). The same course will be taken if the successful party have all his witnesses in attendance day by day, and not merely a sufficient number to occupy the Court for the day (*McLaren v. Home*, 7 Q.B. Div., 417; 50 L.J., 658). The certificate of the Registrar of the amount for witnesses is not conclusive of the amount as between petitioner and respondent. The Master must still tax the witnesses' costs (*ibid.*). On an application to revise the taxation, it is wise to have the briefs in court (*Tillett v. Stracey*, *supra*). As to the time at which costs should be incurred, the time appointed for the delivery of particulars is not analogous to notice of trial in an action. Before the particulars are delivered the respondent may reasonably incur costs in preparing the defence (*Hughes v. Meyrick*, L.R. 5 C.P., 407; 39 L.J., C.P., 249).

Number of witnesses allowed.

In that case the trial was appointed for April 1. On March 22 an order for particulars was obtained. On March 23 and 27 briefs were delivered and witnesses subpoenaed; on March 29 notice of withdrawal of the petition was given. The Master taxed the costs from £920 down to £63. He disallowed the subpoenas and fees to counsel, and substantially the costs of drawing and copying briefs and all the expenses of preliminary inquiries. The Court decided that he was wrong, and sent the case back to him. The costs were then re-taxed at £700, including £288 for instructions for brief, £85 for drawing and copying briefs, and 100 guineas and 75 guineas on the briefs. In point of fact, £210 and £105 were paid on the briefs.

At what time costs to be incurred.

As to the scale of fees to be allowed for witnesses, see *Turnbull v. Janson*, 3 C.P.D., 264; 47 L.J., C.P., 384; 26 W.R., 815; *Mackley v. Chillingworth*, 2 C.P.D., 273;

Scale of fees to witnesses.

46 L.J., C.P., 484; 36 L.T., 514; 25 W.R., 650; and *M'Laren v. Home*, 7 Q.B.D., 477; 50 L.J., 658.

Recovery of  
costs.

In regard to the recovery of costs, it is provided by Section 58 of the Act of 1883:—(1.) “Where any costs or other sums (not being costs of a prosecution on indictment) are, under an order of an Election Court, or otherwise under this Act, to be paid by a county or borough, the Commissioners of Her Majesty’s Treasury shall pay those costs or sums, and obtain repayment of the amount so paid in like manner as if such costs and sums were expenses of Election Commissioners paid by them, and the Election Commissioners Expenses Acts, 1869 and 1871, shall apply accordingly as if they were herein re-enacted, and in terms made applicable to the above-mentioned costs and sums. (2.) Where any costs or other sums are, under the order of an Election Court or otherwise under this Act, to be paid by any person, those costs shall be a simple contract debt due from such person to the person or persons to whom they are to be paid, and if payable to the Commissioners of Her Majesty’s Treasury, shall be a debt to Her Majesty, and in either case may be recovered accordingly.”

Payment of  
security fund  
out of court.

As regards the money (if any) deposited by the petitioner in court, by way of security for costs and claims of witnesses, all claims to it will be adjudicated upon by the Court or a judge. The person claiming to be entitled to it should give notice to the other side that he is about to apply for payment out, and should so apply by judge’s summons at Chambers. The application must be supported by affidavits, proving that due notice of intention to apply has been given, and that all proper claims upon the fund have been satisfied or provided for. The judge, by his order, may direct payment either to the party in whose name the money was deposited, or to any person entitled to receive it. When the order has been made, drawn up and signed, it should be taken to the Clerk of the Lord Chief Justice of England, who will endorse on the order a draft on the Bank of England for the payment of the money. The bank will pay the amount on the presentation of the draft in the usual way. (Gen. Rules (Parl.), March, 1869.)

## PART II.

## THE PUNISHMENT OF OFFENDERS.

THE Act of 1883, with a view to the more effectual repression of offences against the election laws, provides increased facilities for detecting offenders, a new machinery for their prosecution, and augmented penalties for their punishment.

## CHAPTER I.

## THEIR DETECTION AND PROSECUTION.

Heretofore the most efficacious means of unearthing corruption in a constituency has been found to be the appointment of Election Commissioners, who visited the particular county or borough, and, armed with the largest powers, held an exhaustive inquiry on the spot. These commissioners were appointed by the Crown under the 15th & 16th Vict. c. 57, and the 31st & 32nd Vict. c. 125, upon the joint address of both Houses of Parliament; but there was this limitation upon their appointment, that they could only be appointed when an Election Court had reported that there was reason to believe that corrupt practices had extensively prevailed in the constituency to which they were sent. Now, by Section 12 of the Act of 1883, Election Commissioners may be appointed when the report is that there is reason to believe that either *corrupt practices* or *illegal practices* extensively prevailed at the election. And the Commissioners will then be bound to inquire into the prevalence of

Inquisitorial  
powers of  
commis-  
sioners.

Now much  
extended.

illegal practices as well as corrupt practices, and report to the House accordingly. Having regard to the fact that the Act of 1883 creates some fifteen or sixteen new offences, which it calls illegal practices, it is obvious that there is here a considerable extension of the jurisdiction of the Commissioners. The latter have the largest powers of examining witnesses on oath, compelling attendance and the production of books and documents ; and witnesses examined before them are not entitled to any common law right of refusing to answer questions which may tend to criminate them. They are bound to answer, though, if they answer truly, they become entitled to certificates of indemnity, which will protect them against any criminal prosecution (except for perjury), though they may still be scheduled by the Commissioners in their report as guilty of corrupt or illegal practices, as the case may be, and thereupon they come under the disabilities and incapacities to be presently mentioned. It is the duty of Election Commissioners to report the names of all persons whom they are satisfied have been guilty of corrupt or illegal practices, and to state whether certificates of indemnity have been given to them. And by Section 60, the reports of all Election Courts and of Election Commissioners shall be laid before the Attorney-General, "with a view to his instituting and directing a prosecution against such persons as have not received certificates of indemnity, if the evidence shall, in his opinion, be sufficient to support a prosecution."

But while there is this great extension of the jurisdiction of Election Commissioners as to the *class of offences* into which they may inquire, there is a remarkable limitation as to the *time* over which their inquiries may range. By the 15th & 16th Viet. c. 57, the Commissioners were directed, if they found corrupt practices at the last election, to inquire if there were any at the election before, and if they found there were, they were to investigate the election before that, and so on ; but now, by Section 49 of the Act of 1883, it is provided : "Notwithstanding the provisions of the Act 15th & 16th Viet. c. 57, or any amendment thereof in any case where after the

Witnesses  
may be com-  
pelled to  
criminate  
themselves.

An amnesty  
for the past.

passing of this Act any Commissioners have been appointed on a joint address of both Houses of Parliament for the purpose of making inquiry into the existence of corrupt practices at any election, the said Commissioners shall not make inquiries concerning any election that shall have taken place prior to the passing of this Act, and no witness called before such Commissioners, or at any election petition after the passing of this Act, shall be liable to be asked or bound to answer any question for the purpose of proving the commission of any corrupt practice at or in relation to any election prior to the passing of this Act, provided that nothing herein contained shall affect any proceedings that shall be pending at the time of such passing."

The extended jurisdiction of Election Commissioners is one fresh means of detecting offences. Another is the compulsory attendance at the trial of every election petition of a representative of the Director of Public Prosecutions. He attends there with two-fold functions. The one is, in proper cases, to prosecute offenders before the Election Court. The other is to protect the public interest and see that, as the result of an arrangement between the parties or otherwise, no evidence is suppressed or withheld which may cast further light upon the proceedings at the election under investigation.

The Director  
of Public  
Prosecutions.

His functions.

But, first, it should be observed that an election petition once presented cannot be withdrawn without the consent of the Court, nor until the Director of Public Prosecutions has been heard in opposition to its withdrawal. Very stringent conditions in regard to this matter are contained in Section 41. Section 43 defines the duties of the Director of Public Prosecutions in aid of the detection of offences: "On every trial of an election petition the Director of Public Prosecutions shall by himself or by his assistant, or by such representative as hereinafter mentioned, attend at the trial, and it shall be the duty of such director to obey any directions given to him by the Election Court with respect to the summoning and examination of any witness to give evidence on such trial, and with respect to the prosecution by him of

Withdrawal  
of petitions  
prohibited.

Attendance of  
Director at  
trial of every  
petition.

He has power  
to call  
witnesses.

offenders, and with respect to any person to whom notice is given to attend with a view to reporting him as guilty of any corrupt or illegal practice." And by Sub-section 2: "It shall also be the duty of such director, without any direction from the Election Court, if it appears to him that any person is able to give material evidence as to the subject of the trial, to cause such person to attend the trial, and with the leave of the Court to examine such person as a witness." The hearing of an election petition is, therefore, no longer a proceeding merely between the two parties, which can be brought to a conclusion when it suits their convenience; but is a public investigation which can be prolonged at the instance of the official attending in the public interest until either such disclosures have been made as justify the Election Court in reporting that there is reason to believe that corrupt or illegal practices extensively prevailed, or until the information to found criminal proceedings has been obtained by the Court, or until the Court in the exercise of its summary powers has administered adequate punishment itself.

Private  
prosecutions  
still per-  
missible.

Coming next to the machinery for the prosecution of offenders, it must be observed that the right of a private prosecutor to institute proceedings is in no way interfered with. Indeed Sections 10, 12 & 13, of the 17 & 18 Vict., c. 102, which in the case of private prosecutions for corrupt practices give the Court power: (1) When the prosecutor has duly entered into the recognizances mentioned in the 13th Section to order the defendant, if convicted, to pay him the costs and expenses to which he has been put, and which (2) direct that the defendant shall have his costs from the prosecutor when he is acquitted, are expressly extended to any private prosecution for the offence of a *corrupt practice* within the meaning of the new Act (Section 53).

Prosecutions  
generally by  
order of  
(a) Attorney-  
General.

It is, however, contemplated that, as a rule, prosecutions will be instituted by the special order of the Attorney-General, or by the Director of Public Prosecutions. Section 60, which directs that all reports of Election Courts and Election Commissioners shall be submitted to the Attorney-

General, with a view to his directing prosecutions, has already been mentioned. The duties cast upon the Director of Public Prosecutions are, however, more specific and onerous. And first, by Section 45, "When information is given to the Director of Public Prosecutions that any corrupt or illegal practices have prevailed in reference to any election, it shall be his duty, subject to the regulations under the Prosecution of Offences Act, 1879, to make such inquiries and institute such prosecutions as the circumstances of the case appear to him to require," and later sections provide that the costs and charges to which the Director of Public Prosecutions is put in connection with the prosecution of offenders against the election laws shall be provided in the same manner as the funds for the prosecution of felonies are provided. But he has not to wait for information. He has to seek it, and as we have seen already, his duty is to attend in person, or by his deputy, every Election Court. By Section 43, quoted above, he is bound to obey any instructions given him by the Election Court with respect to the prosecution by him of offenders; and not only so but by Sub-section 3 of the same section, "It shall also be the duty of the said Director, *without any direction from the Election Court*, if it appears to him that any person who has not received a certificate of indemnity has been guilty of a corrupt or illegal practice, to prosecute such person for the offence before the said Court, or if he thinks it expedient in the interests of justice before any other competent Court."

or (b) Director  
of Public  
Prosecutions.

Director may  
prosecute  
before Elec-  
tion Court.

## CHAPTER II.

## THEIR PUNISHMENT.

THE tribunals which have jurisdiction to inquire into corrupt and illegal practices, and to inflict penalties of a varying character upon offenders, are as follows:—

Courts which  
may punish.

1. Election Commissioners.
2. The Election Court.
3. A Court of Summary Jurisdiction.
4. The Court of Assize, or where the indictment is removed by *certiorari*, the Central Criminal Court, or the Queen's Bench Division of the High Court of Justice; and
5. The High Court of Justice, in suits for penalties.

It is proposed to consider what offences fall under the cognizances of each one of these tribunals and the extent and kind of punishment which may be inflicted.

## SECTION I.—ELECTION COMMISSIONERS.

An Election Commission is constituted of three members, who must be barristers of at least seven years' standing, "not being members of Parliament, or holding any office or place of profit under the Crown, other than that of a recorder of any city or borough" (15 & 16 Vict. c 57, s. 1).

Election Commissioners have no power to impose either fine or imprisonment upon any person who is shown to them to have committed an offence at an election. Their power is confined to reporting that he has been guilty of the particular corrupt or illegal practice in question, and *then by virtue of their report*, and though the person reported may have obtained a certificate of indemnity, certain disabilities attach to him. Section 38, Sub-section 5, of the Act of 1883, says:—"Every person who after the commencement of this

The effect of  
the report of  
Commis-  
sioners.



Act is reported by any Election Court, or *Election Commissioners* to have been guilty of any corrupt or illegal practice, shall, whether he obtain a certificate of indemnity or not, be subject to the same *incapacity*, as he would under the Act be subject to, if he had at the date of the report been convicted of the offence of which he is reported to have been guilty."

This section at once raises the question—What are the incapacities imposed upon a person by a conviction of either a corrupt or an illegal practice.

The incapacities imposed by it.

By Section 6 (3) a person convicted on indictment of any *corrupt practice* is incapacitated for a period of *seven years* from

- |  |   |
|--|---|
| (a.) Being registered as an elector or voting at any election in the United Kingdom, whether it be a Parliamentary election or an election for any public office.  | (1.) May not vote at any election.                |
| (b.) Holding any public or judicial office, and if he holds any such office the office shall be vacated.   | (2.) Nor hold office.                             |
| (c.) Being elected to or of sitting in the House of Commons during the seven years next after his conviction: and if at that date he has been elected, his election shall be vacated from the time of such conviction. | (3.) Nor sit in House of Commons for seven years. |

In addition to these incapacities, which result from the mere report of Election Commissioners, Section 38, Subsections 6, 7, 8 and 9 provides for other measures of severity being taken against the particular classes of persons mentioned in them when they are reported for any *corrupt practice*.

(4.) Special severities against.

(1). If the person reported is a justice of the peace, "whether he has obtained a certificate of indemnity or not," it is the duty of the Director of Public Prosecutions to report the case to the Lord Chancellor, with such evidence as may have been given of his guilt, and the Lord Chancellor, if he thinks fit, may remove him from the bench. (2). If the person reported is a barrister or a solicitor, or belongs to any profession, the admission to which is regulated by law, "whether such person has obtained a certificate of indemnity or not," the Director of Public Prosecutions must bring the

(1.) Justices of the Peace.

(2.) Barristers and solicitors.

matter before the Inn of Court, High Court, or tribunal having power to take cognizance of any misconduct of such person in his profession, and "such Inn of Court, High Court, or tribunal may deal with such person in like manner as if such corrupt practice were misconduct by such person in his profession." It would seem that the words "who belongs to any profession the admission to which is regulated by law," bring medical practitioners (See the 21 & 22 Vict. c. 56), and dentists (the 41 & 42 Vict. c. 33) within the operation of the section. It is probable, also, that it applies to the case of clergymen of the Churches of England and of Scotland, the admission to whose respective professions is certainly regulated by the ecclesiastical law. (3). If the person reported holds a licence or certificate under the Licensing Acts, and the particular corrupt practice for which he is reported is having "knowingly suffered any bribery or treating in reference to any election to take place upon his licensed premises," then, whether such person obtains a certificate of indemnity or not, it shall be the duty of the Director of Public Prosecutions to bring the report before the licensing justices. The justices are bound to enter the report on the proper register of licences, and they may, if they like, refuse to renew his licence in consequence.

The consequences which result from being reported by Election Commissioners as guilty of an *illegal practice* are not so serious. Section 10 provides that "a person guilty of an illegal practice shall, on summary conviction, be liable to a fine not exceeding one hundred pounds, and be incapable, during a *period of five years from the date of his conviction*, of being registered as an elector, or voting at any election (whether it be a parliamentary election or an election for a public office within the meaning of the Act), held for or within the county or borough in which the illegal practice has been committed." Therefore, the effect upon a person of being scheduled for illegal practices is, that for the next *five years* he is disqualified from being registered or voting—not generally, but *in the county or borough in which he has offended*.

(3.) It is submitted also against doctors, dentists and clergymen.

Severities against licensed persons.

May lose their licenses.

Effect of being reported for illegal practices.

It has been said that all these incapacities result from the mere report of Election Commissioners or the Election Court. They are in every case of a stringent, and in some cases of a ruinous character; and, therefore, it is important to see what precautions are taken to prevent the great injustice of the Commissioners reporting innocent persons.

Section 38 (1) so far as it is material to the action of Election Commissioners, provides—"Before any person is reported by Election Commissioners to have been guilty, at an election, of any corrupt or illegal practice . . . the Commissioners . . . shall cause notice to be given to such person, and, if he appears in pursuance of the notice, shall give him an opportunity of being heard by *himself*, and of calling evidence in his defence to show why he should not be so reported." It is not said that the person charged may appear by his counsel or solicitor, nor is it stated that he may cross-examine the witnesses who implicate him; but, when the nature of the penalties which he incurs if the report is adverse to him is considered, it is difficult to think that an accused person would be refused proper assistance, or the usual facilities for elucidating the truth. Cases are readily conceivable in which the person accused would be incapable of making a statement in self-defence in a crowded court. Without referring to the case of a dumb man, the accused may be a woman or an invalid.

The decision of the Commissioners is not final, for by Sub-section 2 of Section 38, every person reported by *Election Commissioners* to have been guilty at an election of any corrupt or illegal practice, may appeal against such report to the next court of oyer and terminer, or gaol delivery, that is, to the next assizes, in and for the county or place in which the offence is alleged to have been committed. The section contemplates the framing of rules to regulate the procedure incident to such appeals, and no doubt a code of rules will be issued in due course. But subject to such rules the section proceeds: "Such appeal may be brought, heard, and determined in like manner as if the Court were a court of

Persons heard  
in his defence  
before  
reported.

An appeal  
given.

Quarter Sessions, and the said commissioners were a court of summary jurisdiction, and the person so reported had been convicted by a court of summary jurisdiction for an offence under this Act." Notice of the appeal, which must be in writing, is to be given to the Director of Public Prosecutions within a time to be directed by rules of court, and subject to such rules then within three days after the appeal is brought. There is a provision that if the trial of appeals under Section 38 appears to the Lord Chancellor to be likely to interfere with the ordinary business of the assizes, he may direct that they shall be heard by the judges on the rota for the trial of election petitions, and one of such judges shall then proceed to the place in which the offences are alleged to have been committed, and hear and determine them. It is presumed that the appeals will be heard by a single judge without a jury, that counsel representing the Director of Public Prosecutions will support the report, and that the appellant will appear in person, or by counsel. The appeal will be in the nature of a re-hearing, and the Court will decide whether the report of the Commissioners is to be affirmed, or varied, or disallowed.

Appeal  
against report  
of Com-  
missioners.

## SECTION 2.—THE ELECTION COURT.

The Election Court consists of two judges of the Queen's Bench Division, selected from the rota of judges appointed every year to try election petitions. The primary object with which the Election Court sits, is to try a particular election petition; but in addition to this duty, it is now bound to report to the Speaker (*a*) whether any corrupt practice or illegal practice has or has not been proved to have been committed by or with the knowledge and consent of any candidate at such election, and the nature of such corrupt or illegal practice: (*b*) the names of all persons, if any, who have been proved at the trial to have been guilty of any corrupt or illegal practice; and (*c*) whether corrupt or illegal practices have, or whether there is reason to believe,

What the  
Election Court  
must report  
to the  
Speaker.

corrupt or illegal practices have extensively prevailed at the election to which the petition relates (Section 11).

That is one duty cast upon the Election Court, in addition to the trial of the petition. Another duty is, subject to the important limitation on this jurisdiction to be presently stated, summarily to try all such persons as may be charged before it by the Director of Public Prosecutions with any corrupt or illegal practice committed at the election.

The effect of the report of the *Election Court* must be considered, first, as it affects the candidate, and secondly, as it affects other persons. The incapacities imposed upon a candidate by the report materially differ, according as he is declared to have committed a corrupt practice personally, or by his agent, or an illegal practice personally or by his agent. These must be carefully distinguished.

(A.) If the Election Court report that any *corrupt* practice (other than treating or undue influence) has been committed with reference to such election *by* or *with the knowledge and consent of any* candidate at such election (whether the successful or the unsuccessful one), or that the offence of treating or undue influence has been committed *by* any candidate, then such candidate, in addition to being unseated, is declared (a) incapable of *ever* sitting in the House of Commons for the said county or borough; (b) of sitting in the House of Commons for *any constituency* for the next seven years; (c) of being registered as an elector or voting at *any election* in the United Kingdom (whether a parliamentary election or any election for any public office) during a period of seven years; (d) of holding any public or judicial office for seven years; and (e) if he happens to be a justice of the peace, or a licensed person, or belongs to any one of the professions mentioned in Section 38, his misconduct has to be brought by the Director of Public Prosecutions under the cognizance of the Lord Chancellor, or the licensing justices, or any tribunal connected with his profession that takes notice of professional misconduct.

(B.) On the other hand, the Election Court may

The effect of the report.

(a) When candidate guilty of corrupt practice.

(b) When candidate *by*

*his agent guilty of corrupt practice.*

report that a candidate (whether the successful or unsuccessful one) has been guilty, by *his agents*, of any corrupt practice; then in addition to losing his seat, if he has been elected, he is incapable for the next *seven years* of sitting in the House of Commons for *the county or borough in which the offence was committed*.

(c) When candidate guilty of illegal practice.

(C.) The third possible report which the Election Court may make, is that some *illegal practice* has been committed *by* or *with* the knowledge and consent of any candidate. In that case the candidate, in addition to losing his seat, if he has been elected, is (a) incapacitated from sitting in the House of Commons for the county or borough in which the offence was committed for the next *seven years*; and (b) he is rendered incapable for the next five years of being registered as an elector, and voting at any election (whether a parliamentary election or an election to any public office) held for the county or borough in which the offence was committed.

(d) When candidate guilty by agent of illegal practice.

(D.) If, as the fourth alternative, the report is that the candidate by any agent has been guilty of an illegal practice, the seat is avoided if he fills it, and he is declared incapable of being elected for the same place during *the Parliament for which the election was held*.

Effect of report of Election Court upon other persons.

The Election Court also reports the names of all other persons who have been guilty of corrupt or illegal practices. The disabilities which such report imposes upon those persons are exactly the same as those imposed by the report of Election Commissioners. They have been set out in detail at page 181 and it is unnecessary to repeat them here.

Persons to be heard before reported.

Before an Election Court reports any person as being guilty of a corrupt or illegal practice, it is bound by Section 38 to cause notice to be given to such person, and if he appears in pursuance of such notice, he shall have an opportunity of being heard by himself, and of calling evidence in his defence to show why he should not be reported. We have already said, that although there is no express provision that a person charged with a corrupt or illegal practice

may appear by his counsel, and exercise the right of cross-examining the witnesses who inculcate him, we think such assistance and facilities cannot be withheld from him. It is especially desirable that a person should have every aid he is anxious to supply himself with before the Election Court, as there is no appeal whatever from its decision. It would be a great hardship if a candidate could be subjected to so severe a penalty as exclusion *for life* from the representation of a particular constituency, and exclusion for *seven years* from the representation of *any* constituency by a decision from which there is no appeal, without being allowed the same assistance in presenting his case, as would be accorded to him in the most trumpety civil dispute. Although the language of the 38th Section is defective on this point, we cannot but think that the rules of Court will rectify the omission

The other jurisdiction which the Election Court has is in the summary trial of any person charged with a corrupt or illegal practice. (Section 43 (4).) The Director of Public Prosecutions, or his representative, has apparently a discretion whether a person charged with corrupt or illegal practices shall be tried before the Election Court, or some other competent Court. He may, if the alleged offender is present, forthwith prosecute him before the Election Court, subject to this, that the latter cannot in most cases impose as heavy a sentence as it will be seen may be imposed on a trial upon indictment or information. If, however, the charge is preferred before the Election Court, by Section 55 "the Summary Jurisdiction Acts shall, so far as is consistent with the tenor thereof, apply to the prosecution of an offence summarily before an Election Court in like manner, as if it were an offence punishable only on summary conviction, and accordingly the attendance of any person may be enforced, the case heard and determined, and any summary conviction by such Court be carried into effect and enforced, and the costs thereof paid, and the record thereof dealt with under these Acts in like manner as if the court were a petty sessional court for the county or place in

Power of the  
Election  
Court to try  
offenders.

which such conviction took place." The effect of this is that the procedure on the trial of an offence against the election law is assimilated to the procedure in petty sessions. The accused is present, and is entitled to call, examine, or cross-examine witnesses either by himself or his counsel or solicitor, and to address the Court by himself or by his counsel or solicitor.

When  
accused  
entitled to  
a jury.

Where, however, the charge is that of a *corrupt* practice, by Section 43 (4), the Court, before proceeding to try summarily any person, shall give such person the option of being tried by a jury. It seems, therefore, that so far as charges of illegal practices or illegal hirings, employments or payments are concerned, the Election Court has complete criminal jurisdiction, and the accused has no right of trial by a jury. This is the more important, as it is expressly provided by Section 55 that there shall be no appeal from any sentence passed by an Election Court.

The sentence  
the Court  
may impose.

The Court has power to impose a sentence of fine or imprisonment upon any person convicted of a *corrupt practice*—the fine not to exceed £200, and the imprisonment not to be for a longer term than six months *with* or without hard labour. There is no power to imprison for an *illegal practice*, but a fine of £100 may be inflicted. In addition, the effect of the conviction is to impose upon the person convicted all those incapacities and disabilities which result from the report of Election Commissioners, and which have already been stated.

The Election Court, as well as the High Court, will have power under Section 34 (2) to impose a fine not exceeding £500 upon any election agent who makes default in complying with an order directing him to deliver a statement of the particulars required to be contained in the returns and declarations of election expenses, or otherwise to do his duty in regard to the return of expenses.

The Election  
Court may  
commit for  
trial.

But, though the Election Court has absolute jurisdiction to summarily try any person charged with an illegal practice and a qualified jurisdiction to try persons charged with corrupt practices, it is not bound to summarily determine



any case brought before it. It may direct that the accused shall be prosecuted on indictment, or before a Court of summary jurisdiction, and it may commit him for trial. Accordingly (Section 43, Sub-section 5), in such a case, the Court makes an order, naming the tribunal before which the accused is to be tried; and steps must forthwith be taken to bring him before such tribunal. If the offence is an indictable one, and the accused is present before the Election Court, the latter may at once commit him into custody to await his trial, or hold him to bail. If it is only an offence punishable on summary conviction, the Court may hold him to bail, or order him to be taken before the Court of Summary Jurisdiction before which he is to be tried. On the other hand, if the accused is not present, the Election Court may issue a warrant for his apprehension, or a summons, in its discretion directing him to be taken, or to appear before a Court of Summary Jurisdiction.

### SECTION 3.—THE COURT OF SUMMARY JURISDICTION.

A Court of Summary Jurisdiction within the meaning of the Act of 1883, is constituted of any two justices of the peace sitting in Petty Sessions, or in the Metropolitan district, or in districts to which stipendiary magistrates have been appointed, of any one such stipendiary magistrate. Its functions in regard to offences against the election laws are twofold, viz., to commit accused persons to take their trial where the offence is an indictable one, or, when it is an offence punishable on summary conviction, to deal with it.

Powers of a  
Court of  
Summary  
Jurisdiction.

With regard to indictable offences, where the Election Court has issued its warrant or summons directing the accused to be taken before a court of summary jurisdiction, the proceedings before the latter are purely formal. "That court (*i.e.*, Court of Summary Jurisdiction), if the offence is an indictable offence, shall, on proof only of the summons or warrant and the identity of the accused, commit him to take his trial, or

To commit  
for trial.

cause him to give bail to appear and take his trial" (Section 43, Sub-section 6, c). In other cases, where an indictable offence is charged against any person, and he is brought before a Court of Summary Jurisdiction in order that he may be committed for trial, it is presumed that the procedure will be exactly the same as in the common case of a charge made of an indictable offence before justices in petty sessions, with a view to the commitment of the prisoner. A summons or warrant will be issued by the justices in the first instance, the depositions of witnesses will be taken and signed, the prisoner by himself, his counsel or solicitor, will have the usual facilities for cross-examining, calling evidence, and addressing the court, and if the justices are of opinion that there is a *prima facie* case, they will commit him for trial, either remanding him in custody or admitting him to bail.

Time within  
which pro-  
ceedings  
must be taken.

The Act of 1883, however, contemplates that a Court of Summary Jurisdiction will itself deal with and finally dispose of a considerable number of the offences enacted under it. Before we mention the classes of offences which this court has jurisdiction over, it should be observed that all charges under any of the Corrupt Practices Prevention Acts must be made within a certain limit of time. If that time is allowed to go by and no prosecution instituted, it is too late after that to prefer a charge; and this rule applies as much to any proceeding on indictment as to a summary proceeding before the Election Court or Justices. The limitation of time is given in the 51st Section, which provides that "A proceeding against a person in respect of the offence of a corrupt or illegal practice, or any other offence under the Corrupt Practices Prevention Acts, or this Act shall be commenced within *one year* after the offence was committed, or if it was committed in reference to an election with respect to which an inquiry is held by election commissioners it shall be commenced within one year after the offence was committed, or *within three months after the report of such commissioners is made, whichever last happens, so that it shall be commenced within two years after the offence was committed.*" The *issue* of a summons, warrant, writ, or

other process, shall be deemed to be the commencement of a proceeding within the meaning of the above section, where service or execution of the same on or against the alleged offender is prevented by his absconding or concealing himself, or by any other act on his part, and in other cases the *service* of the writ, &c., is the commencement of the proceedings.

The offences with which the Court of Summary Jurisdiction may deal, are:—

I. All *illegal practices*, whether committed by the candidate, his election agent, or any other person. There is no power of imprisonment upon conviction of any illegal practice, but a fine not exceeding £100 can be imposed, and there results from the fact of conviction, or from the fact of being reported by an election court or election commissioners, an incapacity to be registered as an elector or voting for the next five years in the county or borough in which the offence was committed (Section 10).

II. All illegal payments, hirings, and employments. These offences, it has already been explained, became illegal practices when committed by the candidate or his election agent, and they must be dealt with by the court accordingly; but committed by other persons they are something less than illegal practices and subject those guilty of them to a somewhat less punishment. There is no power of imprisonment; but a fine of £100 may be imposed. No incapacity, however, results from conviction of an illegal payment, hiring, or employment.

III. By Section 18, it is provided that every bill, placard, or poster, issued in reference to the election shall bear upon the face thereof the name and address of the printer and publisher thereof. If a candidate, or his election agent, is guilty of a breach of this enactment he commits an illegal practice. Any other person infringing it is not guilty of an illegal practice, nor does the offence which he commits receive any particular denomination, but he "shall be liable on summary conviction to a fine not exceeding £100."

In order to get rid as much as possible of technical

Offences with which Court of Summary Jurisdiction may deal.  
(1.) Illegal practices.

(2.) Illegal payments, &c.

(3.) Publishing bills, &c., without printer's name.

Rules as to  
procedure.

objections to the form of the charge, and to the necessary evidence of the holding of the election at which the offence was committed, it is provided by Section 53 (3) that it shall be sufficient to allege that the person charged was guilty of an illegal practice, payment, employment or hiring, as the case may be; and the certificate of the returning officer at an election that the election mentioned in the certificate was duly held, and that the person named in the certificate was a candidate at such election, shall be sufficient evidence of the facts therein stated. The accused, or the husband or wife of such person, may give evidence in the case (Section 53 (2)). And there is a provision that if, upon hearing the evidence, the Court is satisfied that, though an illegal practice merely is charged, in fact a corrupt practice has been committed, the accused may still be convicted of the former; and so where an illegal payment, hiring or employment is charged, and a corrupt or illegal practice is proved, there may still be a conviction for the former.

Appeal to  
Quarter  
Sessions.

The defendant has no right to a trial by jury, nor indeed does the Court of Summary Jurisdiction have any power to commit him for trial when an offence punishable on summary conviction is charged; but if he is *convicted*, by the 2nd Sub-section of the 54th Section, a right of appeal to Quarter Sessions is given to him: "A person aggrieved by a conviction by a Court of Summary Jurisdiction for an offence under this Act may appeal to Quarter Sessions against such conviction." Where the summary conviction has been made in a city or borough which has an independent Quarter Sessions, the appeal will go there and be heard by the recorder: when it is made anywhere else it will be to the County Quarter Sessions.

It is presumed that the procedure as to the time within which the appeal must be brought, and the notices to be given and so forth, will be the same as in the case of an ordinary appeal to sessions from a summary conviction. The appeal will be in the nature of a re-hearing, and the Quarter Sessions will have power to quash the conviction or affirm or

vary it. There is no appeal beyond the Quarter Sessions, but the latter has power, when any difficult question of law arises, to state a case for the opinion of the Queen's Bench Division.

#### SECTION 4.—THE COURT OF ASSIZE.

All offences punishable by indictment will be tried at the next Assize for the county in which they were committed, unless the Election Court deals with them, or any of them, summarily, under the provisions of Section 42, or unless, in the case of misdemeanours, the Attorney-General files an information in the Queen's Bench Division of the High Court of Justice. The Quarter Sessions has no jurisdiction at all in regard to indictable offences. There is, however, the amplest power of changing the venue and removing the trial either to the Central Criminal Court, or, when a special jury is ordered, into the Queen's Bench Division. (Section 50.) No indictment, however, can be transferred from the Assizes without the order of the High Court, which, however, may be issued when the Attorney-General, on the part of the Crown, suggests that it is expedient, for the purpose of justice, that the indictment should be tried in the Central Criminal Court, or where, owing to some special complication, either of law or fact, the Court is of opinion that a special jury should try the case.

Where  
indictable  
offences tried.

Venue may  
be changed.

The limitation with regard to the time within which proceedings must be taken, the provisions as to the form of the charge, the proof of the holding of the election, and the right of a defendant or his wife or her husband to give evidence, apply to a trial on indictment or on information as much as to trial before a Court of Summary Jurisdiction, and it is also provided that if, on an indictment for a corrupt practice, it is proved that an illegal practice only was committed, the defendant shall be acquitted of the former, but may be convicted of the latter (Section 52).

All corrupt practices within the meaning of the Act of 1883, are indictable offences; but the punishments which

All corrupt  
practices  
indictable.

the Court has power to inflict vary with the particular offence.

False  
declaration.

I. Any candidate or his election agent who makes a false declaration as to the election expenses is by Section 33 declared guilty of a corrupt practice, and, upon indictment, is liable to the same penalty as if he were convicted of *wilful and corrupt perjury*. The maximum penalty for perjury is *seven years' penal servitude*. Therefore, the Court has power to sentence a candidate or his election agent, who makes a false declaration, to such a term of penal servitude.

Personation.

II. "A person who commits the offence of personation or of aiding, abetting, counselling, or procuring the commission of that offence, shall be guilty of *felony*, and any person convicted thereof, on indictment, shall be punished by imprisonment for a term not exceeding two years, *together with hard labour*" (Section 6, Sub-section 2). The Court has no power to impose a fine for this offence. Upon conviction the punishment is imprisonment, and such imprisonment *must* be accompanied by hard labour.

Bribery,  
treating and  
undue  
influence.

III. "A person who commits any corrupt practice other than personation, or aiding, abetting, counselling or procuring the commission of the offence of personation, shall be guilty of a misdemeanour, and on conviction, on indictment, shall be liable to be imprisoned, *with or without hard labour*, for a term not exceeding one year, or to be fined any sum not exceeding £200" (Section 6, Sub-section 1). The corrupt practices which come under this sub section are bribery, treating and undue influence. It will be observed, that the penalty, which is severe enough, is appreciably less stringent than in the case of the other corrupt practices, viz., personation and a false declaration. There is a power to impose a fine instead of imprisonment, and where imprisonment is inflicted it is in the discretion of the Court to say whether it shall be with hard labour or not.

Corrupt  
withdrawal  
of petitions.

IV. By Section 41 (4) of the Act of 1883, if any person makes any agreement or terms, or enters into any under-

taking in relation to the withdrawal of an election petition, and such agreement, terms or undertaking is, or are, for the withdrawal of an election petition in consideration of any payment, or in consideration that the seat shall at any time be vacated, or in consideration of the withdrawal of any other election petition, he shall be guilty of a misdemeanour, and shall be liable on conviction on indictment to imprisonment for a term not exceeding 12 months and to a fine not exceeding £200.

It need hardly be added, that in addition to suffering a term of imprisonment or a fine, any person convicted of a corrupt practice at once comes under all the incapacities and disabilities, which at page 181 have been set out, and it may be repeated here, that though a person who has obtained a certificate of indemnity may not be proceeded against criminally in any court in respect of any corrupt or illegal practice, he is still liable to all the disabilities mentioned.

There is no appeal against a conviction upon indictment. If the innocence of a person convicted should afterwards be made manifest, the Crown may pardon the offence and remit any part of the punishment still to be endured, but the validity of the conviction cannot be impeached. With respect, however, to the incapacities which are nominally no part of the punishment of the offence, but result from the fact of the conviction, in certain circumstances a person may apply to the High Court to have them removed. Section 46 of the Act of 1883 is as follows:—"Where a person has either before or after the commencement of this Act become subject to any incapacity under the Corrupt Practices Prevention Acts or this Act, by reason of a conviction or of a report of any election court or election commissioners, and any witness who gave evidence against such incapacitated person upon the proceeding for such conviction or report is convicted of perjury in respect of that evidence, the incapacitated person may apply to the High Court, and the Court, if satisfied that the conviction or report, so far as respects such person, was based upon perjury, may order that such incapacity shall thenceforth

No appeal from conviction on indictment.

Procedure for reversal of incapacities.

cease and the same shall cease accordingly." This section contemplates an independent application to the High Court by any person under incapacity who desires to be relieved from it. A condition precedent to such application is the conviction for perjury of the person who gave evidence against him in respect of the evidence he so gave, and the Court, if satisfied that the conviction of the applicant or the report against him was based upon such perjured testimony, "may order that such incapacity shall thenceforth cease and the same shall cease accordingly."

*Ex-officio*  
information.

It has been mentioned that instead of a proceeding by indictment the Attorney-General may file an information against any person accused of an indictable misdemeanour against the election laws, and then the trial may be had either in London or the information may be sent down to the assizes for trial. In all material regards the procedure on the trial of an information is the same as on the trial of an indictment. (For the law and practice with reference to *ex-officio* informations see *Archbold's Criminal Evidence and Pleadings*, 19th ed. p. 116.)

#### SECTION 5.—CIVIL SUIT FOR PENALTIES.

Pecuniary  
penalties.

Under the old Acts directed against electoral corruption a common mode of punishing offenders was by exposing them to actions for penalties at the instance of any person who chose to bring them. In practice it has been found that this was a weak deterrent, and in consequence, most of the enactments which gave suits for penalties have been repealed and more stringent punishments substituted. In a few cases, however, the liability to pecuniary penalties is still preserved.

40s. for  
giving  
cockades.

1. By the 7th Section of the Act of 1854 it is provided "No candidate before, during, or after any election shall in regard to such election, by himself or his agent, directly or indirectly, *give or provide* to or for any person having a vote at such election, or to or *for any inhabitant* of the county,



city, borough, or place for which such election is held, any cockade, ribbon, or other mark of distinction; and every person so giving or providing shall for every such offence forfeit the sum of two pounds to such person as shall sue for the same *together with full costs of suit*." It will be remembered that by Section 16, Sub-section 1 of the Act of 1883, any *payment or contract for payment* made on account of, among other things, "banners, cockades, ribbons or other marks of distinction," is declared an illegal payment, imperiling the seat when committed by a candidate or his election agent. Section 7 of the Act of 1854 strikes at the mere *giving* of cockades to voters or inhabitants of the constituency in question, and though the seat is not affected by any violation of this enactment, any candidate or agent of a candidate who gives a bit of ribbon or a cockade exposes himself to an action in the High Court to recover the penalty of two pounds given by the statute.

2. Another case in which a person may be sued for an infringing of the election laws is under Section 33, Sub-section 5 of the Act of 1883, which provides that if the return and declaration of election expenses for a county or borough required by the Act are not transmitted within the time limited for that purpose, the candidate shall not sit or vote in the House of Commons as member for such county or borough "until either such return and declaration have been transmitted, or until the date of the allowance of such an authorised excuse for the failure to transmit the same, as in this Act mentioned, and if he sits or votes in contravention of this enactment *he shall forfeit one hundred pounds for every day on which he so sits or votes to any person who sues for the same.*"

£100 a day  
for sitting in  
Commons  
before  
expenses  
returned.

3. Section 61 (1) of the Act of 1883 is as follows: "Section 11 of the Ballot Act, 1872 shall apply to a returning officer or presiding officer or clerk who is guilty of any wilful misfeasance or wilful act or omission in contravention of this Act in like manner as if the same were in contravention of the Ballot Act of 1872." A reference to Section 11 of the Ballot Act shows that if any returning officer, presiding officer, or clerk is guilty of any wilful misfeasance,

£100 when  
returning  
officer guilty  
of misconduct.

wilful act or omission, he *forfeits to the person aggrieved a sum not exceeding one hundred pounds.*

£100 when  
registration  
officer guilty  
of misconduct.

4. Section 61, Sub-section 2, of the Act of 1883 provides that Section 97 of the Registration Act, 1843, shall apply to every registration officer who is guilty of any wilful misfeasance or any wilful act of commission or omission contrary to this Act in the same manner as if the same were contrary to the Act of 1843. The section in question of the Act of 1843 exposes the persons mentioned in it (*viz.*, every sheriff, under sheriff, clerk of the peace, town clerk, secondary returning officer, clerk of the crown, postmaster, overseer or other person or public officer required by the Act to do any matter or thing) to a penalty not exceeding one hundred pounds, to be recovered by any person aggrieved, when it is proved that any one of such persons has been guilty of a wilful act of commission or omission contrary to this Act.

Actions brought under any of these Acts will be commenced by writ in the Queen's Bench Division, and they will proceed in the way in which actions of contract or tort ordinarily proceed, down to and including judgment and execution.

## APPENDIX.

---

### CORRUPT PRACTICES PREVENTION ACT, 1854.

17 & 18 VICT. c. 102.

17 & 18 Vict.  
c. 102.

An Act to consolidate and amend the Laws relating to  
Bribery, Treating, and Undue Influence at Elections  
of Members of Parliament. [10th August, 1854.]

WHEREAS the laws now in force for preventing corrupt practices in the election of members to serve in Parliament have been found insufficient : And whereas it is expedient to consolidate and amend such laws, and to make further provision for securing the freedom of such elections :

Be it enacted by the Queen's most Excellent Majesty, by and with the advice and consent of the Lords Spiritual and Temporal and Commons, in this present Parliament assembled, and by the authority of the same, as follows :—

**2.** The following persons shall be deemed guilty of bribery, and shall be punishable accordingly : Bribery defined.

1. Every person who shall, directly or indirectly, by himself, or by any other person on his behalf, give, lend, or agree to give or lend, or shall offer, promise, or promise to procure or to endeavour to procure, any money or valuable consideration, to or for any voter, or to or for any person on behalf of any voter, or to or for any other person in order to induce any voter to vote, or refrain from voting, or shall corruptly do any such act, as aforesaid, on account of such voter having voted or refrained from voting at any election :
2. Every person who shall, directly or indirectly, by himself or by any other person on his behalf, give or procure, or agree to give or procure, or offer, promise, or promise to procure or to endeavour to procure, any office, place, or employment to or for any voter, or to or for any person on behalf of any voter, or to or for any other person, in order to induce such voter to vote or refrain from voting, or shall corruptly do any such act as aforesaid, on account of any voter having voted or refrained from voting at any election :

3. Every person who shall, directly or indirectly, by himself or by any other person on his behalf, make any such gift, loan, offer, promise, procurement, or agreement as aforesaid to or for any person, in order to induce such person to procure or endeavour to procure the return of any person to serve in Parliament, or the vote of any voter at any election :
4. Every person who shall, upon or in consequence of any such gift, loan, offer, promise, procurement, or agreement, procure or engage, promise, or endeavour to procure the return of any person to serve in Parliament, or the vote of any voter at any election :
5. Every person who shall advance or pay, or cause to be paid, any money to or to the use of any other person with the intent that such money or any part thereof shall be expended in bribery at any election, or who shall knowingly pay or cause to be paid, any money to any person in discharge or repayment of any money wholly or in part expended in bribery at any election: Provided always that the aforesaid enactment shall not extend or be construed to extend to any money paid or agreed to be paid for or on account of any legal expenses *bonâ fide* incurred at or concerning any election.

Bribery further defined.

3. The following persons shall also be deemed guilty of bribery, and shall be punishable accordingly :—

1. Every voter who shall, before or during any election, directly or indirectly, by himself or by any other person on his behalf, receive, agree, or contract for any money, gift, loan, or valuable consideration, office, place, or employment, for himself or for any other person, for voting or agreeing to vote, or for refraining or agreeing to refrain from voting at any election :
2. Every person who shall, after any election, directly or indirectly, by himself or by any other person on his behalf, receive any money or valuable consideration on account of any person having voted or refrained from voting, or having induced any other person to vote or refrain from voting at any election.

No cockades, &c., to be given at elections.

7. No candidate before, during, or after any election shall in regard to such election, by himself or agent, directly or indirectly, give or provide to or for any person having a vote at such election, or to or for any inhabitant of the county, city, borough, or place for which such election is had, any cockade, ribbon, or other mark of distinction ; and every person so giving or providing shall for every such offence forfeit the sum of two pounds to such person as shall sue for the same, together with full costs of suit.

Penalty.

Voters not to serve as special constables during elections.

8. No person having a right to vote at the election for any county, city, borough, or other place, shall be liable or compelled to serve as a special constable at or during any election for a member or members to serve in Parliament for such county, city, borough, or other place, unless he shall consent so to act ; and he shall not be liable to any fine, penalty, or punishment whatever for refusing so to act, any statute, law, or usage to the contrary notwithstanding.

**10.** It shall be lawful for any criminal court, before which any prosecution shall be instituted for any offence against the provisions of this Act, to order payment to the prosecutor of such costs and expenses as to the said court shall appear to have been reasonably incurred in and about the conduct of such prosecution : Provided always, that no indictment for bribery or undue influence shall be triable before any court of quarter sessions.

Costs and expenses of prosecutions.

**12.** In case of any indictment or information by a private prosecutor for any offence against the provisions of this Act, if judgment shall be given for the defendant, he shall be entitled to recover from the prosecutor the costs sustained by the defendant by reason of such indictment or information, such costs to be taxed by the proper officer of the court in which such judgment shall be given.

In cases of private prosecutions, if judgment be given for the defendant.

**13.** It shall not be lawful for any court to order payment of the costs of a prosecution for any offence against the provisions of this Act, unless the prosecutor shall, before or upon the finding of the indictment or the granting of the information, enter into a recognisance, with two sufficient sureties, in the sum of two hundred pounds (to be acknowledged in like manner as is now required in cases of writs of *certiorari* awarded at the instance of a defendant in an indictment), with the conditions following—that is to say, that the prosecutor shall conduct the prosecution with effect, and shall pay to the defendant or the defendants, in case he or they shall be acquitted, his or their costs.

**35.** On the trial of any action for recovery of any pecuniary penalty under this Act the parties to such action, and the husbands and wives of such parties respectively, shall be competent and compellable to give evidence in the same manner as parties, and their husbands and wives are competent and compellable to give evidence in actions and suits under the Act of the fourteenth and fifteenth Victoria, chapter ninety-nine, and “The Evidence Amendment Act, 1853,” but subject to and with the exceptions contained in such several Acts : Provided always, that any such evidence shall not thereafter be used in any indictment or criminal proceeding under this Act against the party giving it.

In actions for penalties, parties, &c., to be competent witnesses.

**38.** Throughout this Act, in the construction thereof, except there be something in the subject or context repugnant to such construction, the word “county” shall extend to and mean any county, riding, parts, or division of a county, stewardry, or combined counties respectively returning a member or members to serve in Parliament ; and the words “city or borough” shall mean any university, city, borough, town corporate, county of a city, county of a town, cinque port, district of burghs, or other place or combination of places (not being a county as hereinbefore defined) returning a member or members to serve in Parliament ; and the word “election” shall mean the election of any member or members to serve in Parliament ; and the words “returning officer” shall apply to any person or persons to whom, by virtue of his or their office, under any law, custom, or statute, the execution of any writ or precept doth or shall belong for the election of a member or members to serve in Parliament, by whatever name or title such person or persons may be called ; and the words “revising barrister” shall extend to and include an assistant barrister and chairman, presiding in

Interpretation of terms.

any court held for the revision of the lists of voters, or his deputy in Ireland, and a sheriff or sheriff's Court of Appeal in Scotland, and every other person whose duty it may be to hold a court for the revision and correction of the list of registers of voters in any part of the United Kingdom ; and the word "voter" shall mean any person who has or claims to have a right to vote in the election of a member or members to serve in Parliament ; and the words "candidate at an election" shall include all persons elected as members to serve in Parliament at such election, and all persons nominated as candidates, or who shall have declared themselves candidates at or before such election.

## PARLIAMENTARY ELECTIONS ACT, 1868.

31 &amp; 32 VICT. c. 125.

31 & 32 Vict.  
c. 125.

An Act for amending the Laws relating to Election Petitions, and providing more effectually for the Prevention of Corrupt Practices at Parliamentary Elections. [31st July 1868.]

WHEREAS it is expedient to amend the laws relating to election petitions, and to provide more effectually for the prevention of corrupt practices at Parliamentary Elections :

Be it enacted by the Queen's most excellent Majesty, by and with the advice and consent of the Lords Spiritual and Temporal, and Commons, in this present Parliament assembled, and by the authority of the same, as follows :—

*Preliminary.*

1. This Act may be cited for all purposes as "The Parliamentary Elections Act, 1868." Short title of Act.
  
2. The expression "the court" shall, for the purposes of this Act, in its application to England, mean the Court of Common Pleas at Westminster, and in its application to Ireland the Court of Common Pleas at Dublin, and such court shall, subject to the provisions of this Act, have the same power, jurisdiction and authority with reference to an election petition, and the proceedings thereon as it would have if such petition were an ordinary cause within their jurisdiction. Definition and jurisdiction of court.
  
3. The following terms shall in this Act have the meanings hereinafter assigned to them, unless there is something in the context repugnant to such construction (that is to say) : Interpretation of terms.
  - "Metropolitan district" shall mean the City of London and the liberties thereof, and any parish or place subject to the jurisdiction of the Metropolitan Board of Works : "Metropolitan district :"
  - "Election" shall mean an election of a member or members to serve in Parliament : "Election :"
  - "County" shall not include a county of a city or county of a town, but shall mean any county, riding, parts or division of a county returning a member or members to serve in Parliament : "County :"
  - "Borough" shall mean any borough, university, city, place or combination of places, not being a county as hereinbefore defined, returning a member or members to serve in Parliament : "Borough :"
  - "Corrupt practices," or "corrupt practice," shall mean bribery, treating, and undue influence, or any of such offences, as defined by Act of Parliament, or recognised by the common law of Parliament : "Corrupt practices :"
  - "Rules of Court" shall mean rules to be made as hereinafter mentioned : "Rules of Court :"
  - "Prescribed" shall mean "prescribed by the rules of court." "Prescribed :"

Provisions as to speaker.

4. For the purposes of this Act "Speaker" shall be deemed to include Deputy Speaker; and when the office of Speaker is vacant, the Clerk of the House of Commons, or any other officer for the time being performing the duties of the Clerk of the House of Commons, shall be deemed to be substituted for and to be included in the expression "the Speaker."

*Presentation and Service of Petition.*

To whom and by whom election petition may be presented.

5. From and after the next dissolution of Parliament a petition complaining of an undue return or undue election of a member to serve in Parliament for a county or borough may be presented to the Court of Common Pleas at Westminster, if such county or borough is situate in England, or to the Court of Common Pleas at Dublin, if such county or borough is situate in Ireland, by any one or more of the following persons:

1. Some person who voted or who had a right to vote at the election to which the petition relates; or,
2. Some person claiming to have had a right to be returned or elected at such election; or,
3. Some person alleging himself to have been a candidate at such election:

And such petition is hereinafter referred to as an election petition.

Regulations as to presentation of election petition.

6. The following enactments shall be made with respect to the presentation of an election petition under this Act:—

1. The petition shall be signed by the petitioner, or all the petitioners if more than one;
2. The petition shall be presented within 21 days after the return has been made to the Clerk of the Crown in Chancery in England, or to the Clerk of the Crown and Hanaper in Ireland, as the case may be, of the member to whose election the petition relates, unless it question the return or election upon an allegation of corrupt practices, and specifically alleges a payment of money or other reward to have been made by any member, or on his account, or with his privity, since the time of such return, in pursuance or in furtherance of such corrupt practices, in which case the petition may be presented at any time within 28 days after the date of such payment;
3. Presentation of a petition shall be made by delivering it to the prescribed officer or otherwise dealing with the same in manner prescribed;
4. At the time of the presentation of the petition, or within three days afterwards, security for the payment of all costs, charges and expenses that may become payable by the petitioner—
  - (a) To any person summoned as a witness on his behalf; or,
  - (b) To the member whose election or return is complained of (who is hereinafter referred to as the respondent) shall be given on behalf of the petitioner;
5. The security shall be to the amount of £1,000; it shall be given either by recognisance to be entered into by any number of sureties not exceeding four, or by a deposit of money in manner prescribed, or partly in one way and partly in the other.



7. On presentation of the petition the prescribed officer shall send a copy thereof to the returning officer of the county or borough to which the petition relates, who shall forthwith publish the same in the county or borough, as the case may be.

Copy of petition after presentation to be sent to returning officer.

8. Notice of the presentation of a petition under this Act, and of the nature of the proposed security, accompanied with a copy of the petition, shall, within the prescribed time, not exceeding five days after the presentation of the petition, be served by the petitioner on the respondent; and it shall be lawful for the respondent, where the security is given wholly or partially by recognisance, within a further prescribed time, not exceeding five days from the date of the service on him of the notice, to object in writing to such recognisance, on the ground that the sureties, or any of them, are insufficient, or that a surety is dead, or that he cannot be found or ascertained from the want of a sufficient description in the recognisance, or that a person named in the recognisance has not duly acknowledged the same.

Recognisance may be objected to.

9. Any objection made to the security given shall be heard and decided on in the prescribed manner. If an objection to the security is allowed it shall be lawful for the petitioner, within a further prescribed time, not exceeding five days, to remove such objection, by a deposit in the prescribed manner of such sum of money as may be deemed by the court or officer having cognisance of the matter to make the security sufficient.

Determination of objection to recognisance.

If on objection made the security is decided to be insufficient, and such objection is not removed in manner hereinbefore mentioned, no further proceedings shall be had on the petition; otherwise, on the expiration of the time limited for making objections, or, after objection made, on the sufficiency of the security being established, the petition shall be deemed to be at issue.

10. The prescribed officer shall, as soon as may be, make out a list of all petitions under this Act presented to the court of which he is such officer, and which are at issue, placing them in the order in which they were presented, and shall keep at his office a copy of such list, hereinafter referred to as the election list, open to the inspection in the prescribed manner of any person making application.

List of petitions at issue to be made.

Such petitions, as far as conveniently may be, shall be tried in the order in which they stand in such list.

### *Trial of a Petition.*

11.\* The following enactments shall be made with respect to the trial of election petitions under this Act:—

Mode of trial of election petitions.

1. The trial of every election petition shall be conducted before a *puisne* judge of one of Her Majesty's superior courts of common law at Westminster or Dublin, according as the same shall have been presented to the court at Westminster or Dublin, to be selected from a rota to be formed as hereinafter mentioned:

2. The members of each of the courts of Queen's Bench, Common

\* See changes in practice made by 42 & 43 Vict. c. 75, and the Act of 1883.

Pleas and Exchequer in England and Ireland shall respectively, on or before the third day of Michaelmas term in every year, select, by a majority of votes, one of the *puisne* judges of such court, not being a member of the House of Lords, to be placed on the rota for the trial of election petitions during the ensuing year :

3. If in any case the members of the said court are equally divided in their choice of a *puisne* judge to be placed on the rota, the Chief Justice of such court (including under that expression the Chief Baron of the Exchequer) shall have a second or casting vote :
4. Any judge placed on the rota shall be re-eligible in the succeeding or any subsequent year :
5. In the event of the death or the illness of any judge for the time being on the rota, or his inability to act for any reasonable cause, the court to which he belongs shall fill up the vacancy by placing on the rota another *puisne* judge of the same court :
6. The judges for the time being on the rota shall, according to their seniority, respectively try the election petitions standing for trial under this Act, unless they otherwise agree among themselves, in which case the trial of each election petition shall be taken in manner provided by such agreement :
7. When it appears to the judges on the rota, after due consideration of the list of petitions under this Act for the time being at issue, that the trial of such election petitions will be inconveniently delayed unless an additional judge or judges be appointed to assist the judges on the rota, each of the said courts (that is to say), the Court of Exchequer, the Court of Common Pleas, and Court of Queen's Bench, in the order named, shall, on and according to the requisition of such judges on the rota, select, in manner hereinbefore provided, one of the *puisne* judges of the court to try election petitions for the ensuing year ; and any judge so selected shall, during that year, be deemed to be on the rota for the trial of election petitions :
8. Her Majesty may, in manner heretofore in use, appoint an additional *puisne* judge to each of the courts of Queen's Bench, the Common Pleas, and the Exchequer in England :
9. Every election petition shall, except where it raises a question of law for the determination of the court, as hereinafter mentioned, be tried by one of the judges hereinbefore in that behalf mentioned, hereinafter referred to as the judge sitting in open court without a jury :
10. Notice of the time and place at which an election petition will be tried shall be given, not less than fourteen days before the day on which the trial is held, in the prescribed manner :
11. The trial of an election petition, in the case of a petition relating to a borough election, shall take place in the borough, and in the case of a petition relating to a county election, in the county : Provided always, that if it shall appear to the court that special circumstances exist which render it desirable that the petition should be tried elsewhere than in the borough or county, it shall be lawful for the court to appoint such other place for the trial as shall appear most convenient : Provided

- also, that in the case of a petition relating to any of the boroughs within the metropolitan district, the petition may be heard at such place within the district as the court may appoint :
12. The judge presiding at the trial may adjourn the same from time to time, and from any one place to any other place within the county or borough, as to him may seem expedient :
  13. At the conclusion of the trial the judge who tried the petition shall determine whether the member whose return or election is complained of, or any and what other person, was duly returned or elected, or whether the election was void, and shall forthwith certify in writing such determination to the speaker, and upon such certificate being given such determination shall be final to all intents and purposes :
  14. Where any charge is made in an election petition of any corrupt practice having been committed at the election to which the petition refers, the judge shall, in addition to such certificate, and at the same time, report in writing to the speaker as follows :
    - (a.) Whether any corrupt practice has or has not been proved to have been committed by or with the knowledge and consent of any candidate at such election, and the nature of such corrupt practice :
    - (b.) The names of all persons (if any) who have been proved at the trial to have been guilty of any corrupt practice :
    - (c.) Whether corrupt practices have, or whether there is reason to believe that corrupt practices have extensively prevailed at the election to which the petition relates :
  15. The judge may at the same time make a special report to the speaker as to any matters arising in the course of the trial an account of which in his judgment ought to be submitted to the House of Commons :
  16. Where, upon the application of any party to a petition made in the prescribed manner to the Court, it appears to the Court that the case raised by the petition can be conveniently stated as a special case, the Court may direct the same to be stated accordingly, and any such special case shall, as far as may be, be heard before the Court, and the decision of the Court shall be final ; and the Court shall certify to the speaker its determination in reference to such special case.

12. Provided always, that if it shall appear to the judge on the trial of the said petition that any question or questions of law as to the admissibility of evidence or otherwise require further consideration by the Court of Common Pleas, then it shall be lawful for the said judge to postpone the granting of the said certificate until the determination of such question or questions by the Court, and for this purpose to reserve any such question or questions in like manner as questions are usually reserved by a judge on a trial at *nisi prius*.

Applications to the court respecting trials.

13. The House of Commons on being informed by the speaker of such certificate and report or reports, if any, shall order the same to be entered in their journals, and shall give the necessary directions for confirming or altering the return, or for issuing a writ for a new election, or

House of Commons to carry out report.

for carrying the determination into execution, as circumstances may require.

House of  
Commons may  
make order on  
special report.

**14.** Where the judge makes a special report the House of Commons may make such order in respect of such special report as they think proper.

Report of the  
judge as to cor-  
rupt practices.

**15** If the judge states in his report on the trial of an election petition under this Act that corrupt practices have, or that there is reason to believe that corrupt practices have extensively prevailed in any county or borough at the election to which the petition relates, such statement shall for all the purposes of the Act of the Session of the fifteenth and sixteenth years of the reign of Her present Majesty, chapter fifty-seven, intituled "An Act to provide for more effectual Inquiry into the existence of Corrupt Practices at Elections of Members to serve in Parliament," have the same effect, and may be dealt with in the same manner as if it were a report of a committee of the House of Commons appointed to try an election petition, and the expenses of any commission of inquiry which may be issued in accordance with the provisions of the said Act shall be defrayed as if they were expenses incurred in the registration of voters for such county or borough.

Evidence of cor-  
rupt practices  
how received.

**17.** On the trial of an election petition under this Act, unless the judge otherwise directs, any charge of a corrupt practice may be gone into and evidence in relation thereto received before any proof has been given of agency on the part of any candidate in respect of such corrupt practice.

Acceptance of  
office not to  
stop petition.

**18.** The trial of an election petition under this Act shall be proceeded with notwithstanding the acceptance by the respondent of an office of profit under the Crown.

### *Proceedings.*

Form of peti-  
tion.

**20.** An election petition under this Act shall be in such form and state such matters as may be prescribed.

Service of  
petition.

**21.** An election petition under this Act shall be served as nearly as may be in the manner in which a writ or summons is served, or in such other manner as may be prescribed.

Joint respon-  
dents to peti-  
tion.

**22.** Two or more candidates may be made respondents to the same petition, and their case may for the sake of convenience be tried at the same time, but for all the purposes of this Act such petition shall be deemed to be a separate petition against each respondent.

Provision in  
cases where  
more than one  
petition is pre-  
sented.

**23.** Where, under this Act, more petitions than one are presented relating to the same election or return, all such petitions shall in the election list be bracketed together, and shall be dealt with as one petition, but such petitions shall stand in the election list in the place where the last of such petitions would have stood if it had been the only petition presented, unless the court shall otherwise direct.

24. On the trial of an election petition under this Act the shorthand writer of the House of Commons or his deputy shall attend and shall be sworn by the judge faithfully and truly to take down the evidence given at the trial, and from time to time as occasion requires to write or cause the same to be written in words at length; and it shall be the duty of such shorthand writer to take down such evidence, and from time to time to write or cause the same to be written at length, and a copy of such evidence shall accompany the certificate made by the judge to the speaker; and the expenses of the shorthand writer shall be deemed to be part of the expenses incurred in receiving the judge.

Shorthand writer to attend trial of election petition.

### *Jurisdiction and Rules of Court.*

25. The judges for the time being on the rota for the trial of election petitions in England and Ireland may respectively from time to time make, and may from time to time revoke and alter, general rules and orders (in this Act referred to as the rules of court) for the effectual execution of this Act, and of the intention and object thereof, and the regulation of the practice, procedure and costs of election petitions and the trial thereof, and the certifying and reporting thereon.

Rules to be made by court.

Any general rules and orders made as aforesaid shall be deemed to be within the powers conferred by this Act, and shall be of the same force as if they were enacted in the body of this Act.

Any general rules and orders made in pursuance of this section shall be laid before Parliament within three weeks after they are made, if Parliament be then sitting, and if Parliament be not then sitting, within three weeks after the beginning of the then next session of Parliament.

26. Until rules of court have been made in pursuance of this Act, and so far as such rules do not extend, the principles, practice and rules on which committees of the House of Commons have heretofore acted in dealing with election petitions shall be observed so far as may be by the court and judge in the case of election petitions under this Act.

Practice of House of Commons to be observed.

27. The duties to be performed by the prescribed officer under this Act shall be performed by such one or more of the masters of the Court of Common Pleas at Westminster as may be determined by the Chief Justice of the said Court of Common Pleas, and by the Master of the Court of Common Pleas at Dublin, and there shall be awarded to such Masters respectively, in addition to their existing salaries, such remuneration for the performance of the duties imposed on them in pursuance of this Act as the Chief Justices of the said Courts of Common Pleas in Westminster and Dublin may respectively, with the consent of the Commissioners of the Treasury, determine.

Performance of duties by prescribed officer.

### *Reception, Expenses and Jurisdiction of Judge.*

28. The judge shall be received at the place where he is about to try an election petition under this Act with the same state, so far as circumstances admit, as a judge of assize is received at an assize town; he shall be received by the sheriff in the case of a petition relating to a county election, and in any other case by the mayor, in the case of a borough having a mayor, and in the case of a borough not having a

Reception of judge

mayor, by the sheriff of the county in which the borough is situate, or by some person named by such sheriff.

The travelling and other expenses of the judge, and all expenses properly incurred by the sheriff or by such mayor or person named as aforesaid in receiving the judge and providing him with necessary accommodation and with a proper court, shall be defrayed by the Commissioners of the Treasury out of money to be provided by Parliament.

Power of judge.

29. On the trial of an election petition under this Act the judge shall, subject to the provisions of this Act, have the same powers, jurisdiction and authority as a judge of one of the superior courts and as a judge of assize and *nisi prius* and the court held by him shall be a court of record.

Attendance on judge.

30. The judge shall be attended on the trial of an election petition under this Act in the same manner as if he were a judge sitting at *nisi prius*, and the expenses of such attendance shall be deemed to be part of the expenses of providing a court.

#### Witnesses.

Summons of witnesses.

31. Witnesses shall be subpoenaed and sworn in the same manner, as nearly as circumstances admit, as in a trial at *nisi prius* and shall be subject to the same penalties for perjury.

Judge may summon and examine witnesses.

32. On the trial of an election petition under this Act the judge may, by order under his hand, compel the attendance of any person as a witness who appears to him to have been concerned in the election to which the petition refers, and any person refusing to obey such order shall be guilty of contempt of court. The judge may examine any witness so compelled to attend, or any person in court, although such witness is not called and examined by any party to the petition. After the examination of a witness as aforesaid by a judge, such witness may be cross-examined by or on behalf of the petitioner and respondent, or either of them.

Expenses of witnesses.

34. The reasonable expenses incurred by any person in appearing to give evidence at the trial of an election petition under this Act, according to the scale allowed to witnesses on the trial of civil actions at the assizes, may be allowed to such person by a certificate under the hand of the judge or of the prescribed officer, and such expenses, if the witness was called and examined by the judge, shall be deemed part of the expenses of providing a court, and in other cases shall be deemed to be costs of the petition.

#### Withdrawal and abatement of Election Petitions.

Withdrawal of petition and substitution of new petitioners.

35. An election petition under this Act shall not be withdrawn without the leave of the court or judge upon special application, to be made in and at the prescribed manner, time and place.

No such application shall be made for the withdrawal of a petition until the prescribed notice has been given in the county or borough to

which the petition relates of the intention of the petitioner to make an application for the withdrawal of his petition.

On the hearing of the application for withdrawal, any person who might have been a petitioner in respect of the election to which the petition relates may apply to the court or judge to be substituted as a petitioner for the petitioner so desirous of withdrawing the petition.

The court or judge may, if it or he thinks fit, substitute as a petitioner any such applicant as aforesaid; and may further, if the proposed withdrawal is in the opinion of the court or judge induced by any corrupt bargain or consideration, by order direct that the security given on behalf of the original petitioner shall remain as security for any costs that may be incurred by the substituted petitioner, and that to the extent of the sum named in such security the original petitioner shall be liable to pay the costs of the substituted petitioner.

If no such order is made with respect to the security given on behalf of the original petitioner, security to the same amount as would be required in the case of a new petition, and subject to the like conditions, shall be given on behalf of the substituted petitioner before he proceeds with his petition, and within the prescribed time after the order of substitution.

Subject as aforesaid a substituted petitioner shall stand in the same position as nearly as may be, and be subject to the same liabilities as the original petitioner.

If a petition is withdrawn, the petitioner shall be liable to pay the costs of the respondent.

Where there are more petitioners than one, no application to withdraw a petition shall be made except with the consent of all the petitioners.

**37.** An election petition under this Act shall be abated by the death of a sole petitioner or of the survivor of several petitioners.

Abatement of petition.

The abatement of a petition shall not affect the liability of the petitioner to the payment of costs previously incurred.

On the abatement of a petition the prescribed notice of such abatement having taken place shall be given in the county or borough to which the petition relates, and within the prescribed time after the notice is given, any person who might have been a petitioner in respect of the election to which the petition relates may apply to the court or judge, in and at the prescribed manner, time and place to be substituted as a petitioner.

The court or judge may, if it or he thinks fit, substitute as a petitioner any such applicant who is desirous of being substituted, and on whose behalf security to the same amount is given as is required in the case of a new petition.

**38.** If before the trial of any election petition under this Act any of the following events happen in the case of the respondent (that is to say)—

Admission in certain cases of voters to be respondents.

- (1.) If he dies;
- (2.) If he is summoned to Parliament as a peer of Great Britain by a writ issued under the Great Seal of Great Britain;
- (3.) If the House of Commons have resolved that his seat is vacant;
- (4.) If he gives in and at the prescribed manner and time notice to the court that he does not intend to oppose the petition;

notice of such an event having taken place shall be given in the county or borough to which the petition relates, and within the prescribed time after the notice is given any person who might have been a petitioner in respect of the election to which the petition relates may apply to the court or judge to be admitted as a respondent to oppose the petition, and such person shall on such application be admitted accordingly, either with the respondent, if there be a respondent, or in place of the respondent; and any number of persons not exceeding three may be so admitted.

Respondent not opposing not to appear as party or to sit.

**39.** A respondent who has given the prescribed notice that he does not intend to oppose the petition shall not be allowed to appear or act as a party against such petition in any proceedings thereon, and shall not sit or vote in the House of Commons until the House of Commons has been informed of the report on the petition: and the court or judge shall in all cases in which such notice has been given in the prescribed time and manner report the same to the speaker of the House of Commons.

Provisions for cases of double return where the member complained of declines to defend his return.

**40.** Where an election petition under this Act complains of a double return and the respondent has given notice to the prescribed officer that it is not his intention to oppose the petition, and no party has been admitted in pursuance of this Act to defend such return, then the petitioner, if there be no petition complaining of the other member returned on such double return, may withdraw his petition by notice addressed to the prescribed officer, and upon the receipt of such notice the prescribed officer shall report the fact of the withdrawal of such petition to the speaker, and the House of Commons shall thereupon give the necessary directions for amending the said double return by taking off the file the indenture by which the respondent so declining to oppose the petition was returned, or otherwise as the case may require:

### *Costs.*

General costs of petition.

**41.** All costs, charges and expenses of and incidental to the presentation of a petition under this Act, and to the proceedings consequent thereupon, with the exception of such costs, charges and expenses as are by this Act otherwise provided for, shall be defrayed by the parties to the petition in such manner and in such proportions as the court or judge may determine, regard being had to the disallowance of any costs, charges or expenses which may, in the opinion of the court or judge, have been caused by vexatious conduct, unfounded allegations or unfounded objections on the part either of the petitioner or the respondent, and regard being had to the discouragement of any needless expense by throwing the burden of defraying the same on the parties by whom it has been caused, whether such parties are or are not on the whole successful.

The costs may be taxed in the prescribed manner, and such costs may be recovered in the same manner as the costs of an action at law, or in such other manner as may be prescribed.

Recognisance, when to be estreated, &c.

**42.** If any petitioner in an election petition presented under this Act neglect or refuse for the space of six months after demand to pay to any person summoned as a witness on his behalf, or to the



respondent, any sum certified to be due to him for his costs, charges and expenses, and if such neglect or refusal be, within one year after such demand, proved to the satisfaction of the court of elections, in every such case every person who has entered into a recognisance relating to such petition under the provisions of this Act shall be held to have made default in his said recognisance, and the prescribed officer shall thereupon certify such recognisance to be forfeited, and the same shall be dealt with in England in manner provided by the Act of the third year of the reign of King George the Fourth, chapter forty-six, and in Ireland in manner provided by "The Fines Act (Ireland), 1851."

### *Punishment of Corrupt Practices.*

**44.** If on the trial of any election petition under this Act any candidate is proved to have personally engaged at the election to which such petition relates as a canvasser or agent for the management of the election any person, knowing that such person has within seven years previous to such engagement been found guilty of any corrupt practice by any competent legal tribunal, or been reported guilty of any corrupt practice by a committee of the House of Commons, or by the report of the judge upon an election petition under this Act, or by the report of commissioners appointed in pursuance of the Act of the session of the fifteenth and sixteenth years of the reign of her present Majesty, chapter fifty-seven, the election of such candidate shall be void.

Penalty for employing corrupt agent.

### *Miscellaneous.*

**48.** If any returning officer wilfully delays, neglects, or refuses duly to return any person who ought to be returned to serve in Parliament for any county or borough, such person may, in case it has been determined on the hearing of an election petition under this Act that such person was entitled to have been returned, sue the officer having so wilfully delayed, neglected, or refused duly to make such return at his election in any of Her Majesty's courts of record at Westminster, and shall recover double the damages he has sustained by reason thereof, together with full costs of suit, provided such action be commenced within one year after the commission of the act on which it is grounded, or within six months after the conclusion of the trial relating to such election.

Returning officer may be sued for neglecting to return any person duly elected.

**49.** In reckoning time for the purposes of this Act, Sunday, Christmas Day, Good Friday, and any day set apart for a public fast or public thanksgiving, shall be excluded.

Calculation of time

**50.** From and after the next dissolution of Parliament no election or return to Parliament shall be questioned, except in accordance with the provisions of this Act.

Controverted elections to be tried under Act.

**51.** Where an election petition under this Act complains of the conduct of a returning officer, such returning officer shall, for all the purposes of this Act, except the admission of respondents in his place, be deemed to be a respondent.

Returning officer if complained of to be respondent.

Petition complaining of no return.

**52.** A petition under this Act complaining of no return may be presented to the court, and shall be deemed to be an election petition within the meaning of this Act, and the court may make such order thereon as they think expedient for compelling a return to be made, or may allow such petition to be heard by the judge in manner hereinbefore provided with respect to ordinary election petitions.

Recrimination when petition for undue return.

**53.** On the trial of a petition under this Act complaining of an undue return, and claiming the seat for some person, the respondent may give evidence to prove that the election of such person was undue in the same manner as if he had presented a petition complaining of such election.

Repeal of Acts.

**54.** From and after the next dissolution of Parliament, the Acts contained in the schedule hereto are repealed so far as relates to elections and petitions to the extent therein mentioned.

Provision as to payment of additional judges and remuneration of judges for duties to be performed under this Act.

**55.** The additional *puisne* judge appointed under this Act to each of the courts of Queen's Bench, the Common Pleas, and the Exchequer in England, shall, as to rank, salary, pension, attendant officers, jurisdiction, and all other privileges and duties of a judge, stand in the same position as the other *puisne* judges of the court to which he is attached.

Any *puisne* judge of the said courts appointed in pursuance of or after the passing of this Act, shall be authorised to sit; and shall, when requested by the Lord Chancellor, sit as judge of the Court of Probate and Court of Marriage and Divorce, or of the Admiralty Court.

Commissions of inquiry into corrupt practices.

**56.** If, upon a petition to the House of Commons, presented within 21 days after the return to the Clerk of the Crown in Chancery in England, or to the Clerk of the Crown and Hanaper in Ireland, of a member to serve in Parliament for any borough or county, or within 14 days after the meeting of Parliament, and signed by two or more electors of such borough or county, and alleging that corrupt practices have extensively prevailed at the then last election for such borough or county, or that there is reason to believe that corrupt practices have there so prevailed, an address be presented by both Houses of Parliament, praying that such allegation may be inquired into, the Crown may appoint commissioners to inquire into the same, and if such commissioners in such case be appointed, they shall inquire in the same manner, and with the same powers, and subject to all the provisions of the statute of the 15th & 16th of Viet. c. 57.

Rules as to agents practising in cases of election petitions.

**57.** Any person who at the time of the passing of this Act was entitled to practise as agent, according to the principles, practice, and rules of the House of Commons in cases of election petitions and matters relating to election of members of the House of Commons, shall be entitled to practise as an attorney or agent in cases of election petitions and all matters relating to elections before the court and judges prescribed by this Act: Provided that every such person so practising as aforesaid shall, in respect of such practice and everything relating thereto, be subject to the jurisdiction and orders of the court as if he were an attorney of the said court: and further, provided that no such person shall practise as aforesaid until his name shall have been entered

on a roll to be made and kept, and which is hereby authorised to be made and kept, by the prescribed officer in the prescribed manner.

**58.** The provisions of this Act shall apply to Scotland, subject to the following modifications :— Application of  
Act to Scotland

1. The expression "the court" shall mean either division of the inner house of the court of session, and either of such divisions shall have the same powers, jurisdiction and authority with reference to an election petition in Scotland, and the proceedings thereon, which by this Act are conferred on the Court of Common Pleas at Westminster with respect to election petitions in England :
2. The expression "county" shall not include a county of a city, but shall mean any county or division of a county, or any combination of counties, or of counties and portions of counties, returning a member to serve in Parliament :
3. The expression "borough" shall mean any university or universities, or any city, town, burgh, or district of cities, towns, or burghs, returning a member or members to serve in Parliament :
4. "Recognisance" shall mean a bond of caution with usual and necessary clauses :
5. The trial of every election petition in Scotland shall be conducted before a judge of the court of session, to be selected from a rota to be formed as hereinafter mentioned :
6. The judges of the court of session shall, on or before the first day of the winter session in every year, select, by a majority of votes, two of the judges of such court, not being members of the House of Lords, to be placed on the rota for the trial of election petitions during the ensuing year :
7. If in any case the judges of the said court are equally divided in their choice of a judge to be placed on the rota, the lord president shall have a second or casting vote :
8. Any judge placed on the rota shall be re-eligible in the succeeding or any subsequent year :
9. In the event of the death or illness of any judge for the time being on the rota, or his inability to act for any reasonable cause, the judges shall fill up the vacancy by placing on the rota another judge :
10. The judges for the time being on the rota shall, according to their seniority, respectively try the election petitions standing for trial under this Act, unless they otherwise agree among themselves, in which case the trial of each election petition shall be taken in manner provided by such agreement :
11. Where it appears to the judges on the rota, after due consideration of the list of petitions under this Act for the time being at issue, that the trial of such election petitions will be inconveniently delayed unless an additional judge or judges be appointed to assist the judges on the rota, the judges of the court of session shall, on and according to the requisition of such judges on the rota, select in manner hereinbefore provided, a judge to try election petitions for the ensuing year ; and any judge so selected shall during that year be deemed to be on the rota for the trial of election petitions :
12. The duties to be performed by the prescribed officer under this

Act with reference to election petitions in Scotland shall be performed by such one or more of the principal clerks of session as may be determined by the lord president of the court of session; and there shall be awarded to such principal clerk or clerks, in addition to their existing salaries, such remuneration for the performance of the duties imposed on them in pursuance of this Act as the said lord president may, with the consent of the commissioners of the treasury, determine :

13. The judge shall be received at the place where he is about to try an election petition under this Act in the same manner and by the same authorities, as far as circumstances admit, as a judge of the court of judicary is received at a circuit town, and he shall be attended by such officer or officers as shall be necessary.
14. The travelling and other expenses of the judge, and of the officer or officers in attendance upon him, and all expenses properly incurred in providing the judge with a proper court, shall be defrayed by the commissioners of the treasury out of money to be provided by Parliament :
15. On the trial of an election petition under this Act, the judge shall, subject to the provisions of this Act, have the same powers, jurisdictions and authority as a judge of the court of session presiding at the trial of a civil cause without a jury :
16. Any of Her Majesty's courts of record at Westminster shall in Scotland mean the court of session in Scotland :
17. In lieu of the provisions for the estreating of a recognisance under an election petition, the prescribed officer shall, when otherwise competent under the provisions of this Act, certify that the conditions contained in the bond of caution have not been fulfilled, and it shall then be competent for the party or parties interested to register the said bond, and do diligence upon it as accords of law.

#### SCHEDULE.

Date of Act.	Title of Act.	Extent of Repeal.
4 & 5 Vict. c. 57 .	An Act for the prevention of Bribery at Elections	The whole Act.
5 & 6 Vict. c. 102 .	An Act for the better Discovery and Prevention of Bribery and Treating at the Election of Members of Parliament	The whole Act.
11 & 12 Vict. c. 98.	An Act to amend the Law for the Trial of Election Petitions	The whole Act.
26 Vict. c. 29 .	An Act to amend and continue the Law relating to Corrupt Practices at Elections of Members of Parliament	Section 8.
28 Vict. c. 8 .	An Act to amend "The Election Petitions Act, 1848," in certain particulars	The whole Act.

## THE BALLOT ACT, 1872.\*

35 &amp; 36 VICT. CHAP. 33.

35 & 36 Vict.  
c. 33.An Act to Amend the Law relating to Procedure at  
Parliamentary and Municipal Elections.  
[18th July, 1872.]

WHEREAS it is expedient to amend the law relating to procedure at parliamentary and municipal elections :

Be it enacted by the Queen's most Excellent Majesty, by and with the advice and consent of the Lords Spiritual and Temporal, and Commons, in this present Parliament assembled, and by the authority of the same, as follows :—

## PART I.

## PARLIAMENTARY ELECTIONS.

*Procedure at Election.*

1. A candidate for election to serve in Parliament for a county or borough shall be nominated in writing. The writing shall be subscribed by two registered electors of such county or borough as proposer and seconder, and by eight other registered electors of the same county or borough as assenting to the nomination, and shall be delivered during the time appointed for the election to the returning officer by the candidate himself, or his proposer or seconder.

Nomination  
of candidates  
for parlia-  
mentary  
elections.

If at the expiration of one hour after the time appointed for the election no more candidates stand nominated than there are vacancies to be filled up, the returning officer shall forthwith declare the candidates who may stand nominated to be elected, and return their names to the clerk of the crown in chancery ; but if at the expiration of such hour more candidates stand nominated than there are vacancies to be filled up, the returning officer shall adjourn the election and shall take a poll in manner in this Act mentioned.

A candidate may, during the time appointed for the election, but not afterwards, withdraw from his candidature by giving a notice to that effect, signed by him, to the returning officer : Provided that the proposer of a candidate nominated in his absence out of the United Kingdom may withdraw such candidate by a written notice signed by him and delivered to the returning officer, together with a written declaration of such absence of the candidate.

If after the adjournment of an election by the returning officer for the purpose of taking a poll, one of the candidates nominated shall die before the poll has commenced, the returning officer shall, upon being satisfied of the fact of such death, countermand notice of the poll, and all the proceedings with reference to the election shall be commenced afresh in all respects, as if the writ had been received by the returning

\* The clauses, which are not material for the purposes of this work, are omitted in order to save space.

officer on the day on which proof was given to him of such death : provided that no fresh nomination shall be necessary in the case of a candidate who stood nominated at the time of the countermand of the poll.

Poll at  
elections.

2. In the case of a poll at an election the votes shall be given by ballot. The ballot of each voter shall consist of a paper (in this Act called a ballot paper) showing the names and description of the candidates. Each ballot paper shall have a number printed on the back, and shall have attached a counterfoil with the same number printed on the face. At the time of voting, the ballot paper shall be marked on both sides with an official mark, and delivered to the voter within the polling station, and the number of such voter on the register of voters shall be marked on the counterfoil, and the voter having secretly marked his vote on the paper, and folded it up so as to conceal his vote, shall place it in a closed box in the presence of the officer presiding at the polling station (in this Act called the "presiding officer") after having shown to him the official mark at the back.

Any ballot paper which has not on its back the official mark, or on which votes are given to more candidates than the voter is entitled to vote for, or on which anything, except the said number on the back, is written or marked by which the voter can be identified, shall be void and not counted.

After the close of the poll the ballot boxes shall be sealed up, so as to prevent the introduction of additional ballot papers, and shall be taken charge of by the returning officer, and that officer shall, in the presence of such agents, if any, of the candidates as may be in attendance, open the ballot boxes, and ascertain the result of the poll by counting the votes given to each candidate, and shall forthwith declare to be elected the candidates or candidate to whom the majority of votes have been given, and return their names to the clerk of the crown in chancery. The decision of the returning officer as to any question arising in respect of any ballot paper shall be final, subject to reversal on petition questioning the election or return.

Where an equality of votes is found to exist between any candidates at an election for a county or borough, and the addition of a vote would entitle any of such candidates to be declared elected, the returning officer, if a registered elector of such county or borough, may give such additional vote, but shall not in any other case be entitled to vote at an election for which he is returning officer.

### *Offences at Elections.*

Offences in  
respect of  
nomination  
papers,  
ballot  
papers, and  
ballot boxes.

3. Every person who,—

1. Forges or fraudulently defaces or fraudulently destroys any nomination paper, or delivers to the returning officer any nomination paper, knowing the same to be forged ; or
2. Forges or counterfeits or fraudulently defaces or fraudulently destroys any ballot paper or the official mark on any ballot paper ; or
3. Without due authority supplies any ballot paper to any person ; or
4. Fraudulently puts into any ballot box any paper other than the ballot paper which he is authorised by law to put in ; or
5. Fraudulently takes out of the polling station any ballot paper ; or

6. Without due authority destroys, takes, opens, or otherwise interferes with any ballot box or packet of ballot papers then in use for the purposes of the election :

shall be guilty of a misdemeanor, and be liable, if he is a returning officer or an officer or clerk in attendance at a polling station, to imprisonment for any term not exceeding two years, with or without hard labour, and if he is any other person, to imprisonment for any term not exceeding six months, with or without hard labour.

Any attempt to commit any offence specified in this section shall be punishable in the manner in which the offence itself is punishable.

In any indictment or other prosecution for an offence in relation to the nomination papers, ballot boxes, ballot papers, and marking instruments at an election, the property in such papers, boxes, and instruments may be stated to be in the returning officer at such election, as well as the property in the counterfoils.

4. Every officer, clerk, and agent in attendance at a polling station shall maintain and aid in maintaining the secrecy of the voting in such station, and shall not communicate, except for some purpose authorised by law, before the poll is closed, to any person any information as to the name or number on the register of voters of any elector who has or has not applied for a ballot paper or voted at that station, or as to the official mark, and no officer, clerk, or agent, and no person whosoever, shall interfere with or attempt to interfere with a voter when marking his vote, or otherwise attempt to obtain in the polling station information as to the candidate for whom any voter in such station is about to vote or has voted, or communicate at any time to any person any information obtained in a polling station as to the candidate for whom any voter in such station is about to vote or has voted, or as to the number on the back of the ballot paper given to any voter at such station. Every officer, clerk, and agent in attendance at the counting of the votes shall maintain and aid in maintaining the secrecy of the voting, and shall not attempt to ascertain at such counting the number on the back of any ballot paper, or communicate any information obtained at such counting as to the candidate for whom any vote is given in any particular ballot paper. No person shall directly or indirectly induce any voter to display his ballot paper after he shall have marked the same, so as to make known to any person the name of the candidate for or against whom he has so marked his vote.

Infringe-  
ment of  
secrecy.

Every person who acts in contravention of the provisions of this section shall be liable, on summary conviction before two justices of the peace, to imprisonment for any term not exceeding six months, with or without hard labour.

#### *Amendment of Law.*

7. At any election for a county or borough, a person shall not be entitled to vote unless his name is on the register of voters for the time being in force for such county or borough, and every person whose name is on such register shall be entitled to demand and receive a ballot paper and to vote : Provided that nothing in this section shall entitle any person to vote who is prohibited from voting by any statute, or by the common law of Parliament, or relieve such person from any penalties to which he may be liable for voting.

Conclusiveness  
of register of  
voters.

*Duties of Returning and Election Officers.*

General powers  
and duties of  
returning  
officer.

8. Subject to the provisions of this Act, every returning officer shall provide such nomination papers, polling stations, ballot boxes, ballot papers, stamping instruments, copies of register of voters, and other things, appoint and pay such officers, and do such other acts and things as may be necessary for effectually conducting an election in manner provided by this Act.

All expenses properly incurred by any returning officer in carrying into effect the provisions of this Act, in the case of any parliamentary election, shall be payable in the same manner as expenses incurred in the erection of polling booths at such election are by law payable.

Where the sheriff is returning officer for more than one county as defined for the purposes of parliamentary elections, he may, without prejudice to any other power, by writing under his hand, appoint a fit person to be his deputy for all or any of the purposes relating to an election in any such county, and may, by himself or such deputy, exercise any powers and do any things which the returning officer is authorised or required to exercise or do in relation to such election. Every such deputy, and also any under sheriff, shall, in so far as he acts as returning officer, be deemed to be included in the term returning officer in the provisions of this Act relating to parliamentary elections, and the enactments with which this part of this Act is to be construed as one.

Keeping of  
order in  
station.

9. If any person misconducts himself in the polling station, or fails to obey the lawful orders of the presiding officer, he may immediately, by order of the presiding officer, be removed from the polling station by any constable in or near that station, or any other person authorised in writing by the returning officer to remove him; and the person so removed shall not, unless with the permission of the presiding officer, again be allowed to enter the polling station during the day.

Any person so removed as aforesaid, if charged with the commission in such station of any offence, may be kept in custody until he can be brought before the justice of the peace.

Provided that the powers conferred by this section shall not be exercised so as to prevent any elector who is otherwise entitled to vote at any polling station from having an opportunity of voting at such station.

Powers of  
presiding officer  
and adminis-  
tration of  
oaths, &c.

10. For the purpose of the adjournment of the poll, and of every other enactment relating to the poll, a presiding officer shall have the power by law belonging to a deputy returning officer; and any presiding officer and any clerk appointed by the returning officer to attend at a polling station shall have the power of asking the questions and administering the oath authorised by law to be asked of and administered to voters, and any justice of the peace and any returning officer may take and receive any declaration authorised by this Act to be taken before him.

Liability of  
officers for  
misconduct.

11. Every returning officer, presiding officer, and clerk who is guilty of any wilful misfeasance or any wilful act or omission in contravention of this Act shall, in addition to any other penalty or liability to which



he may be subject, forfeit to any person aggrieved by such misfeasance, act, or omission, a penal sum not exceeding one hundred pounds.

Section 50 of the Representation of the People Act, 1867 (which relates to the acting of any returning officer, or his partner or clerk, as agent for a candidate), shall apply to any returning officer or officer appointed by him in pursuance of this Act, and to his partner or clerk.

30 & 31 Vict.  
c. 102.

### *Miscellaneous.*

12. No person who has voted at an election shall, in any legal proceeding to question the election or return, be required to state for whom he has voted.

Prohibition of  
disclosure of  
vote.

13. No election shall be declared invalid by reason of a non-compliance with the rules contained in the first schedule to this Act, or any mistake in the use of forms in the second schedule to this Act, if it appears to the tribunal having cognizance of the question that the election was conducted in accordance with the principles laid down in the body of this Act, and that such non-compliance or mistake did not affect the result of the election.

Non-com-  
pliance with  
rules.

14. Where a parliamentary borough and municipal borough occupy the whole or any part of the same area, and ballot boxes or fittings for polling stations and compartments provided for such parliamentary borough or such municipal borough may be used in any municipal or parliamentary election in such borough free of charge, and any damage other than reasonable wear and tear caused to the same shall be paid as part of the expenses of the election at which they are so used.

Use of  
municipal  
ballot boxes,  
&c., for parlia-  
mentary  
election, and  
*vice versa*.

15. This part of this Act shall, so far as is consistent with the tenor thereof, be construed as one with the enactments for the time being in force relating to the representation of the people, and to the registration of persons entitled to vote at the election of members to serve in parliament, and with any enactments otherwise relating to the subject matter of this part of this Act, and terms used in this part of this Act shall have the same meaning as in the said enactments; and in construing the said enactments relating to an election or to the poll or taking the votes by poll, the mode of election and of taking the poll established by this Act shall for the purposes of the said enactments be deemed to be substituted for the mode of election or poll, or taking the votes by poll, referred to in the said enactments; and any person applying for a ballot paper under this Act shall be deemed "to tender his vote," or "to assume to vote," within the meaning of the said enactments; and any application for a ballot paper under this Act, or expressions relative thereto, shall be equivalent to "voting" in the said enactments and any expressions relative thereto; and the term "polling booth" as used in the said enactments shall be deemed to include a polling station; and the term "proclamation" as used in the said enactments, shall be deemed to include a public notice given in pursuance of this Act.

Construction  
of Act.

## PART III.

## PERSONATION.

Definition and punishment of personation.

**24.** The following enactments shall be made with respect to personation at parliamentary and municipal elections :

A person shall for all purposes of the laws relating to parliamentary and municipal elections, be deemed to be guilty of the offence of personation who at an election for a county or borough, or at a municipal election, applies for a ballot paper in the name of some other person, whether that name be that of a person living or dead or of a fictitious person, or who having voted once at any such election applies at the same election for a ballot paper in his own name.

It shall be the duty of the returning officer to institute a prosecution against any person whom he may believe to have been guilty of personation, or of aiding, abetting, counselling, or procuring the commission of the offence of personation by any person at the election for which he is returning officer, and the costs and expenses of the prosecutor and the witnesses in such case, together with compensation for their trouble and loss of time, shall be allowed by the court in the same manner in which courts are empowered to allow the same in cases of felony,

The provisions of the Registration Acts, specified in the third schedule to this Act, shall in England and Ireland respectively apply to personation under this Act in the same manner as they apply to a person who knowingly personates and falsely assumes to vote in the name of another person as mentioned in the said Acts.

Vote to be struck off for bribery, treating, or undue influence.

**25.** Where a candidate, on the trial of an election petition claiming the seat for any person, is proved to have been guilty, by himself or by any person on his behalf, of bribery, treating, or undue influence in respect of any person who voted at such election, or where any person retained or employed for reward by or on behalf of such candidate for all or any of the purposes of such election, as agent, clerk, messenger, or in any other employment, is proved on such trial to have voted at such election, there shall, on a scrutiny, be struck off from the number of votes appearing to have been given to such candidate one vote for every person who voted at such election and is proved to have been so bribed, treated, or unduly influenced, or so retained or employed for reward as aforesaid.

Construction of part of Act.

**26.** This part of this Act, so far as regards parliamentary elections, shall be construed as one with The Parliamentary Elections Act, 1868, and shall apply to an election for a university or combination of universities.

## PART IV.

## MISCELLANEOUS.

Application of Act.

**30.** This Act shall apply to any parliamentary or municipal election which may be held after the passing thereof.

**31.** Nothing in this Act, except Part III. thereof, shall apply to any Saving.  
election for a university or combination of universities.

### *Repeal.*

**32.** The Act specified in the fourth, fifth, and sixth schedules to this Act, to the extent specified in the third column of those schedules, and all other enactments inconsistent with this Act, are hereby repealed— Repeal of Acts  
in schedule.

Provided that this repeal shall not affect—

- (a.) Anything duly done or suffered under any enactment hereby repealed ; or
- (b.) Any right or liability acquired, accrued, or incurred under any enactment hereby repealed ; or
- (c.) Any penalty, forfeiture, or punishment incurred in respect of any offence committed against any enactment hereby repealed ; or
- (d.) Any investigation, legal proceeding, or remedy in respect of any such right, liability, penalty, forfeiture, or punishment as aforesaid ; and any such investigation, legal proceeding, and remedy may be carried on as if this Act had not passed.

---

## SCHEDULES.

### FIRST SCHEDULE.

#### PART I.

#### RULES FOR PARLIAMENTARY ELECTIONS.

##### *Elections.*

1. The returning officer shall, in the case of a county election, within two days after the day on which he receives the writ, and in the case of a borough election, on the day on which he receives the writ or the following day, give public notice, between the hours of nine in the morning and four in the afternoon, of the day on which and the place at which he will proceed to an election, and of the time appointed for the election, and of the day on which the poll will be taken in case the election is contested, and of the time and place at which forms of nomination papers may be obtained, and in the case of a county election shall send one of such notices by post, under cover, to the postmaster of the principal post-office of each polling place in the county, endorsed with the words "Notice of election," and the same shall be forwarded free of charge ; and the postmaster receiving the same shall forthwith publish the same in the manner in which post-office notices are usually published.

2. The day of election shall be fixed by the returning officer as follows ; that is to say, in the case of an election for a county or a district

borough not later than the ninth day after the day on which he receives the writ, with an interval of not less than three clear days between the day on which he gives the notice and the day of election; and in the case of an election for any borough other than a district borough not later than the fourth day after the day on which he receives the writ, with an interval of not less than two clear days between the day on which he gives the notice and the day of election.

3. The place of election shall be a convenient room situate in the town in which such election would have been held if this Act had not passed, or where the election would not have been held in a town, then situate in such town in the county as the returning officer may from time to time determine as being in his opinion most convenient for the electors.

4. The time appointed for the election shall be such two hours between the hours of ten in the forenoon and three in the afternoon as may be appointed by the returning officer, and the returning officer shall attend during those two hours and for one hour after.

5. Each candidate shall be nominated by a separate nomination paper, but the same electors or any of them may subscribe as many nomination papers as there are vacancies to be filled, but no more.

6. Each candidate shall be described in the nomination paper in such manner as in the opinion of the returning officer is calculated to sufficiently identify such candidate; the description shall include his names, his abode, and his rank, profession, or calling, and his surname shall come first in the list of his names. No objection to a nomination paper on the ground of the description of the candidate therein being insufficient, or not being in compliance with this rule, shall be allowed or deemed valid, unless such objection is made by the returning officer, or by some other person, at or immediately after the time of the delivery of the nomination paper.

7. The returning officer shall supply a form of nomination paper to any registered elector requiring the same during such two hours as the returning officer may fix, between the hours of ten in the morning, and two in the afternoon on each day intervening between the day on which notice of the election was given and the day of election, and during the time appointed for the election; but nothing in this Act shall render obligatory the use of a nomination paper supplied by the returning officer, so, however, that the paper be in the form prescribed by this Act.

8. The nomination papers shall be delivered to the returning officer, at the place of election during the time appointed for the election; and the candidate nominated by each nomination paper, and his proposer and seconder, and one other person selected by the candidate, and no person other than aforesaid, shall, except for the purpose of assisting the returning officer, be entitled to attend the proceedings during the time appointed for the election.

9. If the election is contested, the returning officer shall, as soon as practicable after adjourning the election, give public notice of the day on which the poll will be taken, and of the candidates described as in their respective nomination papers, and of the names of the persons who subscribe the nomination paper of each candidate, and of the order in which the names of the candidates will be printed in the ballot paper, and, in the case of an election for a county, deliver to the postmaster of the principal post-office of the town in which is situate the place of election a paper, signed by himself, containing the names of the candidates nominated, and stating the day on which the poll is to be taken.

and the postmaster shall forward the information contained in such paper by telegraph, free of charge, to the several postal telegraph offices situate in the county for which the election is to be held, and such information shall be published forthwith at each such office in the manner in which post-office notices are usually published.

10. If any candidate nominated during the time appointed for the election is withdrawn in pursuance of this Act, the returning officer shall give public notice of the name of such candidate, and the names of the persons who subscribed the nomination paper of such candidate, as well as of the candidates who stood nominated or were elected.

11. The returning officer shall, on the nomination paper being delivered to him, forthwith publish notice of the name of the person nominated as a candidate, and of the names of his proposer and seconder, by placarding or causing to be placarded the names of the candidate and his proposer and seconder in a conspicuous position outside the building in which the room is situate appointed for the election.

12. A person shall not be entitled to have his name inserted in any ballot paper as a candidate unless he has been nominated in manner provided by this Act, and every person whose nomination paper has been delivered to the returning officer during the time appointed for the election shall be deemed to have been nominated in manner provided by this Act, unless objection be made to his nomination paper by the returning officer or some other person before the expiration of the time appointed for the election or within one hour afterwards.

13. The returning officer shall decide on the validity of every objection made to a nomination paper, and his decision, if disallowing the objection, shall be final; but if allowing the same, shall be subject to reversal on petition questioning the election or return.

### *The Poll.*

14. The poll shall take place on such day as the returning officer may appoint, not being in the case of an election for a county or a district borough less than two or more than six clear days, and not being in the case of an election for a borough other than a district borough more than three clear days after the day fixed for the election.

15. At every polling place the returning officer shall provide a sufficient number of polling stations for the accommodation of the electors entitled to vote at such polling place, and shall distribute the polling stations amongst those electors in such a manner as he thinks most convenient, provided that in a district borough there shall be at least one polling station at each contributory place of such borough.

16. Each polling station shall be furnished with such number of compartments, in which the voters can mark their votes screened from observation, as the returning officer thinks necessary, so that at least one compartment be provided for every one hundred and fifty electors entitled to vote at such polling station.

17. A separate room or separate booth may contain a separate polling station, or several polling stations may be constructed in the same room or booth.

18. No person shall be admitted to vote at any polling station except the one allotted to him.

19. The returning officer shall give public notice of the situation of polling stations and the description of voters entitled to vote at each station, and of the mode in which electors are to vote.

20. The returning officer shall provide each polling station with materials for voters to mark the ballot papers, with instruments for stamping thereon the official mark, and with copies of the register of voters, or such part thereof as contains the names of the voters allotted to vote at such station. He shall keep the official mark secret, and an interval of not less than seven years shall intervene between the use of the same official mark at elections for the same county or borough.

21. The returning officer shall appoint a presiding officer to preside at each station, and the officer so appointed shall keep order at his station, shall regulate the number of electors to be admitted at a time, and shall exclude all other persons except the clerks, the agents of the candidates, and the constables on duty.

22. Every ballot paper shall contain a list of the candidates described as in their respective nomination papers, and arranged alphabetically in the order of their surnames, and (if there are two or more candidates with the same surname) of their other names : it shall be in the form set forth in the second schedule to this Act or as near thereto as circumstances admit, and shall be capable of being folded up.

23. Every ballot box shall be so constructed that the ballot papers can be introduced therein, but cannot be withdrawn therefrom, without the box being unlocked. The presiding officer at any polling station, just before the commencement of the poll, shall show the ballot box empty to such persons, if any, as may be present in such station, so that they may see that it is empty, and shall then lock it up, and place his seal upon it in such manner as to prevent its being opened without breaking such seal, and shall place it in his view for the receipt of ballot papers, and keep it so locked and sealed.

24. Immediately before a ballot paper is delivered to an elector, it shall be marked on both sides with the official mark, either stamped or perforated, and the number, name and description of the elector as stated in the copy of the register shall be called out, and the number of such elector shall be marked on the counterfoil, and a mark shall be placed in the register against the number of the elector, to denote that he has received a ballot paper, but without showing the particular ballot paper which he has received.

25. The elector, on receiving the ballot paper, shall forthwith proceed into one of the compartments in the polling station, and there mark his paper, and fold it up so as to conceal his vote, and shall then put his ballot paper, so folded up, into the ballot box ; he shall vote without undue delay, and shall quit the polling station as soon as he has put his ballot paper into the ballot box.

26. The presiding officer, on the application of any voter who is incapacitated by blindness or other physical cause from voting in manner prescribed by this Act, or (if the poll be taken on Saturday) of any voter who declares that he is of the Jewish persuasion, and objects on religious grounds to vote in the manner prescribed in this Act, or of any voter who makes such a declaration as hereinafter mentioned that he is unable to read, shall, in the presence of the agents of the candidates, cause the vote of such voter to be marked on a ballot paper in manner directed by such voter, and the ballot paper to be placed in the ballot box, and the name and number on the register of voters of every voter whose vote is marked in pursuance of this rule, and the reason why it is so marked, shall be entered on a list, in this Act called " the list of votes marked by the presiding officer."

The said declaration, in this Act referred to as " the declaration of

inability to read," shall be made by the voter at the time of polling, before the presiding officer, who shall attest it in the form hereinafter mentioned, and no fee, stamp, or other payment shall be charged in respect of such declaration, and the said declaration shall be given to the presiding officer at the time of voting.

27. If a person, representing himself to be a particular elector named on the register, applies for a ballot paper after another person has voted as such elector, the applicant shall, upon duly answering the questions and taking the oath permitted by law to be asked of and to be administered to voters at the time of polling, be entitled to mark a ballot paper in the same manner as any other voter, but the ballot paper (in this Act called a tendered ballot paper) shall be of a colour differing from the other ballot papers, and, instead of being put into the ballot box, shall be given to the presiding officer and endorsed by him with the name of the voter and his number in the register of voters, and set aside in a separate packet, and shall not be counted by the returning officer. And the name of the voter and his number on the register shall be entered on a list, in this Act called the tendered votes list.

28. A voter who has inadvertently dealt with his ballot paper in such manner that it cannot be conveniently used as a ballot paper, may, on delivering to the presiding officer the ballot paper so inadvertently dealt with, and proving the fact of the inadvertence to the satisfaction of the presiding officer, obtain another ballot paper in the place of the ballot paper so delivered up (in this Act called a spoilt ballot paper), and the spoilt ballot paper shall be immediately cancelled.

29. The presiding officer of each station, as soon as practicable after the close of the poll, shall, in the presence of the agents of the candidates, make up into separate packets sealed with his own seal and the seals of such agents of the candidates as desired to affix their seals—

1. Each ballot box in use at his station, unopened but with the key attached; and
2. The unused and spoilt ballot papers, placed together; and
3. The tendered ballot papers; and
4. The marked copies of the register of voters, and the counterfoils of the ballot papers; and
5. The tendered votes list, and the list of votes marked by the presiding officer, and a statement of the number of the voters whose votes are so marked by the presiding officer under the heads "physical incapacity," "Jews," and "unable to read," and the declarations of inability to read;

and shall deliver such packets to the returning officer.

30. The packets shall be accompanied by a statement made by such presiding officer, showing the number of ballot papers entrusted to him, and accounting for them under the heads of ballot papers in the ballot box, unused, spoilt, and tendered ballot papers, which statement is in this Act referred to as the ballot paper account.

### *Counting Votes.*

31. The candidates may respectively appoint agents to attend the counting of the votes.

32. The returning officer shall make arrangements for counting the votes in the presence of the agents of the candidates as soon as practicable after the close of the poll, and shall give to the agents of the

candidates appointed to attend at the counting of the votes notice in writing of the time and place at which he will begin to count the same.

33. The returning officer, his assistants and clerks, and the agents of the candidates, and no other person, except with the sanction of the returning officer, may be present at the counting of the votes.

34. Before the returning officer proceeds to count the votes, he shall, in the presence of the agents of the candidates, open each ballot box, and, taking out the papers therein, shall count and record the numbers thereof, and then mix together the whole of the ballot papers contained in the ballot boxes. The returning officer, while counting and recording the number of ballot papers and counting the votes, shall keep the ballot papers with their faces upwards, and take all proper precautions for preventing any person from seeing the numbers printed on the backs of such papers.

35. The returning officer shall, so far as practicable, proceed continuously with counting the votes, allowing only time for refreshment, and excluding (except so far as he and the agents otherwise agree) the hours between seven o'clock at night and nine o'clock on the succeeding morning. During the excluded time the returning officer shall place the ballot papers and other documents relating to the election under his own seal and the seals of such of the agents of the candidates as desire to affix their seals, and shall otherwise take proper precautions for the security of such papers and documents.

36. The returning officer shall endorse "rejected" on any ballot paper which he may reject as invalid, and shall add to the endorsement "rejection objected to," if an objection be in fact made by any agent to his decision. The returning officer shall report to the clerk of the crown in chancery the number of ballot papers rejected and not counted by him under the several heads of—

1. Want of official mark ;
2. Voting for more candidates than entitled to ;
3. Writing or mark by which voter could be identified ;
4. Unmarked, or void for uncertainty ;

and shall on request allow any agent of the candidates, before such report is sent, to copy it.

37. Upon the completion of the counting, the returning officer shall seal up in separate packets the counted and rejected ballot papers. He shall not open the sealed packet of tendered ballot papers or marked copy of the register of voters and counterfoils, but shall proceed, in the presence of the agents of the candidates, to verify the ballot paper account given by each presiding officer by comparing it with the number of ballot papers recorded by him as aforesaid, and the unused and spoilt ballot papers in his possession, and the tendered votes list, and shall reseal each sealed packet after examination. The returning officer shall report to the clerk of the crown in chancery the result of such verification, and shall, on request, allow any agent of the candidates, before such report is sent, to copy it.

38. Lastly, the returning officer shall forward to the clerk of the crown in chancery (in manner in which the poll books are by any existing enactment required to be forwarded to such clerk, or as near thereto as circumstances admit) all the packets of ballot papers in his possession, together with the said reports, the ballot paper accounts, tendered votes lists, lists of votes marked by the presiding officer, statements relating thereto, declarations of inability to read, and packets of counterfoils, and marked copies of registers, sent by each presiding officer, endorsing on each packet a description of its contents and the date of the election to



which they relate, and the name of the county or borough for which such election was held; and the term poll book in any such enactments shall be construed to include any document forwarded in pursuance of this rule.

39. The clerk of the crown shall retain for a year all documents relating to an election forwarded to him in pursuance of this Act by a returning officer, and then, unless otherwise directed by an order of the House of Commons, or of one of Her Majesty's superior courts, shall cause them to be destroyed.

40. No person shall be allowed to inspect any *rejected ballot papers* in the custody of the clerk of the crown in chancery, except under the order of the House of Commons or under the order of one of Her Majesty's superior courts, to be granted by such court on being satisfied by evidence on oath that the inspection or production of such ballot papers is required for the purpose of instituting or maintaining a prosecution for an offence in relation to ballot papers, or for the purpose of a petition questioning an election or return; and any such order for the inspection or production of *ballot papers* may be made subject to such conditions as to persons, time, place, and mode of inspection or production as the House or Court making the same may think expedient, and shall be obeyed by the clerk of the crown in chancery. Any power given to a court by this rule may be exercised by any judge of such court at chambers.

41. No person shall, except by order of the House of Commons or any tribunal having cognizance of petitions complaining of undue returns or undue elections, open *the sealed packet of counterfoils* after the same has been once sealed up, or be allowed to inspect any *counted ballot papers* in the custody of the clerk of the crown in chancery; such order may be made subject to such conditions as to persons, time, place, and mode of opening or inspection as the house or tribunal making the order may think expedient; provided that on making and carrying into effect any such order, care shall be taken that the mode in which any particular elector has voted shall not be discovered until he has been proved to have voted, and his vote has been declared by a competent court to be invalid.

42. All documents forwarded by a returning officer in pursuance of this Act to the clerk of the crown in chancery, other than ballot papers and counterfoils, shall be open to public inspection at such time and under such regulations as may be prescribed by the clerk of the crown in chancery, with the consent of the Speaker of the House of Commons, and the clerk of the crown shall supply copies of or extracts from the said documents to any person demanding the same on payment of such fees and subject to such regulations as may be sanctioned by the Treasury.

43. Where an order is made for the production by the clerk of the crown in chancery of any document in his possession relating to any specified election, the production by such clerk or his agent of the document ordered, in such manner as may be directed by such order, or by a rule of court having power to make such order, shall be conclusive evidence that such document relates to the specified election; and any endorsement appearing on any packet of ballot papers produced by such clerk of the crown or his agent shall be evidences of such papers being what they are stated to be by the endorsement. The production from proper custody of a ballot paper purporting to have been used at any election, and of a counterfoil marked with the same printed number and having a number marked thereon in writing, shall be *prima facie* evidence that the person who voted by such ballot paper was the person who

at the time of such election had affixed to his name in the register of voters at such election the same number as the number written on such counterfoil.

*General Provisions.*

44. The return of a member or members elected to serve in Parliament for any county or borough shall be made by a certificate of the names of such member or members under the hand of the returning officer endorsed on the writ of election for such county or borough, and such certificate shall have effect and be dealt with in like manner as the return under the existing law, and the returning officer may, if he think fit, deliver the writ with such certificate endorsed to the postmaster of the principal post-office of the place of election, or his deputy, and in that case he shall take a receipt from the postmaster or his deputy for the same; and such postmaster or his deputy, shall then forward the same by the first post, free of charge, under cover to the clerk of the crown, with the words "Election Writ and Return" endorsed thereon.

45. The returning officer shall, as soon as possible, give public notice of the names of the candidates elected, and, in case of a contested election, of the total number of votes given for each candidate, whether elected or not.

46. Where the returning officer is required or authorised by this Act to give any public notice, he shall carry such requirement into effect by advertisements, placards, handbills, or such other means as he thinks best calculated to afford information to the electors.

47. The returning officer may, if he think fit, preside at any polling station, and the provisions of this Act relating to a presiding officer shall apply to such returning officer with the necessary modifications as to things to be done by the returning officer to the presiding officer, or the presiding officer to the returning officer.

48. In the case of a contested election for any county or borough the returning officer may, in addition to any clerks, appoint competent persons to assist him in counting the votes.

49. No person shall be appointed by a returning officer for the purposes of an election who has been employed by any other person in or about the election.

50. The presiding officer may do, by the clerks appointed to assist him, any act which he is required or authorised to do by this Act at a polling station, except ordering the arrest, exclusion, or ejection from the polling station of any person.

51. A candidate may himself undertake the duties which any agent of his if appointed might have undertaken, or may assist his agent in the performance of such duties, and may be present at any place at which his agent may, in pursuance of this Act, attend.

52. The name and address of every agent of a candidate appointed to attend the counting of the votes shall be transmitted to the returning officer one clear day at the least before the opening of the poll; and the returning officer may refuse to admit to the place where the votes are counted any agent whose name and address has not been so transmitted, notwithstanding that his appointment may be otherwise valid and any notice required to be given to an agent by the returning officer may be delivered at or sent by post to such address.

53. If any person appointed an agent by a candidate for the purposes of attending at the polling station or at the counting of the votes dies, or becomes incapable of acting during the time of the election, the

candidate may appoint another agent in his place, and shall forthwith give to the returning officer notice in writing of the name and address of the agent so appointed.

54. Every returning officer, and every officer, clerk or agent authorised to attend at the polling station or at the counting of the votes, shall, before the opening of the poll, make a statutory declaration of secrecy, in the presence, if he is the returning officer, of a justice of the peace, and if he is any other officer or an agent, of a justice of the peace or of the returning officer; but no such returning officer, officer, clerk or agent as aforesaid shall, save as aforesaid, be required as such to make any declaration or take any oath on the occasion of any election.

55. Where in this Act any expressions are used requiring or authorising or inferring that any act or thing is to be done in the presence of the agents of the candidates, such expressions shall be deemed to refer to the presence of such agents of the candidates as may be authorised to attend, and as have in fact attended, at the time and place where such act or thing is being done, and the non-attendance of any agents or agent at such time and place shall not, if such act or thing be otherwise duly done, in anywise invalidate the act or thing done.

56. In reckoning time for the purposes of this Act, Sunday, Christmas Day, Good Friday, and any day set apart for a public fast or public thanksgiving, shall be excluded; and where anything is required by this Act to be done on any day which falls on the above-mentioned days, such thing may be done on the next day, unless it is one of the days excluded as above-mentioned.

57. In this Act—

The expression “district borough” means the borough of Monmouth and any of the boroughs specified in Schedule E. to the Act of the session of the second and third years of the reign of King William the Fourth, chapter 45, intituled “An Act to Amend the Representation of the People in England and Wales;” and—

The expression “polling place” means in the case of a borough, such borough or any part thereof in which a separate booth is required or authorised by law to be required; and

The expression “agents of the candidates,” used in relation to a polling station, means agents appointed in pursuance of Section 85 of the Act of the session of the sixth and seventh years of the reign of Her present Majesty, chapter 18.

## “GENERAL RULES (PARLIAMENTARY)

M.T., 1868.”

### I.

The presentation of an election petition shall be made by leaving it at the office of the master nominated by the Chief Justice of the Common Pleas, and such master or his clerk shall (if required) give a receipt, which may be in the following form :—

Received on the       day of       at the master's office a petition touching the election of A.B., a member for       purporting to be signed by [*insert the names of petitioners*].

C.D., *Master's Clerk.*

With the petition shall also be left a copy thereof for the master to send to the returning officer pursuant to Section 7 of the Act.

### II.

An election petition shall contain the following statements :—

1. It shall state the right of the petitioner to petition within Section 5 of the Act.

2. It shall state the holding and result of the election, and shall briefly state the facts and grounds relied on to sustain the prayer.

### III.

The petition shall be divided into paragraphs, each of which, as nearly as may be, shall be confined to a distinct portion of the subject, and every paragraph shall be numbered consecutively, and no costs shall be allowed of drawing or copying any petition not substantially in compliance with this rule, unless otherwise ordered by the court or a judge.

### IV.

The petition shall conclude with a prayer, as, for instance that some specified person should be declared duly returned or elected, or that the election should be declared void, or that a return may be enforced (as the case may be), and shall be signed by all the petitioners.

### V.

The following form, or one to the like effect, shall be sufficient :—  
In the Common Pleas.

“The Parliamentary Elections Act, 1868.”

Election for [*state the place*] holden on the       day of       A.D.

The petition of A. of       [*or of A. of       and B. of*  
*as the case may be*] whose names are subscribed.

1. Your petitioner A. is a person who voted [*or had a right to vote as the case may be*] at the above election [*or claims to have had a right to be returned at the above election, or was a candidate at the above election*] : and your petitioner B. [*here state in like manner the right of each petitioner.*]

2. And your petitioners state that the election was holden on the day of A.D. when A.B., C.D. and E.F. were candidates, and the returning officer has returned A.B. and C.D. as being duly elected.

3. And your petitioners say that [*here state the facts and grounds on which the petitioners rely.*]

Wherefore your petitioners pray that it may be determined that the said A. B. was not duly elected or returned, and that the election was void [*or that the said E.F. was duly elected and ought to have been returned, or as the case may be.*]

(Signed) A.  
B.

#### VI.

Evidence need not be stated in the petition, but the court or a judge may order such particulars as may be necessary to prevent surprise and unnecessary expense, and to ensure a fair and effectual trial in the same way as in ordinary proceedings in the Court of Common Pleas, and upon such terms as to costs and otherwise as may be ordered.

#### VII.

When a petitioner claims the seat for an unsuccessful candidate, alleging that he had a majority of lawful votes, the party complaining of or defending the election or return, shall, six days before the day appointed for trial, deliver to the master, and also to the address, if any, given by the petitioners and respondent, as the case may be, a list of the votes intended to be objected to, and of the heads of objection to each such vote, and the master shall allow inspection and office copies of such lists to all parties concerned; and no evidence shall be given against the validity of any vote, nor upon any head of objection not specified in the list, except by the leave of the court or judge upon such terms as to amendment of the list, postponement of the inquiry and payment of costs as may be ordered.

#### VIII.

When the respondent in a petition under the Act, complaining of an undue return and claiming the seat for some person, intends to give evidence to prove that the election of such person was undue, pursuant to the 53rd Section of the Act, such respondent shall six days before the day appointed for trial deliver to the master, and also at the address, if any, given by the petitioner, a list of objections to the election upon which he intends to rely, and the master shall allow inspection and office copies of such lists to all parties concerned; and no evidence shall be given by a respondent of any objection to the election not specified in the list, except by leave of the court or judge, upon such terms as to amendments of the list, postponement of the inquiry and payment of costs, as may be ordered.

#### IX.

With the petition, petitioners shall leave at the office of the master a writing signed by them or on their behalf, giving the name of some person entitled to practise as an attorney or agent in cases of election petitions whom they authorise to act as their agent, or stating that they act for themselves, as the case may be, and in either case

giving an address within three miles from the General Post Office at which notices addressed to them may be left ; and if no such writing be left or address given, then notice of objection to the recognizances and all other notices and proceedings may be given by sticking up the same at the master's office.

#### X.

Any person returned as a member may at any time after he is returned send or leave at the office of the master a writing signed by him or on his behalf, appointing a person entitled to practise as an attorney or agent in cases of election petitions, to act as his agent in case there should be a petition against him, or stating that he intends to act for himself, and in either case giving an address within three miles from the General Post Office at which notices may be left, and in default of such writing being left in a week after service of the petition, notices and proceedings may be given and served respectively by sticking up the same at the master's office.

#### XI.

The master shall keep a book or books at his office in which he shall enter all addresses and the names of agents given under either of the preceding rules, which book shall be open to inspection by any person during office hours.

#### XII.

The master shall upon the presentation of the petition forthwith send a copy of the petition to the returning officer, pursuant to Section 7 of the Act, and shall therewith send the name of the petitioner's agent, if any, and of the address, if any, given as prescribed, and also of the name of the respondent's agent, and the address, if any, given as prescribed, and the returning officer shall forthwith publish those particulars along with the petition.

The cost of publication of this and any other matter required to be published by the returning officer shall be paid by the petitioner or person moving in the matter, and shall form part of the general costs of the petition.

#### XIII.

The time for giving notice of the presentation of a petition and of the nature of the proposed security shall be five days, exclusive of the day of presentation.

#### XIV.

Where the respondent has named an agent or given an address, the service of an election petition may be by delivery of it to the agent or by posting it in a registered letter to the address given at such time that, in the ordinary course of post, it would be delivered within the prescribed time.

In other cases the service must be personal on the respondent unless a judge on an application made to him not later than five days after the petition is presented on affidavit showing what has been done, shall be satisfied that all reasonable effort has been made to effect personal service and cause the matter to come to the knowledge of the respondent, including, when practicable, service upon an agent for election

expenses, in which case the judge may order that what has been done shall be considered sufficient service, subject to such conditions as he may think reasonable.

## XV.

In case of evasion of service, the sticking up a notice in the office of the master of the petition having been presented stating the petitioner, the prayer, and the nature of the proposed security, shall be deemed equivalent to personal service, if so ordered by a judge.

## XVI.

The deposit of money by way of security for payment of costs, charges and expenses payable by the petitioner, shall be made by payment into the Bank of England to an account to be opened there by the description of "The Parliamentary Elections Act, 1868, Security Fund," which shall be vested in and drawn upon from time to time by the chief justice of the Common Pleas for the time being, for the purposes for which security is required by the said Act, and a bank-receipt or certificate for the same shall be forthwith left at the master's office.

## XVII.

The master shall file such receipt or certificate, and keep a book open to inspection of all parties concerned, in which shall be entered from time to time the amount and the petition to which it is applicable.

## XVIII.

The recognizance as security for costs may be acknowledged before a judge at chambers or the master in town, or a justice of the peace in the country.

There may be one recognizance acknowledged by all the sureties, or separate recognizances by one or more, as may be convenient.

## XIX.

The recognizance shall contain the name and usual place of abode of each surety, with such sufficient description as shall enable him to be found or ascertained, and may be as follows :—

Be it remembered that on the                      day of                      in the year of our Lord 18    , before me [*name and description*] came A. B., of [*name and description as above prescribed*] and acknowledged himself [*or severally acknowledged themselves*] to owe to our sovereign lady the Queen the sum of one thousand pounds [*or the following sums*] (that is to say) the said C. D. the sum of £                      , the said E. F., the sum of £                      , the said G. H. the sum of £                      , and the said J. K., the sum of £                      , to be levied on his [*or their respective*] goods and chattels, land and tenements, to the use of our sovereign lady the Queen, her heirs and successors.

The condition of this recognizance is that if [*here insert the names of all the petitioners, and if more than one add, or any of them*] shall well and truly pay all costs, charges and expenses in respect of the election petition signed by him [*or them*] relating to the [*here insert the name of the borough, or county*] which shall become payable by the said petitioner [*or petitioners, or any of them*] under the Parliamentary

Elections Act, 1868, to any person or persons, then this recognizance to be void, otherwise to stand in full force.

(Signed)

[*Signatures of sureties.*]

Taken and acknowledged by the above-named [*names of sureties*] on the       day of       at       , before me,

C. D.,

A justice of the peace [*or as the case may be.*]

## XX.

The recognizance or recognizances shall be left at the master's office, by or on behalf of the petitioner in like manner as before described for the leaving of a petition forthwith after being acknowledged.

## XXI.

The time for giving notice of any objection to a recognizance under the 8th Section of the Act shall be within five days from the date of service of the notice of the petition and of the nature of the security, exclusive of the day of service.

## XXII.

An objection to the recognizance must state the ground or grounds thereof, as that the sureties or any, and which of them, are insufficient, or that a surety is dead, or that he cannot be found, or that a person named in the recognizance has not duly acknowledged the same.

## XXIII.

Any objection made to the security shall be heard and decided by the master, subject to appeal within five days to a judge, upon summons taken out by either party to declare the security sufficient or insufficient.

## XXIV.

Such hearing and decision may be either upon affidavit or personal examination of witnesses, or both, as the master or judge may think fit.

## XXV.

If by order made upon such summons the security be declared sufficient, its sufficiency shall be deemed to be established within the meaning of the 9th Section of the said Act, and the petition shall be at issue.

## XXVI.

If by order made upon such summons an objection be allowed and the security be declared insufficient, the master or judge shall in such order state what amount he deems requisite to make the security sufficient, and the further prescribed time to remove the objection by deposit shall be within five days from the date of the order, not including the day of the date, and such deposit shall be made in the manner already prescribed.



## XXVII.

The costs of hearing and deciding the objection made to the security given shall be paid as ordered by the master or judge, and in default of such order shall form part of the general costs of the petition.

## XXVIII.

The costs of hearing and deciding an objection upon the ground of insufficiency of a surety or sureties, shall be paid by the petitioner, and a clause to that effect shall be inserted in the order declaring its sufficiency or insufficiency, unless at the time of leaving the recognizance with the master, there be also left with the master an affidavit of the sufficiency of the surety or sureties sworn by each surety before a justice of the peace, which affidavit any justice of the peace is hereby authorized to take, or before some person authorized to take affidavits in the Court of Common Pleas, that he is seized or possessed of real or personal estate, or both, above what will satisfy his debts of the clear value of the sum for which he is bound by his recognizance, which affidavit may be as follows:—

In the Common Pleas.

“Parliamentary Elections Act, 1868.”

I, A. B. of [*as in recognizance*], make oath and say that I am seized or possessed of real [*or personal*] estate above what will satisfy my debts of the clear value of £

Sworn, &c.

## XXIX.

The order of the master for payment of costs shall have the same force as an order made by a judge, and may be made a rule of the Court of Common Pleas, and enforced in like manner as a judge's order.

## XXX.

The master shall make out the election list. In it he shall insert the name of the agents of the petitioners and respondent, and the addresses to which notices may be sent, if any. The list may be inspected at the master's office at any time during office hours, and shall be put up for that purpose upon a notice board appropriated to proceedings under the said Act, and headed “Parliamentary Elections Act, 1868.”

## XXXI.

The time and place of the trial of each election petition shall be fixed by the judges on the rota, and notice thereof shall be given in writing by the master by sticking notice up in his office, sending one copy by the post to the address given by the petitioner, another to the address given by the respondent, if any, and a copy by the post to the sheriff, or in case of a borough having a mayor, to the mayor of that borough, fifteen days before the day appointed for the trial.

The sheriff or mayor, as the case may be, shall forthwith publish the same in the county or borough.

## XXXII.

The sticking up of the notice of trial at the office of the master shall be deemed and taken to be notice in the prescribed manner within the meaning of the Act, and such notice shall not be vitiated by any mis-carriage of, or relating to, the copy or copies thereof to be sent as already directed.

## XXXIII.

The notice of trial may be in the following form :—

“Parliamentary Elections Act, 1868.”

Election petition of                      county [or borough] of

Take notice, that the above petition [or petitions] will be tried at                      on the                      day of                      and on such other subsequent days as may be needful.

Dated the                      day of                      .

By order,

(Signed)                      A.B.,

The master appointed under the above Act.

## XXXIV.

A judge may from time to time, by order made upon the application of a party to the petition, or by notice in such form as the judge may direct to be sent to the sheriff or mayor, as the case may be, postpone the beginning of the trial to such day as he may name, and such notice when received shall be forthwith made public by the sheriff or mayor.

## XXXV.

In the event of the judge not having arrived at the time appointed for the trial, or to which the trial is postponed, the commencement of the trial shall *ipso facto* stand adjourned to the ensuing day, and so from day to day.

## XXXVI.

No formal adjournment of the court for the trial of an election petition shall be necessary, but the trial is to be deemed adjourned, and may be continued from day to day until the inquiry is concluded; and in the event of the judge who begins the trial being disabled by illness or otherwise, it may be recommenced and concluded by another judge.

## XXXVII.

The application to state a special case may be made by rule in the Court of Common Pleas when sitting, or by a summons before a judge at chambers, upon hearing the parties.

## XXXVIII.

The title of the court of record held for the trial of an election petition may be as follows :—

Court for the trial of an election petition for the                      [county  
of                      or borough of                      as may be] between                      petitioner  
and                      respondent.

And it shall be sufficient so to entitle all proceedings in that court.

## XXXIX.

An officer shall be appointed for each court for the trial of an election petition, who shall attend at the trial in like manner as the clerks of assize and of arraigns attend at the assize.

## XL.

Repealed.

## XLI.

The order of a judge to compel the attendance, of a person as a witness may be in the following form :—

Court for the trial of an election petition for [*complete the title of the court*] the            day of            To A.B. [*describe the person*] You are hereby required to attend before the above court at [*place*] on the            day of            at the hour of [*or forthwith, as the case may be*] to be examined as a witness in the matter of the said petition, and to attend the said court until your examination shall have been completed.

As witness my hand,

A. B.,

Judge of the said court.

## XLII.

In the event of its being necessary to commit any person for contempt, the warrant may be as follows :—

At a court holden on            at            for the trial of an election petition for the county [*or borough*] of           , before Sir Samuel Martin, knight, one of the barons of her Majesty's Court of Exchequer, and one of the judges for the time being for the trial of election petitions in England, pursuant to "The Parliamentary Elections Act, 1868."

Whereas A. B. has this day been guilty, and is by the said court adjudged to be guilty, of a contempt thereof. The said court does therefore sentence the said A. B. for his said contempt to be imprisoned in the            gaol for            calendar months, and to pay to our lady the Queen a fine of £           , and to be further imprisoned in the said gaol until the said fine be paid. And the court further orders that the sheriff of the said county [*or as the case may be*] and all constables and officers of the peace of any county or place where the said A. B. may be found, shall take the said A. B. into custody and convey him to the said gaol, and there deliver him into the custody of the gaoler thereof, to undergo his said sentence. And the court further orders the said gaoler to receive the said A. B. into his custody, and that he shall be detained in the said gaol in pursuance of the said sentence.

A. D.

Signed the            day of

S. M.

## XLIII.

Such warrant may be made out and directed to the sheriff or other person having the execution of process of the superior courts, as the case may be, and to all constables and officers of the peace of the county or

place where the person adjudged guilty of contempt may be found, and such warrant shall be sufficient without further particularity, and shall and may be executed by the person to whom it is directed, or any or either of them.

## XLIV.

All interlocutory questions and matters, except as to the sufficiency of the security, shall be heard and disposed of before a judge, who shall have the same control over the proceedings under "The Parliamentary Elections Act, 1868," as a judge at chambers in the ordinary proceedings of the superior courts, and such questions and matters shall be heard and disposed of by one of the judges upon the rota, if practicable, and if not, then by any judge at chambers.

## XLV.

Notice of an application for leave to withdraw a petition shall be in writing and signed by the petitioners or their agent.

It shall state the ground on which the application is intended to be supported.

The following form shall be sufficient :—

"Parliamentary Elections Act, 1868."

County [*or borough*] of

Petition of [*state petitioners*], presented  
of

day

The petitioner proposes to apply to withdraw his petition upon the following ground [*here state the ground*], and prays that a day may be appointed for hearing his application. Dated this       day of  
(Signed)

## XLVI.

The notice of application for leave to withdraw shall be left at the master's office.

## XLVII.

A copy of such notice of the intention of the petitioner to apply for leave to withdraw his petition shall be given by the petitioner to the respondent, and to the returning officer, who shall make it public in the county or borough to which it relates, and shall be forthwith published by the petitioner in at least one newspaper circulating in the place.

The following may be the form of such notice :—

"Parliamentary Elections Act, 1868."

In the election petition for       in which       is petitioner and  
respondent.

Notice is hereby given that the above petitioner has on the  
day of       lodged at the master's office, notice of an application  
to withdraw the petition, of which notice the following is a copy—(*set  
it out.*)

And take notice that, by the rule made by the judges, any person who might have been a petitioner in respect of the said election may, within five days after publication by the returning officer of this notice, give notice in writing of his intention on the hearing to apply for leave to be substituted as a petitioner.

(Signed)

## XLVIII.

Any person who might have been a petitioner in respect of the election to which the petition relates, may, within five days after such notice is published by the returning officer, give notice in writing, signed by him or on his behalf, to the master, of his intention to apply at the hearing to be substituted for the petitioner, but the want of such notice shall not defeat such application if in fact made at the hearing.

## XLIX.

The time and place for hearing the application shall be fixed by a judge, and whether before the Court of Common Pleas, or before a judge, as he may deem advisable, but shall not be less than a week after the notice of the intention to apply has been given to the master as herein-before provided, and notice of the time and place appointed for the hearing shall be given to such person or persons, if any, as shall have given notice to the master of an intention to apply to be substituted as petitioners, and otherwise in such manner and at such time as the judge directs.

## L.

Notice of abatement of a petition, by death of the petitioner or surviving petitioner, under Section 37 of the said Act, shall be given by the party or person interested in the same manner as notice of an application to withdraw a petition; and the time within which application may be made to the court or a judge, by motion or summons at chambers, to be substituted as a petitioner, shall be one calendar month, or such further time as upon consideration of any special circumstances, the court or a judge may allow.

## LI.

If the respondent dies or is summoned to Parliament as a peer of Great Britain by a writ issued under the great seal of Great Britain, or if the House of Commons have resolved that his seat is vacant, any person entitled to be a petitioner under the Act in respect of the election to which the petition relates, may give notice of the fact in the county or borough by causing such notice to be published in at least one newspaper circulating therein, if any, and by leaving a copy of such notice signed by him or on his behalf with the returning officer, and a like copy with the master.

## LII.

The manner and time of the respondent's giving notice to the court that he does not intend to oppose the petition, shall be by leaving notice thereof in writing at the office of the master, signed by the respondent, six days before the day appointed for trial, exclusive of the day of leaving such notice.

## LIII.

Upon such notice being left at the master's office, the master shall forthwith send a copy thereof by the post to the petitioner or his agent and to the sheriff or mayor, as the case may be, who shall cause the same to be published in the county or borough.

## LIV.

The time for applying to be admitted as a respondent in either of the events mentioned in the 38th Section of the Act shall be within ten days after such notice is given as hereinbefore directed, or such further time as the court or a judge may allow.

## LV.

Costs shall be taxed by the master, or at his request, by any master of a superior court, upon the rule of court or judge's order by which the costs are payable, and costs when taxed may be recovered by execution issued upon the rule of court ordering them to be paid ; or, if payable by the order of a judge, then by making such order a rule of court in the ordinary way, and issuing execution upon such rule against the person by whom the costs are ordered to be paid, or in case there be money in the bank available for the purpose, then to the extent of such money by order of the Chief Justice of the Common Pleas for the time being, upon a duplicate of the rule of court.

The office fees payable for inspection, office copies, enrolment, and other proceedings under the Act, and these rules, shall be the same as those payable, if any, for like proceedings according to the present practice of the Court of Common Pleas.

## LVI.

The master shall prepare and keep a roll properly headed for entering the names of all persons entitled to practise as attorney or agent in cases of election petitions, and all matters relating to elections before the court and judges, pursuant to the 57th Section of the said Act ; which roll shall be kept and dealt with in all respects as the roll of attorneys of the Court of Common Pleas, and shall be under the control of that court, as to striking off the roll and otherwise.

## LVII.

The entry upon the roll shall be written and subscribed by the attorney or agent, or some attorney authorised by him in writing to sign on his behalf, who shall therein set forth the name, description and address in full.

## LVIII.

The master may allow any person upon the roll of attorneys for the time being, and during the present year any person whose name, or the name of whose firm is in the Law List of the present year as a Parliamentary agent to subscribe the roll, and permission to subscribe the roll may be granted to any other person by the court or judge upon affidavit, showing the facts which entitle the applicant to practise as agent according to the principles, practice and rules of the House of Commons in cases of election petitions.

## LIX.

An agent employed for the petitioner or respondent shall forthwith leave written notice at the office of the master of his appointment to act as such agent, and service of notices and proceedings upon such agent shall be sufficient for all purposes.

## LX.

No proceeding under "The Parliamentary Elections Act, 1868," shall be defeated by any formal objection.

## LXI.

Any rule made or to be made in pursuance of the Act, if made in Term time, shall be published by being read by the master in the Court of Common Pleas, and if made out of Term, by a copy thereof being put up at the master's office.

Dated the 21st day of November, 1868.

SAMUEL MARTIN.           ×

J. S. WILLES.           ×

COLIN BLACKBURN.       ×

*The Judges for the trial of Election Petitions in England.*

Read in open court, Common Pleas,  
the 23rd day of November, 1868.

**“ADDITIONAL GENERAL RULE (PARLIAM-  
MENTARY), Dec., 1868.”**

That notice of the time and place of the trial of each election petition shall be transmitted by the master to the treasury, and to the clerk of the crown in chancery, and that the clerk of the crown in chancery shall, on or before the day fixed for the trial, deliver or cause to be delivered to the registrar of the judge who is to try the petition, or his deputy, the poll-books, for which the registrar or his deputy shall give, if required, a receipt. And that the registrar shall keep in safe custody the said poll-books until the trial is over, and then return the same to the crown office.

SAMUEL MARTIN.  
J. S. WILLES.  
COLIN BLACKBURN.

Dated the 19th day of December, 1868.



✱

“ADDITIONAL GENERAL RULES (PARLIAM-  
MENTARY), March, 1869.”

## I.

All claims at law or in equity to money deposited or to be deposited in the Bank of England for payment of costs, charges and expenses payable by the petitioners pursuant to the 16th General Rule, made the 21st November, 1868, by the judges for the trial of election petitions in England, shall be disposed of by the Court of Common Pleas or a judge.

## II.

Money so deposited shall, if and when the same is no longer needed for securing payment of such costs, charges and expenses, be returned or otherwise disposed of as justice may require, by rule of the Court of Common Pleas or order of a judge.

## III.

Such rule or order may be made after such notice of intention to apply, and proof that all just claims have been satisfied or otherwise sufficiently provided for as the court or judge may require.

## IV.

The rule or order may direct payment either to the party in whose name the same is deposited or to any person entitled to receive the same.

## V.

Upon such rule or order being made, the amount may be drawn for by the Chief Justice of the Common Pleas for the time being.

## VI.

The draft of the Chief Justice of the Common Pleas for the time being shall, in all cases, be a sufficient warrant to the Bank of England for all payments made thereunder.

Dated the 25th day of March, 1869.

SAMUEL MARTIN.	×
J. S. WILLES.	×
COLIN BLACKBURN.	×

*The Judges for the trial of Election Petitions  
in England.*

♦

“ADDITIONAL GENERAL RULES (PARLIAM-  
MENTARY), January, 1875.”

I.

A copy of every order (other than an order giving further time for delivering particulars, or for costs only), or if the master shall so direct, the order itself or a duplicate thereof, also a copy of every particular delivered, shall be forthwith filed with the master, and the same shall be produced at the trial by the registrar, stamped with the official seal. Such order and particular respectively shall be filed by the party obtaining the same.

II.

The petitioner or his agent shall, immediately after notice of the presentation of a petition and of the nature of the proposed security shall have been served, file with the master an affidavit of the time and manner of service thereof.

III.

The days mentioned in Rules 7 and 8, and in any rule of court or judge's order, whereby particulars are ordered to be delivered, or any act is directed to be done, so many days before the day appointed for trial, are exclusively also of Sunday, Christmas Day, Good Friday, and any day set apart for a public fast or public thanksgiving.

IV.

When the last day for presenting petitions or filing lists of votes or objections, under Rules 7 or 8, or recognizances, or any other matter required to be filed within a given time, shall happen to fall on a holiday, the petition or other matter shall be deemed duly filed if put into the letter box at the master's office at any time during such day; but an affidavit, stating with reasonable precision the time when such delivery was made, shall be filed on the first day after the expiration of the holidays.

V.

Rule 40 is hereby revoked, and in lieu thereof it is ordered that the amount to be paid to any witness whose expenses shall be allowed by the judge shall be ascertained and certified by the registrar; or in the event of his becoming incapacitated from giving such certificate, by the judge.

VI.

After receiving notice of the petitioner's intention to apply for leave to withdraw, or of the respondent's intention not to oppose, or of the abatement of the petition by death, or of the happening of any of the

events mentioned in the 38th section of the Act, if such notice be received after notice of trial shall have been given, and before the trial has commenced, the master shall forthwith countermand the notice of trial. The countermand shall be given in the same manner, as near as may be, as the notice of trial.

Dated the 27th day of January, 1875.

G. PIGOTT.  
ROBT. LUSH.  
GEORGE E. HONYMAN.

*Judges for the time being on the rota for the trial  
of Election Petitions in England.*      v

## CORRUPT AND ILLEGAL PRACTICES PREVENTION ACT, 1883.

46 & 47 Vict.  
c. 51.

46 & 47 VICT. c. 51.

### An Act for the Better Prevention of Corrupt and Illegal Practices at Parliamentary Elections. [25th August, 1883.]

BE it enacted by the Queen's most Excellent Majesty, by and with the advice and consent of the Lords Spiritual and Temporal, and Commons, in this present Parliament assembled, and by the authority of the same, as follows :—

#### *Corrupt Practices.*

What is  
treating.

1. Whereas under Section 4 of the Corrupt Practices Prevention Act, 1854, persons other than candidates at parliamentary elections are not liable to any punishment for treating, and it is expedient to make such persons liable; be it therefore enacted in substitution for the said Section 4, as follows :—

- (1.) Any person who corruptly by himself or by any other person, either before, during, or after an election, directly or indirectly gives or provides, or pays wholly or in part the expense of giving or providing, any meat, drink, entertainment or provision to or for any person, for the purpose of corruptly influencing that person or any other person to give or refrain from giving his vote at the election, or on account of such person or any other person having voted or refrained from voting, or being about to vote or refrain from voting at such election, shall be guilty of treating.
- (2.) And every elector who corruptly accepts or takes any such meat, drink, entertainment or provision shall also be guilty of treating.

What is undue  
influence.

2. Every person who shall directly or indirectly, by himself or by any other person on his behalf, make use of or threaten to make use of any force, violence, or restraint, or inflict or threaten to inflict, by himself or by any other person, any temporal or spiritual injury, damage, harm, or loss upon or against any person in order to induce or compel such person to vote or refrain from voting, or on account of such person having voted or refrained from voting at any election, or who shall by abduction, duress, or any fraudulent device or contrivance impede or prevent the free exercise of the franchise of any elector, or shall thereby compel, induce, or prevail upon any elector either to give or to refrain from giving his vote at any election, shall be guilty of undue influence.

What is corrupt  
practice.

3. The expression "corrupt practice" as used in this Act means any of the following offences: namely, treating and undue influence, as

defined by this Act, and bribery, and personation, as defined by the enactments set forth in Part III. of the Third Schedule to this Act, and aiding, abetting, counselling, and procuring the commission of the offence of personation, and every offence which is a corrupt practice within the meaning of this Act shall be a corrupt practice within the meaning of the Parliamentary Elections Act, 1868.

31 & 32 Vict.  
c. 125.

4. Where upon the trial of an election petition respecting an election for a county or borough the election court, by the report made to the Speaker in pursuance of Section 11 of the Parliamentary Elections Act, 1868, reports that any corrupt practice other than treating or undue influence has been proved to have been committed in reference to such election by or with the knowledge and consent of any candidate at such election, or that the offence of treating or undue influence has been proved to have been committed in reference to such election, by any candidate at such election, that candidate shall not be capable of ever being elected to or sitting in the House of Commons for the said county or borough, and if he has been elected, his election shall be void: and he shall further be subject to the same incapacities as if at the date of the said report he had been convicted on an indictment of a corrupt practice.

Punishment of  
candidate  
found, on  
election  
petition, guilty  
personally of  
corrupt  
practices.  
31 & 32 Vict.  
c. 125.

5. Upon the trial of an election petition respecting an election for a county or borough, in which a charge is made of any corrupt practice having been committed in reference to such election, the election court shall report in writing to the Speaker whether any of the candidates at such election has been guilty by his agents of any corrupt practice in reference to such election: and if the report is that any candidate at such election has been guilty by his agents of any corrupt practice in reference to such election, that candidate shall not be capable of being elected to or sitting in the House of Commons for such county or borough for seven years after the date of the report, and if he has been elected his election shall be void.

Punishment of  
candidate  
found, on  
election  
petition, guilty  
by agents of  
corrupt  
practices.

6. (1.) A person who commits any corrupt practice other than personation, or aiding, abetting, counselling, or procuring the commission of the offence of personation, shall be guilty of a misdemeanour, and on conviction on indictment shall be liable to be imprisoned, with or without hard labour, for a term not exceeding one year, or to be fined any sum not exceeding two hundred pounds.

Punishment of  
person con-  
victed on  
indictment of  
corrupt  
practices.

(2.) A person who commits the offence of personation, or of aiding, abetting, counselling, or procuring the commission of that offence, shall be guilty of felony, and any person convicted thereof, on indictment shall be punished by imprisonment for a term not exceeding two years, together with hard labour.

(3.) A person who is convicted on indictment of any corrupt practice shall (in addition to any punishment as above provided) be not capable during a period of seven years from the date of his conviction:

(a.) of being registered as an elector or voting at any election in the United Kingdom, whether it be a parliamentary election or an election for any public office within the meaning of this Act; or

(b.) of holding any public or judicial office with the meaning of this Act, and if he holds any such office the office shall be vacated.

(4.) Any person so convicted of a corrupt practice in reference to any election shall also be incapable of being elected to and of sitting in the House of Commons during the seven years next after the date of his conviction, and if at that date he has been elected to the House of Commons his election shall be vacated from the time of such conviction.

*Illegal practices.*

Certain expenditure to be illegal practice.

7. (1.) No payment or contract for payment shall, for the purpose of promoting or procuring the election of a candidate at any election, be made—

- (a.) on account of the conveyance of electors to or from the poll, whether for the hiring of horses or carriages, or for railway fares, or otherwise ; or
- (b.) to an elector on account of the use of any house, land, building, or premises for the exhibition of any address, bill, or notice, or on account of the exhibition of any address, bill, or notice ; or
- (c.) on account of any committee-room in excess of the number allowed by the First Schedule to this Act.

(2.) Subject to such exception as may be allowed in pursuance of this Act, if any payment or contract for payment is knowingly made in contravention of this section either before, during, or after an election, the person making such payment or contract shall be guilty of an illegal practice, and any person receiving such payment or being a party to any such contract, knowing the same to be in contravention of this Act, shall be guilty of an illegal practice.

(3.) Provided that where it is the ordinary business of an elector as an advertising agent to exhibit for payment bills and advertisements, a payment to or contract with such elector, if made in the ordinary course of business, shall not be deemed to be an illegal practice within the meaning of this section.

Expense in excess of maximum to be illegal practice.

8. (1.) Subject to such exception as may be allowed in pursuance of this Act, no sum shall be paid and no expense shall be incurred by a candidate at an election or his election agent, whether before, during, or after an election, on account of or in respect of the conduct or management of such election, in excess of any maximum amount in that behalf specified in the First Schedule to this Act.

(2.) Any candidate or election agent who knowingly acts in contravention of this section shall be guilty of an illegal practice.

Voting by prohibited persons and publishing of false statements of withdrawal to be illegal.

9. (1.) If any person votes or induces or procures any person to vote at any election, knowing that he or such person is prohibited, whether by this or any other Act from voting at such election, he shall be guilty of an illegal practice.

(2.) Any person who before or during an election knowingly publishes a false statement of the withdrawal of a candidate at such election for the purpose of promoting or procuring the election of another candidate shall be guilty of an illegal practice.

(3.) Provided that a candidate shall not be liable, nor shall his election be avoided, for any illegal practice under this section committed by his agent other than his election agent.

10. A person guilty of an illegal practice, whether under the foregoing sections or under the provisions hereinafter contained in this Act, shall on summary conviction be liable to a fine not exceeding one hundred pounds, and be incapable during a period of five years from the date of his conviction of being registered as an elector or voting at any election (whether it be a parliamentary election or an election for a public office within the meaning of this Act) held for or within the county or borough in which the illegal practice has been committed.

Punishment on conviction of illegal practice.

11. Whereas by sub-section 14 of Section 11 of the Parliamentary Elections Act, 1868, it is provided that where a charge is made in an election petition of any corrupt practice having been committed at the election to which the petition refers, the judge shall report in writing to the speaker as follows:—

Report of election court respecting illegal practice, and punishment of candidate found guilty by such report.  
31 & 32 Vict. c. 125.

(a.) "Whether any corrupt practice has or has not been proved to have been committed by or with the knowledge and consent of any candidate at such election, and the nature of such corrupt practice :

(b.) "The names of all persons, if any, who have been proved at the trial to have been guilty of any corrupt practice :

(c.) "Whether corrupt practices have, or whether there is reason to believe corrupt practices have extensively prevailed at the election to which the petition relates" :

And whereas it is expedient to extend the said sub-section to illegal practices :

Be it therefore enacted as follows :—

Sub-section 14 of Section 11 of the Parliamentary Elections Act, 1868, shall apply as if that sub-section were herein re-enacted with the substitution of illegal practice within the meaning of this Act for corrupt practice ; and upon the trial of an election petition respecting an election for a county or borough, the election court shall report in writing to the speaker the particulars required by the said sub-section as herein re-enacted, and shall also report whether any candidate at such election has been guilty by his agents of any illegal practice within the meaning of this Act in reference to such election, and the following consequences shall ensue upon the report by the election court to the speaker ; (that is to say)

31 & 32 Vict., c. 125.

(a.) If the report is that any illegal practice has been proved to have been committed in reference to such election by or with the knowledge and consent of any candidate at such election, that candidate shall not be capable of being elected to or sitting in the House of Commons for the said county or borough for seven years next after the date of the report, and if he has been elected his election shall be void ; and he shall further be subject to the same incapacities as if at the date of the report he had been convicted of such illegal practice ; and

(b.) If the report is that a candidate at such election has been guilty by his agents of any illegal practice in reference to such election, that candidate shall not be capable of being elected to or sitting in the House of Commons for the said county or borough during the Parliament for which the election was held, and if he has been elected, his election shall be void.

12. Whereas by the Election Commissioners Act, 1852, as amended by the Parliamentary Elections Act, 1868, it is enacted that where a

Extension of 15 & 16 Vict. c. 57, respecting

election commissioners to illegal practices.  
15 & 16 Vict.  
c. 57.  
31 & 32 Vict.  
c. 57.

joint address of both Houses of Parliament represents to Her Majesty that an election court has reported to the Speaker that corrupt practices have, or that there is reason to believe that corrupt practices have extensively prevailed at an election in any county or borough, and prays Her Majesty to cause inquiry under that Act to be made by persons named in such address (being qualified as therein mentioned), it shall be lawful for Her Majesty to appoint the said persons to be election commissioners for the purpose of making inquiry into the existence of such corrupt practices :

And whereas it is expedient to extend the said enactments to the case of illegal practices :

Be it therefore enacted as follows :

15 & 16 Vict.  
c. 57.

When election commissioners have been appointed in pursuance of the Election Commissioners Act, 1852, and the enactments amending the same, they may make inquiries and act and report as if "corrupt practices" in the said Act and the enactments amending the same included illegal practices ; and the Election Commissioners Act, 1852, shall be construed with such modifications as are necessary for giving effect to this section, and the expression "corrupt practice" in that Act shall have the same meaning as in this Act.

### *Illegal Payment, Employment, and Hiring.*

Providing of money for hackney carriage or payment to be illegal payment.

13. Where a person knowingly provides money for any payment which is contrary to the provisions of this Act, or for any expenses incurred in excess of any maximum amount allowed by this Act, or for replacing any money expended in any such payment or expenses, except where the same may have been previously allowed in pursuance of this Act to be an exception, such person shall be guilty of illegal payment.

Employment of hackney carriages, or of carriages and horses kept for hire.

14. (1.) A person shall not let, lend, or employ for the purpose of the conveyance of electors to or from the poll, any public stage or hackney carriage, or any horse or other animal kept or used for drawing the same, or any carriage, horse, or other animal which he keeps or uses for the purpose of letting out for hire, and if he lets, lends, or employs such carriage, horse, or other animal, knowing that it is intended to be used for the purpose of the conveyance of electors to or from the poll, he shall be guilty of an illegal hiring.

(2.) A person shall not hire, borrow, or use for the purpose of the conveyance of electors to or from the poll any carriage, horse, or other animal which he knows the owner thereof is prohibited by this section to let, lend, or employ for that purpose, and if he does so he shall be guilty of an illegal hiring.

(3.) Nothing in this Act shall prevent a carriage, horse, or other animal being let to or hired, employed, or used by an elector, or several electors at their joint cost, for the purpose of being conveyed to or from the poll.

(4.) No person shall be liable to pay any duty or to take out a license for any carriage by reason only of such carriage being used without payment or promise of payment for the conveyance of electors to or from the poll at an election.

Corrupt with-

15. Any person who corruptly induces or procures any other person



to withdraw from being a candidate at an election, in consideration of any payment or promise of payment, shall be guilty of illegal payment, and any person withdrawing, in pursuance of such inducement or procurement, shall also be guilty of illegal payment.

drawal from a candidature.

16. (1.) No payment or contract for payment shall, for the purpose of promoting or procuring the election of a candidate at any election, be made on account of bands of music, torches, flags, banners, cockades, ribbons, or other marks of distinction.

Certain expenditure to be illegal payment.

(2.) Subject to such exception as may be allowed in pursuance of this Act, if any payment or contract for payment is made in contravention of this section, either before, during, or after an election, the person making such payment shall be guilty of illegal payment, and any person being a party to any such contract or receiving such payment shall also be guilty of illegal payment if he knew that the same was made contrary to law.

17. (1.) No person shall, for the purpose of promoting or procuring the election of a candidate at any election, be engaged or employed for payment or promise of payment for any purpose or in any capacity whatever, except for any purposes or capacities mentioned in the first or second parts of the First Schedule to this Act, or except so far as payment is authorised by the first or second parts of the First Schedule to this Act.

Certain employment to be illegal.

(2.) Subject to such exception as may be allowed in pursuance of this Act, if any person is engaged or employed in contravention of this section, either before, during, or after an election, the person engaging or employing him shall be guilty of illegal employment, and the person so engaged or employed shall also be guilty of illegal employment if he knew that he was engaged or employed contrary to law.

18. Every bill, placard, or poster having reference to an election shall bear upon the face thereof the name and address of the printer and publisher thereof; and any person printing, publishing, or posting, or causing to be printed, published, or posted, any such bill, placard, or poster as aforesaid, which fails to bear upon the face thereof the name and address of the printer and publisher, shall, if he is the candidate, or the election agent of the candidate, be guilty of an illegal practice, and if he is not the candidate, or the election agent of a candidate, shall be liable on summary conviction to a fine not exceeding one hundred pounds.

Name and address of printer on placards.

19. The provisions of this Act prohibiting certain payments and contracts for payments, and the payment of any sum, and the incurring of any expense in excess of a certain maximum, shall not affect the right of any creditor, who, when the contract was made or the expense was incurred, was ignorant of the same being in contravention of this Act.

Saving for creditors.

20. (a.) Any premises on which the sale by wholesale or retail of any intoxicating liquor is authorised by a licence (whether the licence be for consumption on or off the premises), or

Use of committee room in house for sale of

intoxicating liquor or refreshment, or in elementary school, to be illegal hiring.

(b.) Any premises where any intoxicating liquor is sold, or is supplied to members of a club, society, or association other than a permanent political club, or

(c.) Any premises whereon refreshment of any kind, whether food or drink, is ordinarily sold for consumption on the premises, or

(d.) The premises of any public elementary school in receipt of an annual parliamentary grant, or any part of any such premises, or shall not be used as a committee room for the purpose of promoting or procuring the election of a candidate at an election, and if any person hires or uses any such premises or any part thereof for a committee room he shall be guilty of illegal hiring, and the person letting such premises or part, if he knew it was intended to use the same as a committee room, shall also be guilty of illegal hiring :

Provided that nothing in this Section shall apply to any part of such premises which is ordinarily let for the purpose of chambers or offices or the holding of public meetings or of arbitrations, if such part has a separate entrance and no direct communication with any part of the premises on which any intoxicating liquor or refreshment is sold or supplied as aforesaid.

Punishment of illegal payment, employment, or hiring.

21. (1.) A person guilty of an offence of illegal payment, employment or hiring shall, on summary conviction, be liable to a fine not exceeding one hundred pounds.

(2.) A candidate or an election agent of a candidate who is personally guilty of an offence of illegal payment, employment, or hiring shall be guilty of an illegal practice.

*Excuse and Exception for Corrupt or Illegal Practice or Illegal Payment, Employment, or Hiring.*

Report exonerating candidate in certain cases of corrupt and illegal practice by agents.

22. Where, upon the trial of an election petition respecting an election for a county or borough, the election court report that a candidate at such election has been guilty by his agents of the offence of treating and undue influence, and illegal practice, or of any of such offences, in reference to such election, and the election court further report that the candidate has proved to the court :

(a.) That no corrupt or illegal practice was committed at such election by the candidate or his election agent and the offences mentioned in the said report were committed contrary to the orders and without the sanction or connivance of such candidate or his election agent ; and

(b.) That such candidate and his election agent took all reasonable means for preventing the commission of corrupt and illegal practices at such election ; and

(c.) That the offences mentioned in the said report were of a trivial, unimportant, and limited character ; and

(d.) That in all other respects the election was free from any corrupt or illegal practice on the part of such candidate and of his agents ;

then the election of such candidate shall not, by reason of the offences mentioned in such report, be void, nor shall the candidate be subject to any incapacity under this Act.

Power of High Court and election court

23. Where, on application made, it is shown to the High Court or to an election court by such evidence as seems to the Court sufficient :

- (a.) That any act or omission of a candidate at any election, or of his election agent or of any other agent or person, would, by reason of being a payment, engagement, employment, or contract in contravention of this Act, or being the payment of a sum or the incurring of expense in excess of any maximum amount allowed by this Act, or of otherwise being in contravention of any of the provisions of this Act, be but for this section an illegal practice, payment, employment, or hiring; and
- (b.) That such act or omission arose from inadvertence or from accidental miscalculation or from some other reasonable cause of a like nature, and in any case did not rise from any want of good faith; and
- (c.) That such notice of the application has been given in the county or borough for which the election was held as to the court seems fit;

to except innocent act from being illegal practice, &c.

and under the circumstances it seems to the court to be just that the candidate and the said election and other agent and person, or any of them, should not be subject to any of the consequences under this Act of the said act or omission, the court may make an order allowing such act or omission to be an exception from the provisions of this Act which would otherwise make the same an illegal practice, payment, employment, or hiring, and thereupon such candidate, agent, or person shall not be subject to any of the consequences under this Act of the said act or omission.

#### *Election Expenses.*

24. (1.) On or before the day of nomination at an election, a person shall be named by or on behalf of each candidate as his agent for such election (in this Act referred to as the election agent).

Nomination of election agent.

(2.) A candidate may name himself as election agent, and thereupon shall, so far as circumstances admit, be subject to the provisions of this Act both as a candidate and as an election agent, and any reference in this Act to an election agent shall be construed to refer to the candidate acting in his capacity of election agent.

(3.) On or before the day of nomination the name and address of the election agent of each candidate shall be declared in writing by the candidate or some other person on his behalf to the returning officer, and the returning officer shall forthwith give public notice of the name and address of every election agent so declared.

(4.) One election agent only shall be appointed for each candidate, but the appointment, whether the election agent appointed be the candidate himself or not, may be revoked, and in the event of such revocation or his death, whether such event is before, during, or after the election, then forthwith another election agent shall be appointed, and his name and address declared in writing to the returning officer, who shall forthwith give public notice of the same.

25. (1.) In the case of the elections specified in that behalf in the First Schedule to this Act an election agent of a candidate may appoint the number of deputies therein mentioned (which deputies are in this Act referred to as sub-agents), to act within different polling districts.

Nomination of deputy election agent as sub-agent.

(2.) As regards matters in a polling district the election agent may act by the sub-agent for that district, and anything done for the purposes

of this Act by or to the sub-agent in his district shall be deemed to be done by or to the election agent, and any act or default of a sub-agent which, if he were the election agent, would be an illegal practice or other offence against this Act, shall be an illegal practice and offence against this Act committed by the sub-agent, and the sub-agent shall be liable to punishment accordingly; and the candidate shall suffer the like incapacity as if the said act or default had been the act or default of the election agent.

(3.) One clear day before the polling the election agent shall declare in writing the name and address of every sub-agent to the returning officer, and the returning officer shall forthwith give public notice of the name and address of every sub-agent so declared.

(4.) The appointment of a sub-agent shall not be vacated by the election agent who appointed him ceasing to be election agent, but may be revoked by the election agent for the time being of the candidate, and in the event of such revocation or of the death of a sub-agent another sub-agent may be appointed, and his name and address shall be forthwith declared in writing to the returning officer, who shall forthwith give public notice of the same.

Office of election agent and sub-agent.

26. (1.) An election agent at an election for a county or borough shall have within the county or borough, or within any county of a city or town adjoining thereto, and a sub-agent shall have within his district, or within any county of a city or town adjoining thereto, an office or place to which all claims, notices, writs, summonses, and documents may be sent, and the address of such office or place shall be declared at the same time as the appointment of the said agent to the returning officer, and shall be stated in the public notice of the name of the agent.

(2.) Any claim, notice, writ, summons, or document delivered at such office or place and addressed to the election agent or sub-agent, as the case may be, shall be deemed to have been served on him, and every such agent may in respect of any matter connected with the election in which he is acting be sued in any court having jurisdiction in the county or borough in which the said office or place is situate.

Making of contracts through election agent.

27. (1.) The election agent of a candidate by himself or by his sub-agent shall appoint every polling agent, clerk, and messenger employed for payment on behalf of the candidate at an election, and hire every committee-room hired on behalf of the candidate.

(2.) A contract whereby any expenses are incurred on account of or in respect of the conduct or management of an election shall not be enforceable against a candidate at such election unless made by the candidate himself or by his election agent, either by himself or by his sub-agent; provided that the inability under this section to enforce such contract against the candidate shall not relieve the candidate from the consequences of any corrupt or illegal practice having been committed by his agent.

Payment of expenses through election agent.

28. (2.) Except as permitted by or in pursuance of this Act, no payment and no advance or deposit shall be made by a candidate at an election or by any agent on behalf of the candidate or by any other person at any time, whether before, during, or after such election, in respect of any expenses incurred on account of or in respect of the

conduct or management of such election, otherwise than by or through the election agent of the candidate, whether acting in person or by a sub-agent; and all money provided by any person other than the candidate for any expenses incurred on account of or in respect of the conduct or management of the election, whether as gift, loan, advance, or deposit, shall be paid to the candidate or his election agent and not otherwise;

Provided that this section shall not be deemed to apply to a tender of security to or any payment by the returning officer or to any sum disbursed by any person out of his own money for any small expense legally incurred by himself, if such sum is not repaid to him.

(2.) A person who makes any payment, advance, or deposit in contravention of this section, or pays in contravention of this section any money so provided as aforesaid, shall be guilty of an illegal practice.

29. (1.) Every payment made by an election agent, whether by himself or a sub-agent, in respect of any expenses incurred on account of or in respect of the conduct or management of an election, shall, except where less than forty shillings, be vouched for by a bill stating the particulars and by a receipt.

Period for sending in claims and making payments for election expenses.

(2.) Every claim against a candidate at an election or his election agent in respect of any expenses incurred on account of or in respect of the conduct or management of such election which is not sent in to the election agent within the time limited by this Act shall be barred and shall not be paid; and, subject to such exception as may be allowed in pursuance of this Act, an election agent who pays a claim in contravention of this enactment shall be guilty of an illegal practice.

(3.) Except as by this Act permitted, the time limited by this Act for sending in claims shall be fourteen days after the day on which the candidates returned are declared elected.

(4.) All expenses incurred by or on behalf of a candidate at an election, which are incurred on account of or in respect of the conduct or management of such election, shall be paid within the time limited by this Act and not otherwise; and, subject to such exception as may be allowed in pursuance of this Act, an election agent who makes a payment in contravention of this provision shall be guilty of an illegal practice.

(5.) Except as by this Act permitted, the time limited by this Act for the payment of such expenses as aforesaid shall be twenty-eight days after the day on which the candidates returned are declared elected.

(6.) Where the election court reports that it has been proved to such court by a candidate that any payment made by an election agent in contravention of this section was made without the sanction or connivance of such candidate, the election of such candidate shall not be void, nor shall he be subject to any incapacity under this Act by reason only of such payment having been made in contravention of this section.

(7.) If the election agent in the case of any claim sent in to him within the time limited by this Act disputes it, or refuses or fails to pay it within the said period of twenty-eight days, such claim shall be deemed to be a disputed claim.

(8.) The claimant may, if he thinks fit, bring an action for a disputed claim in any competent court; and any sum paid by the candidate or his agent in pursuance of the judgment or order of such court shall be deemed to be paid within the time limited by this Act, and to be an

exception from the provisions of this Act requiring claims to be paid by the election agent.

(9.) On cause shown to the satisfaction of the High Court, such court, on application by the claimant or by the candidate or his election agent, may by order give leave for the payment by a candidate or his election agent of a disputed claim, or of a claim for any such expenses as aforesaid, although sent in after the time in this section mentioned for sending in claims, or although the same was sent in to the candidate and not to the election agent.

(10.) Any sum specified in the order of leave may be paid by the candidate or his election agent, and when paid in pursuance of such leave shall be deemed to be paid within the time limited by this Act.

Reference to  
taxation of  
claim against  
candidates.

**30.** If any action is brought in any competent court to recover a disputed claim against a candidate at an election, or his election agent, in respect of any expenses incurred on account or in respect of the conduct or management of such election, and the defendant admits his liability, but disputes the amount of the claim, the said amount shall, unless the court, on the application of the plaintiff in the action otherwise directs, be forthwith referred for taxation to the master, official referee, registrar, or other proper officer of the court, and the amount found due on such taxation shall be the amount to be recovered in such action in respect of such claim.

Personal  
expenses of  
candidate and  
petty expenses.

**31. (1.)** The candidate at an election may pay any personal expenses incurred by him on account of or in connection with or incidental to such election to an amount not exceeding one hundred pounds, but any further personal expenses so incurred by him shall be paid by his election agent.

(2.) The candidate shall send to the election agent within the time limited by this Act for sending in claims a written statement of the amount of personal expenses paid as aforesaid by such candidate.

(3.) Any person may, if so authorised in writing by the election agent of the candidate, pay any necessary expenses for stationery, postage, telegrams, and other petty expenses, to a total amount not exceeding that named in the authority, but any excess above the total amount so named shall be paid by the election agent.

(4.) A statement of the particulars of payments made by any person so authorised shall be sent to the election agent within the time limited by this Act for the sending in of claims, and shall be vouched for by a bill containing the receipt of that person.

Remuneration  
of election  
agent and  
returning  
officer's  
expenses.

**32. (1.)** So far as circumstances admit, this Act shall apply to a claim for his remuneration by an election agent and to the payment thereof in like manner as if he were any other creditor, and if any difference arises respecting the amount of such claim, the claim shall be a disputed claim within the meaning of this Act, and be dealt with accordingly.

(2.) The account of the charges claimed by the returning officer in the case of a candidate and transmitted in pursuance of Section 4 of the Parliamentary Elections (Returning Officers) Act, 1875, shall be transmitted within the time specified in the said section to the election agent of the candidate, and need not be transmitted to the candidate.

**33.** (1.) Within thirty-five days after the day on which the candidates returned at an election are declared elected, the election agent of every candidate at that election shall transmit to the returning officer a true return (in this Act referred to as a return respecting election expenses), in the form set forth in the Second Schedule to this Act or to the like effect, containing, as respects that candidate :—

Return and declaration respecting election expenses.

- (a.) A statement of all payments made by the election agent, together with all the bills and receipts (which bills and receipts are in this Act included in the expression "return respecting election expenses");
- (b.) A statement of the amount of personal expenses, if any, paid by the candidate;
- (c.) A statement of the sums paid to the returning officer for his charges, or, if the amount is in dispute, of the sum claimed and the amount disputed;
- (d.) A statement of all other disputed claims of which the election agent is aware;
- (e.) A statement of all the unpaid claims, if any, of which the election agent is aware, in respect of which application has been or is about to be made to the High Court;
- (f.) A statement of all money, securities, and equivalent of money received by the election agent from the candidate or any other person for the purpose of expenses incurred or to be incurred on account of or in respect of the conduct or management of the election, with a statement of the name of every person from whom the same may have been received.

(2.) The return so transmitted to the returning officer shall be accompanied by a declaration made by the election agent before a justice of the peace in the form in the Second Schedule to this Act (which declaration is in this Act referred to as a declaration respecting election expenses).

(3.) Where the candidate has named himself as his election agent, a statement of all money, securities, and equivalent of money paid by the candidate shall be substituted in the return required by this section to be transmitted by the election agent for the like statement of money, securities, and equivalent of money received by the election agent from the candidate; and the declaration by an election agent respecting election expenses need not be made, and the declaration by the candidate respecting election expenses shall be modified as specified in the Second Schedule to this Act.

(4.) At the same time that the agent transmits the said return, or within seven days afterwards, the candidate shall transmit or cause to be transmitted to the returning officer a declaration made by him before a justice of the peace, in the form in the first part of the Second Schedule to this Act (which declaration is in this Act referred to as a declaration respecting election expenses).

(5.) If in the case of an election for any county or borough, the said return and declarations are not transmitted before the expiration of the time limited for the purpose, the candidate shall not, after the expiration of such time, sit or vote in the House of Commons as member for that county or borough until either such return and declarations have been transmitted, or until the date of the allowance of such an authorised excuse for the failure to transmit the same, as in this Act mentioned, and if he sits or votes in contravention of this enactment he shall forfeit one hundred pounds for every day on which he so sits or votes to any person who sues for the same.

(6.) If without such authorised excuse as in this Act mentioned, a candidate or an election agent fails to comply with the requirements of this section, he shall be guilty of an illegal practice.

(7.) If any candidate or election agent knowingly makes the declaration required by this section falsely, he shall be guilty of an offence, and on conviction thereof on indictment shall be liable to the punishment for wilful and corrupt perjury; such offence shall also be deemed to be a corrupt practice within the meaning of this Act.

(8.) When the candidate is out of the United Kingdom at the time when the return is so transmitted to the returning officer, the declaration required by this section may be made by him within fourteen days after his return to the United Kingdom, and in that case shall be forthwith transmitted to the returning officer, but the delay hereby authorised in making such declaration shall not exonerate the election agent from complying with the provisions of this Act as to the return and declaration respecting election expenses.

(9.) Where, after the date at which the return respecting election expenses is transmitted, leave is given by the High Court for any claims to be paid, the candidate or his election agent shall, within seven days after the payment thereof, transmit to the returning officer a return of the sums paid in pursuance of such leave accompanied by a copy of the order of the court giving the leave, and in default he shall be deemed to have failed to comply with the requirements of this section without such authorised excuse as in this Act mentioned.

34. (1.) Where the return and declarations respecting election expenses of a candidate at an election for a county or borough have not been transmitted as required by this Act, or being transmitted contain some error or false statement, then—

(a.) if the candidate applies to the High Court or an election court, and shows that the failure to transmit such return and declarations, or any of them, or any part thereof, or any error or false statement therein, has arisen by reason of his illness, or of the absence, death, illness or misconduct of his election agent or sub-agent, or of any clerk or officer of such agent, or by reason of inadvertence or of any reasonable cause of a like nature, and not by reason of any want of good faith on the part of the applicant, or

(b.) if the election agent of the candidate applies to the High Court or an election court, and shows that the failure to transmit the return and declarations which he was required to transmit, or any part thereof, or any error or false statement therein, arose by reason of his illness or of the death or illness of any prior election agent of the candidate, or of the absence, death, illness, or misconduct of any sub-agent, clerk, or officer of an election agent of the candidate, or by reason of inadvertence or of any reasonable cause of a like nature, and not by reason of any want of good faith on the part of the applicant,

the court may, after such notice of the application in the said county or borough, and on production of such evidence of the grounds stated in the application, and of the good faith of the application, and otherwise, as to the court seems fit, make such order for allowing an authorised excuse for the failure to transmit such return and declaration, or for an error or false statement in such return and declaration as to the court seems just.

Authorise  
excuse for  
non-compliance  
with provisions  
as to return and  
declaration  
respecting  
election  
expenses



(2.) Where it appears to the court that any person being or having been election agent or sub-agent has refused or failed to make such return or to supply such particulars as will enable the candidate and his election agent respectively to comply with the provisions of this Act as to the return and declaration respecting election expenses, the court before making an order allowing the excuse as in this section mentioned shall order such person to attend before the court, and on his attendance shall, unless he shows cause to the contrary, order him to make the return and declaration, or to deliver a statement of the particulars required to be contained in the return, as to the court seem just, and to make or deliver the same within such time and to such person and in such manner as the court may direct, or may order him to be examined with respect to such particulars, and may in default of compliance with any such order order him to pay a fine not exceeding five hundred pounds.

(3.) The order may make the allowance conditional upon the making of the return and declaration in a modified form or within an extended time, and upon the compliance with such other terms as to the court seem best calculated for carrying into effect the objects of this Act; and an order allowing an authorised excuse shall relieve the applicant for the order from any liability or consequences under this Act in respect of the matter excused by the order; and where it is proved by the candidate to the court that any act or omission of the election agent in relation to the return and declaration respecting election expenses was without the sanction or connivance of the candidate, and that the candidate took all reasonable means for preventing such act or omission, the court shall relieve the candidate from the consequences of such act or omission on the part of his election agent.

(4.) The date of the order, or if conditions and terms are to be complied with, the date at which the applicant fully complies with them, is referred to in this Act as the date of the allowance of the excuse.

**35. (1.)** The returning officer at an election, within ten days after he receives from the election agent of a candidate a return respecting election expenses, shall publish a summary of the return in not less than two newspapers circulating in the county or borough for which the election was held, accompanied by a notice of the time and place at which the return and declarations (including the accompanying documents) can be inspected, and may charge the candidate in respect of such publication, and the amount of such charge shall be the sum allowed by the Parliamentary Elections (Returning Officers') Act, 1875.

Publication  
summary of  
return of  
election  
expenses.

(2.) The return and declarations (including the accompanying documents) sent to the returning officer by an election agent shall be kept at the office of the returning officer, or some convenient place appointed by him, and shall at all reasonable times during two years next after they are received by the returning officer be open to inspection by any person on payment of a fee of one shilling, and the returning officer shall on demand furnish copies thereof or any part thereof at the price of two-pence for every seventy-two words. After the expiration of the said two years the returning officer may cause the said return and declarations (including the accompanying documents) to be destroyed, or, if the candidate or his election agent so require, shall return the same to the candidate.

38 & 39 Vic  
c. 84.

### *Disqualification of Electors.*

**36.** Every person guilty of a corrupt or illegal practice or of illegal

Prohibition of  
persons guilty

of corrupt or illegal practices, &c., from voting.

Prohibition of disqualified persons from voting.

35 & 36 Viet.

c. 60.

45 & 46 Viet.

c. 50.

employment, payment, or hiring at an election is prohibited from voting at such election, and if any such person votes his vote shall be void.

**37.** Every person who, in consequence of conviction or of the report of any election court or election commissioners under this Act, or under the Corrupt Practices (Municipal Elections) Act, 1872, or under Part IV. of the Municipal Corporations Act, 1882, or under any other Act for the time being in force relating to corrupt practices at an election for any public office, has become incapable of voting at any election, whether a parliamentary election or an election to any public office, is prohibited from voting at any such election, and his vote shall be void.

Hearing of person before he is reported, guilty of corrupt or illegal practice, and incapacity of person reported guilty.

**38.** (1.) Before a person, not being a party to an election petition nor a candidate on behalf of whom the seat is claimed by an election petition, is reported by an election court, and before any person is reported by election commissioners, to have been guilty, at an election, of any corrupt or illegal practice, the court or commissioners, as the case may be, shall cause notice to be given to such person, and if he appears in pursuance of the notice, shall give him an opportunity of being heard by himself and of calling evidence in his defence to show why he should not be so reported.

(2.) Every person reported by election commissioners to have been guilty at an election of any corrupt or illegal practice may appeal against such report to the next court of oyer and terminer or gaol delivery held in and for the county or place in which the offence is alleged to have been committed, and such court may hear and determine the appeal; and subject to rules of court such appeal may be brought, heard, and determined in like manner as if the court were a court of quarter sessions and the said commissioners were a court of summary jurisdiction, and the person so reported had been convicted by a court of summary jurisdiction for an offence under this Act, and notice of every such appeal shall be given to the Director of Public Prosecutions in the manner and within the time directed by rules of court, and subject to such rules then within three days after the appeal is brought.

(3.) Where it appears to the Lord Chancellor that appeals under this section are interfering or are likely to interfere with the ordinary business transacted before any courts of oyer and terminer or gaol delivery, he may direct that the said appeals, or any of them, shall be heard by the judges for the time being on the rota for election petitions, and in such case one of such judges shall proceed to the county or place in which the offences are alleged to have been committed, and shall there hear and determine the appeals in like manner as if such judge were a court of oyer and terminer.

(4.) The provisions of the Parliamentary Elections Act, 1868, with respect to the reception and powers of and attendance on an election court, and to the expenses of an election court, and of receiving and accommodating an election court, shall apply as if such judge were an election court.

(5.) Every person who after the commencement of this Act is reported by any election court or election commissioners to have been guilty of any corrupt or illegal practice at an election, shall, whether he obtained a certificate of indemnity or not, be subject to the same incapacity as he would be subject to if he had at the date of such election been convicted of the offence of which he is reported

to have been guilty : Provided that a report of any election commissioners inquiring into an election for a county or borough shall not avoid the election of any candidate who has been declared by an election court on the trial of a petition respecting such election to have been duly elected at such election, or render him incapable of sitting in the House of Commons for the said county or borough during the Parliament for which he was elected.

(6.) Where a person who is a justice of the peace is reported by any election court or election commissioners to have been guilty of any corrupt practice in reference to an election, whether he has obtained a certificate of indemnity or not, it shall be the duty of the Director of Public Prosecutions to report the case to the Lord High Chancellor of Great Britain with such evidence as may have been given of such corrupt practice, and where any such person acts as a justice of the peace by virtue of his being, or having been, mayor of a borough, the Lord High Chancellor shall have the same power to remove such person from being a justice of the peace as if he was named in a commission of the peace.

(7.) Where a person who is a barrister or a solicitor, or who belongs to any profession the admission to which is regulated by law, is reported by any election court or election commissioners to have been guilty of any corrupt practice in reference to an election, whether such person has obtained a certificate of indemnity or not, it shall be the duty of the Director of Public Prosecutions to bring the matter before the Inn of Court, High Court, or tribunal having power to take cognisance of any misconduct of such person in his profession, and such Inn of Court, High Court, or tribunal may deal with such person in like manner as if such corrupt practice were misconduct by such person in his profession.

(8.) With respect to a person holding a licence or certificate under the Licensing Acts (in this section referred to as a licensed person) the following provisions shall have effect :

(a.) If it appears to the court by which any licensed person is convicted of the offence of bribery or treating that such offence was committed on his licensed premises, the court shall direct such conviction to be entered in the proper register of licenses.

(b.) If it appears to an election court or election commissioners that a licensed person has knowingly suffered any bribery or treating in reference to any election to take place upon his licensed premises, such court or commissioners (subject to the provisions of this Act as to a person having an opportunity of being heard by himself and producing evidence before being reported) shall report the same ; and whether such person obtained a certificate of indemnity or not it shall be the duty of the Director of Public Prosecutions to bring such report before the licensing justices from whom or on whose certificate the licensed person obtained his license, and such licensing justices shall cause such report to be entered in the proper register of licenses.

(c.) Where an entry is made in the register of licenses of any such conviction or report respecting any licensed person as above in this section mentioned, it shall be taken into consideration by the licensing justices in determining whether they will or will not grant to such person the renewal of his license or certificate, and may be a ground, if the justices think fit, for refusing such renewal.

(9.) Where the evidence showing any corrupt practice to have been

committed by a justice of the peace, barrister, solicitor, or other professional person, or any licensed person, was given before election commissioners, those commissioners shall report the case to the Director of Public Prosecutions, with such information as is necessary or proper for enabling him to act under this section.

(10.) This section shall apply to an election court under this Act or under Part IV. of the Municipal Corporations Act, 1882, and the expression election shall be construed accordingly.

List in register of voters of persons incapacitated for voting by corrupt or illegal practices. 45 & 46 Vict. c. 50.

39. (1.) The registration officer in every county and borough shall annually make out a list containing the names and description of all persons who, though otherwise qualified to vote at a parliamentary election for such county or borough respectively, are not capable of voting by reason of having, after the commencement of this Act, been found guilty of a corrupt or illegal practice on conviction or by the report of any election court or election commissioners, whether under this Act or under Part IV. of the Municipal Corporations Act, 1882, or under any other Act for the time being in force relating to a parliamentary election or an election to any public office; and such officer shall state in the list (in this Act referred to as the corrupt and illegal practices list), the offence of which each person has been found guilty.

(2.) For the purpose of making out such list he shall examine the report of any election court or election commissioners who have respectively tried an election petition or inquired into an election where the election (whether a parliamentary election or an election to any public office) was held in any of the following places; that is to say—

(a.) If he is the registration officer of a county, in that county, or in any borough in that county; and

(b.) if he is the registration officer of a borough, in the county in which such borough is situate, or in any borough in that county.

(3.) The registration officer shall send the list to the overseers of every parish within his county or borough, together with his precept, and the overseers shall publish the list together with the list of voters, and shall also in the case of every person in the corrupt and illegal practices list, omit his name from the list of persons entitled to vote, or, as circumstances require, add "objected" before his name in the list of claimants or copy of the register published by them in like manner as is required by law in any other cases of disqualification.

(4.) Any person named in the corrupt and illegal practices list may claim to have his name omitted therefrom, and any person entitled to object to any list of voters for the county or borough may object to the omission of the name of any person from such list. Such claims and objections shall be sent in within the same time and be dealt with in like manner, and any such objection shall be served on the person referred to therein in like manner, as nearly as circumstances admit, as other claims and objections under the enactments relating to the registration of Parliamentary electors.

(5.) The revising barrister shall determine such claims and objections, and shall revise such list in like manner, as nearly as circumstances admit, as in the case of other claims and objections, and of any list of voters.

(6.) Where it appears to the revising barrister that a person not named in the corrupt and illegal practices list is subject to have his name inserted in such list, he shall (whether an objection to the omission of such name from the list has or has not been made, but) after giving such person an opportunity of making a statement to show cause to the

contrary, insert his name in such list and expunge his name from any list of voters.

(7.) A revising barrister in acting under this section shall determine only whether a person is incapacitated by conviction or by the report of any election court or election commissioners, and shall not determine whether a person has or has not been guilty of any corrupt or illegal practice.

(8.) The corrupt and illegal practices list shall be appended to the register of electors, and shall be printed and published therewith wherever the same is printed or published.

*Proceedings on Election Petition.*

40. (1.) Where an election petition questions the return or the election upon an allegation of an illegal practice, then notwithstanding anything in the Parliamentary Elections Act, 1868, such petition, so far as respects such illegal practice, may be presented within the time following (that is to say) :

Time for presentation of election petitions alleging illegal practice, 31 & 32 Vict. c. 125.

(a.) At any time before the expiration of fourteen days after the day on which the returning officer receives the return and declarations respecting election expenses by the member to whose election the petition relates and his election agent.

(b.) If the election petition specifically alleges a payment of money, or some other act to have been made or done since the said day by the member or an agent of the member, or with the privity of the member or his election agent in pursuance or in furtherance of the illegal practice alleged in the petition, the petition may be presented at any time within twenty-eight days after the date of such payment or other act.

(2.) Any election petition presented within the time limited by the Parliamentary Elections Act, 1868, may for the purpose of questioning the return or the election upon an allegation of an illegal practice be amended with the leave of the High Court, within the time within which a petition questioning the return upon the allegation of that illegal practice can under this section be presented.

31 & 32 Vict. c. 125.

(3.) This section shall apply in the case of an offence relating to the return and declarations respecting election expenses in like manner as if it were an illegal practice, and also shall apply notwithstanding that the Act constituting the alleged illegal practice amounted to a corrupt practice.

(4.) For the purposes of this section—

(a.) Where the return and declarations are received on different days, the day on which the last of them is received, and

(b.) Where there is an authorised excuse for failing to make and transmit the return and declarations respecting election expenses, the date of the allowance of the excuse, or if there was a failure as regards two or more of them, and the excuse was allowed at different times, the date of the allowance of the last excuse,

shall be substituted for the day on which the return and declarations are received by the returning officer.

(5.) For the purpose of this section, time shall be reckoned in like manner as it is reckoned for the purposes of the Parliamentary Elections Act, 1868.

41. (1.) Before leave for the withdrawal of an election petition is

Withdrawal of election petition.

granted, there shall be produced affidavits by all the parties to the petition and their solicitors, and by the election agents of all of the said parties who were candidates at the election, but the High Court may on cause shown dispense with the affidavit of any particular person if it seems to the court on special grounds to be just so to do.

(2.) Each affidavit shall state that, to the best of the deponents' knowledge and belief, no agreement or terms of any kind whatsoever has or have been made, and no undertaking has been entered into, in relation to the withdrawal of the petition; but if any lawful agreement has been made with respect to the withdrawal of the petition, the affidavit shall set forth that agreement, and shall make the foregoing statement subject to what appears from the affidavit.

(3.) The affidavits of the applicant and his solicitor shall further state the ground on which the petition is sought to be withdrawn.

(4.) If any person makes any agreement or terms, or enters into any undertaking, in relation to the withdrawal of an election petition, and such agreement, terms, or undertaking is or are for the withdrawal of the election petition in consideration of any payment, or in consideration that the seat shall at any time be vacated, or in consideration of the withdrawal of any other election petition, or is or are (whether lawful or unlawful) not mentioned in the aforesaid affidavits, he shall be guilty of a misdemeanour, and shall be liable on conviction on indictment to imprisonment for a term not exceeding twelve months, and to a fine not exceeding two hundred pounds.

(5.) Copies of the said affidavits shall be delivered to the director of public prosecutions a reasonable time before the application for the withdrawal is heard, and the court may hear the director of public prosecutions or his assistant or other representative (appointed with the approval of the Attorney-General), in opposition to the allowance of the withdrawal of the petition, and shall have power to receive the evidence on oath of any person or persons whose evidence the director of public prosecutions or his assistant, or other representative, may consider material.

(6.) Where in the opinion of the court the proposed withdrawal of a petition was the result of any agreement, terms, or undertaking prohibited by this section, the court shall have the same power with respect to the security as under Section 35 of the Parliamentary Elections Act, 1868, where the withdrawal is induced by a corrupt consideration.

(7.) In every case of the withdrawal of an election petition the court shall report to the Speaker whether, in the opinion of such court, the withdrawal of such petition was the result of any agreement, terms, or undertaking, or was in consideration of any payment, or in consideration that the seat should at any time be vacated, or in consideration of the withdrawal of any other election petition, or for any other consideration, and, if so, shall state the circumstances attending the withdrawal.

(8.) Where more than one solicitor is concerned for the petitioner or respondent, whether as agent for another solicitor or otherwise, the affidavit shall be made by all such solicitors.

(9.) Where a person not a solicitor is lawfully acting as agent in the case of an election petition, that agent shall be deemed to be a solicitor for the purpose of making an affidavit in pursuance of this section.

42. The trial of every election petition so far as is practicable, consistently with the interests of justice in respect of such trial, shall be continued *de die in diem* on every lawful day until its conclusion, and

in case the rota of judges for the year shall expire before the conclusion of the trial, or of all the proceedings in relation or incidental to the petition, the authority of the said judges shall continue for the purpose of the said trial and proceedings.

43. (1.) On every trial of an election petition the director of public prosecutions shall by himself or by his assistant, or by such representative as hereinafter mentioned, attend at the trial, and it shall be the duty of such director to obey any directions given to him by the election court with respect to the summoning and examination of any witness to give evidence on such trial, and with respect to the prosecution by him of offenders, and with respect to any person to whom notice is given to attend with a view to report him as guilty of any corrupt or illegal practice.

Attendance of director of public prosecutions on trial of election petition and prosecution by him of offenders.

(2.) It shall also be the duty of such director, without any direction from the election court, if it appears to him that any person is able to give material evidence as to the subject of the trial, to cause such person to attend the trial, and with the leave of the court to examine such person as a witness.

(3.) It shall also be the duty of the said director, without any direction from the election court, if it appears to him that any person who has not received a certificate of indemnity has been guilty of a corrupt or illegal practice, to prosecute such person for the offence before the said court, or if he thinks it expedient in the interests of justice before any other competent court.

(4.) Where a person is prosecuted before an election court for any corrupt or illegal practice, and such person appears before the court, the court shall proceed to try him summarily for the said offence, and such person, if convicted thereof upon such trial, shall be subject to the same incapacities as he is rendered subject to under this Act upon conviction, whether on indictment or in any other proceeding for the said offence; and further, may be adjudged by the court, if the offence is a corrupt practice, to be imprisoned, with or without hard labour, for a term not exceeding six months or to pay a fine not exceeding two hundred pounds, and if the offence is an illegal practice to pay such fine as is fixed by this Act for the offence;

Provided that, in the case of a corrupt practice, the court, before proceeding to try summarily any person, shall give such person the option of being tried by a jury.

(5.) Where a person is so prosecuted for any such offence, and either he elects to be tried by a jury or he does not appear before the court, or the court thinks it in the interests of justice expedient that he should be tried before some other court, the court, if of opinion that the evidence is sufficient to put the said person upon his trial for the offence, shall order such person to be prosecuted on indictment or before a court of summary jurisdiction, as the case may require, for the said offence; and in either case may order him to be prosecuted before such court as may be named in the order; and for all purposes preliminary and of and incidental to such prosecution the offence shall be deemed to have been committed within the jurisdiction of the court so named.

(6.) Upon such order being made,

(a.) if the accused person is present before the court, and the offence is an indictable offence, the court shall commit him to take his trial, or cause him to give bail to appear and take his trial for the said offence; and

- (b.) if the accused person is present before the court, and the offence is not an indictable offence, the court shall order him to be brought before the court of summary jurisdiction before whom he is to be prosecuted, or cause him to give bail to appear before that court ; and
- (c.) if the accused person is not present before the court, the court shall as circumstances require issue a summons for his attendance, or a warrant to apprehend him and bring him before a court of summary jurisdiction, and that court, if the offence is an indictable offence, shall, on proof only of the summons or warrant and the identity of the accused, commit him to take his trial, or cause him to give bail to appear and take his trial for the said offence, or, if the offence is punishable on summary conviction, shall proceed to hear the case, or if such court be not the court before whom he is directed to be prosecuted, shall order him to be brought before that court.

(7.) The director of public prosecutions may nominate, with the approval of the Attorney-General, a barrister or solicitor of not less than ten years standing, to be his representative for the purpose of this section, and that representative shall receive such remuneration as the Commissioners of Her Majesty's Treasury may approve. There shall be allowed to the director and his assistant or representative, for the purposes of this section, such allowance for expenses as the Commissioners of Her Majesty's Treasury may approve.

(8.) The costs incurred in defraying the expenses of the director of public prosecutions under this section (including the remuneration of his representative) shall, in the first instance, be paid by the Commissioners of Her Majesty's Treasury, and so far as they are not in the case of any prosecution paid by the defendant shall be deemed to be expenses of the election court ; but if for any reasonable cause it seems just to the court so to do, the court shall order all or part of the said costs to be repaid to the Commissioners of Her Majesty's Treasury by the parties to the petition, or such of them as the court may direct.

Power to election court to order payment by county or borough or individual of costs of election petition.

44. (1.) Where upon the trial of an election petition respecting an election for a county or borough it appears to the election court that a corrupt practice has not been proved to have been committed in reference to such election by or with the knowledge and consent of the respondent to the petition, and that such respondent took all reasonable means to prevent corrupt practices being committed on his behalf, the court may make one or more orders with respect to the payment either of the whole or such part of the costs of the petition as the court may think right as follows :—

- (a.) if it appears to the court that corrupt practices extensively prevailed in reference to the said election, the court may order the whole or part of the costs to be paid by the county or borough ; and
- (b.) if it appears to the court that any person or persons is or are proved, whether by providing money or otherwise, to have been extensively engaged in corrupt practices, or to have encouraged or promoted extensive corrupt practices in reference to such election, the court may, after giving such person or persons an opportunity of being heard by counsel or solicitor and examining and cross-examining witnesses to show cause why the order should not be made, order the whole or part of



the costs to be paid by that person, or those persons or any of them, and may order that if the costs cannot be recovered from one or more of such persons they shall be paid by some other of such persons or by either of the parties to the petition.

(2.) Where any person appears to the court to have been guilty of the offence of a corrupt or illegal practice, the court may, after giving such person an opportunity of making a statement to show why the order should not be made, order the whole or any part of the costs of or incidental to any proceeding before the court in relation to the said offence or to the said person to be paid by the said person.

(3.) The rules and regulations of the Supreme Court of Judicature with respect to costs to be allowed in actions, causes, and matters in the High Court shall in principle and so far as practicable apply to the costs of petition and other proceedings under the Parliamentary Elections Act, 1868, and under this Act, and the taxing officer shall not allow any costs, charges or expenses on a higher scale than would be allowed in any action, cause, or matter in the High Court on the higher scale, as between solicitor and client.

### *Miscellaneous.*

45. Where information is given to the Director of Public Prosecutions that any corrupt or illegal practices have prevailed in reference to any election, it shall be his duty, subject to the regulations under the Prosecution of Offences Act, 1879, to make such inquiries and institute such prosecutions as the circumstances of the case appear to him to require.

Inquiry by director of public prosecutions into alleged corrupt or illegal practices.

46. Where a person has, either before or after the commencement of this Act, become subject to any incapacity under the Corrupt Practices Prevention Acts or this Act by reason of a conviction or of a report of any election court or election commissioners, and any witness who gave evidence against such incapacitated person upon the proceeding for such conviction or report is convicted of perjury in respect of that evidence, the incapacitated person may apply to the High Court, and the court, if satisfied that the conviction or report so far as respects such person was based upon perjury, may order that such incapacity shall thenceforth cease, and the same shall cease accordingly.

Removal of incapacity on proof that it was procured by perjury.

47. (1.) Every county shall be divided into polling districts, and a polling place shall be assigned to each district in such manner that, so far as is reasonably practicable, every elector resident in the county shall have his polling place within a distance not exceeding three miles from his residence, so nevertheless that a polling district need not in any case be constituted containing less than one hundred electors.

Amendment of law as to polling districts and polling places.

(2.) In every county the local authority who have power to divide that county into polling districts shall from time to time divide the county into polling districts, and assign polling places to those districts, and alter those districts and polling places in such manner as may be necessary for the purpose of carrying into effect this section.

(3.) The power of dividing a borough into polling districts vested in a local authority by the Representation of the People Act, 1867, and the enactments amending the same, may be exercised by such

local authority from time to time, and as often as the authority think fit, and the said power shall be deemed to include the power of altering any polling district, and the said local authority shall from time to time, where necessary for the purpose of carrying this section into effect, divide the borough into polling districts in such manner that :—

(a.) Every elector resident in the borough, if other than one herein after mentioned, shall be enabled to poll within a distance not exceeding one mile from his residence, so nevertheless that a polling district need not be constituted containing less than three hundred electors ; and

(b.) Every elector resident in the boroughs of East Retford, Shoreham, Cricklade, Much Wenlock, and Aylesbury, shall be enabled to poll within a distance not exceeding three miles from his residence, so nevertheless that a polling district need not be constituted containing less than one hundred electors.

(4.) So much of Section 5 of the Ballot Act, 1872, and the enactments amending the same as in force and is not repealed by this Act, shall apply as if the same were incorporated in this section.

(5.) The expenses incurred by the local authority of a county or borough under this or any other Act in dividing their county or borough into polling districts, and, in the case of a county, assigning polling places to such districts, and in altering any such districts or polling places, shall be defrayed in like manner as if they were expenses incurred by the registration officer in the execution of the enactments respecting the registration of electors in such county or borough, and those enactments, so far as is consistent with the tenor thereof, shall apply accordingly.

Conveyance of voters by sea in certain cases.

48. Where the nature of a county is such that any electors residing therein are unable at an election for such county to reach their polling place without crossing the sea or a branch or arm thereof, this Act shall not prevent the provision of means for conveying such electors by sea to their polling place, and the amount of payment for such means of conveyance may be in addition to the maximum amount of expenses allowed by this Act.

Election commissioners not to inquire into elections before the passing of this Act.

49. Notwithstanding the provisions of the Act 15 and 16 Vict. cap. 57, or any amendment thereof, in any case where, after the passing of this Act, any commissioners have been appointed, on a joint address of both Houses of Parliament, for the purpose of making inquiry into the existence of corrupt practices in any election, the said commissioners shall not make inquiries concerning any election that shall have taken place prior to the passing of this Act, and no witness called before such commissioners, or at any election petition after the passing of this Act, shall be liable to be asked or bound to answer any question for the purpose of proving the commission of any corrupt practice at or in relation to any election prior to the passing of this Act : Provided that nothing herein contained shall affect any proceedings that shall be pending at the time of such passing.

#### *Legal Proceedings.*

Trial in Central Criminal Court of indictment

50. Where an indictment as defined by this Act for any offence under the Corrupt Practices Prevention Acts or this Act is instituted in

the High Court, or is removed into the High Court by a writ of certiorari issued at the instance of the Attorney-General, and the Attorney-General suggests on the part of the Crown that it is expedient for the purposes of justice that the indictment should be tried in the Central Criminal Court, or if a special jury is ordered, that it should be tried before a judge and jury at the Royal Courts of Justice, the High Court may, if it think fit, order that such indictment shall be so tried upon such terms as the court may think just, and the High Court may make such orders as appear to the court necessary or proper for carrying into effect the order for such trial.

for corrupt practice at instance of Attorney-General.

**51. (1.)** A proceeding against a person in respect of the offence of a corrupt or illegal practice, or any other offence under the Corrupt Practices Prevention Act, or this Act, shall be commenced within one year after the offence was committed, or if it was committed in reference to an election with respect to which an inquiry is held by election commissioners shall be commenced within one year after the offence was committed, or within three months after the report of such commissioners is made, whichever period last expires, so that it be commenced within two years after the offence was committed, and the time so limited by this section shall, in the case of any proceeding under the Summary Jurisdiction Acts for any such offence, whether before an election court or otherwise, be substituted for any limitation of time contained in the last-mentioned Acts.

Limitation of time for prosecution of offence.

**(2.)** For the purposes of this section the issue of a summons, warrant, writ, or other process shall be deemed to be a commencement of a proceeding, where the service or execution of the same on or against the alleged offender is prevented by the absconding or concealment or act of the alleged offender, but save as aforesaid the service or execution of the same on or against the alleged offender, and not the offence thereof, shall be deemed to be the commencement of the proceeding.

**52.** Any person charged with a corrupt practice may, if the circumstances warrant such finding, be found guilty of an illegal practice (which offence shall for that purpose be an indictable offence), and any person charged with an illegal practice may be found guilty of that offence, notwithstanding that the act constituting the offence amounted to a corrupt practice, and a person charged with illegal payment, employment, or hiring, may be found guilty of that offence, notwithstanding that the Act constituting the offence amounted to a corrupt or illegal practice.

Persons charged with corrupt practice may be found guilty of illegal practice.

**53. (1.)** Sections 10, 12, and 13 of the Corrupt Practices Prevention Act, 1854, and Section 6 of the Corrupt Practices Prevention Act, 1863 (which relate to prosecutions for bribery and other offences under those Acts), shall extend to any prosecution on indictment for the offence of any corrupt practice within the meaning of this Act, and to any action for any pecuniary forfeiture for an offence under this Act, in like manner as if such offence were bribery within the meaning of those Acts, and such indictment or action were the indictment or action in those sections mentioned, and an order under the said Section 10 may be made on the defendant; but the Director of Public Prosecutions, or any person instituting any prosecution in his behalf, or by direction of an

Application of enactments of 17 & 18 Vict. c. 102, and 26 & 27 Vict. c. 29, relating to prosecutions for bribery. 17 & 18 Vict. c. 102, 26 & 27 Vict. c. 29.

election court, shall not be deemed to be a private prosecutor, nor required under the said sections to give any security.

(2.) On any prosecution under this Act, whether on indictment or summarily, and whether before an election court or otherwise, and in any action for a pecuniary forfeiture under this Act, the person prosecuted or sued, and the husband or wife of such person, may, if he or she think fit, be examined as an ordinary witness in the case.

(3.) On any such prosecution or action as aforesaid it shall be sufficient to allege that the person charged was guilty of an illegal practice, payment, employment, or hiring within the meaning of this Act, as the case may be, and the certificate of the returning officer at an election that the election mentioned in the certificate was duly held, and that the person named in the certificate was a candidate at such election, shall be sufficient evidence of the facts therein stated.

Prosecution on summary conviction, and appeal to quarter sessions.

**54. (1.)** All offences under this Act punishable on summary conviction may be prosecuted in manner provided by the Summary Jurisdiction Acts.

(2.) A person aggrieved by a conviction by a Court of Summary Jurisdiction for an offence under this Act may appeal to general or quarter sessions against such conviction.

Application of Summary Jurisdiction and Indictable Offences Acts to proceedings before election courts.

**55. (1.)** Except that nothing in this Act shall authorise any appeal against a summary conviction by an election court, the Summary Jurisdiction Act shall, so far as is consistent with the tenor thereof, apply to the prosecution of an offence summarily before an election court, in like manner as if it were an offence punishable only on summary conviction, and accordingly the attendance of any person may be enforced, the case heard and determined, and any summary conviction by such court be carried into effect and enforced, and the costs thereof paid, and the record thereof dealt with under those Acts in like manner as if the court were a Petty Sessional Court for the county or place in which such conviction took place.

(2.) The enactments relating to charges before justices against persons for indictable offences shall, so far as is consistent with the tenor thereof, apply to every case where an election court orders a person to be prosecuted on indictment in like manner as if the court were a justice of the peace.

Exercise of jurisdiction of High Court, and making of rules of court.

**56. (1.)** Subject to any rules of court, any jurisdiction vested by this Act in the High Court may, so far as it relates to indictments or other criminal proceedings, be exercised by any judge of the Queen's Bench Division, and in other respects may either be exercised by one of the judges for the time being on the rota for the trial of election petitions, sitting either in court or at chambers, or may be exercised by a master of the Supreme Court of Judicature in manner directed by and subject to an appeal to the said judges :

Provided that a master shall not exercise jurisdiction in the case either of an order declaring any act or omission to be an exception from the provisions of this Act with respect to illegal practices, payments, employments, or hirings, or of an order allowing an excuse in relation to a return or declaration respecting election expenses.

(2.) Rules of court may from time to time be made, revoked, and altered for the purposes of this Act, and of the Parliamentary Elections

Act, 1868, and the Acts amending the same, by the same authority by whom rules of court for procedure and practice in the Supreme Court of Judicature can for the time being be made.

57. (1.) The Director of Public Prosecutions, in performing any duty under this Act, shall act in accordance with the regulations under the Prosecution of Offences Act, 1879, and subject thereto in accordance with the directions (if any) given to him by the Attorney-General; and any assistant or representative of the Director of Public Prosecutions, in performing any duty under this Act, shall act in accordance with the said regulations and directions, if any, and with the directions given to him by the Director of Public Prosecutions.

Director of public prosecutions and expenses of prosecutions, 12 & 43 Vict. c. 22.

(2.) Subject to the provisions of this Act, the costs of any prosecution on indictment for an offence punishable under this Act, whether by the Director of Public Prosecutions or his representative, or by any other person, shall, so far as they are not paid by the defendant, be paid in like manner as costs in the case of a prosecution for felony are paid.

58. (1.) Where any costs or other sums (not being costs of a prosecution on indictment) are, under an order of an election court, or otherwise under this Act, to be paid by a county or borough, the Commissioners of Her Majesty's Treasury shall pay those costs or sums, and obtain repayment of the amount so paid, in like manner as if such costs and sums were expenses of Election Commissioners paid by them, and the Election Commissioners' Expenses Acts, 1869 and 1871, shall apply accordingly as if they were herein re-enacted and in terms made applicable to the above-mentioned costs and sums.

Recovery of costs payable by county or borough or by person.

32 & 33 Vict. c. 21.  
34 & 35 Vict. c. 61.

(2.) Where any costs or other sums are, under the order of an election court or otherwise under this Act, to be paid by any person, those costs shall be a simple contract debt due from such person to the person or persons to whom they are to be paid, and if payable to the Commissioners of Her Majesty's Treasury shall be a debt to Her Majesty, and in either case may be recovered accordingly.

### *Supplemental Provisions, Definitions, Savings, and Repeals.*

59. (1.) A person who is called as a witness respecting an election before any election court shall not be excused from answering any question relating to any offence at or connected with such election, on the ground that the answer thereto may criminate or tend to criminate himself or on the ground of privilege;

Obligation of witness to answer, and certificate of indemnity.

Provided that—

(a.) a witness who answers truly all questions which he is required by the election court to answer shall be entitled to receive a certificate of indemnity under the hand of a member of the court stating that such witness has so answered; and

(b.) an answer by a person to a question put by or before any election court shall not, except in the case of any criminal proceeding for perjury in receipt of such evidence, be in any proceeding, civil or criminal, admissible in evidence against him;

(2.) Where a person has received such a certificate of indemnity in relation to an election, and any legal proceeding is at any time instituted

against him for any offence under the Corrupt Practices Prevention Acts or this Act committed by him previously to the date of the certificate at or in relation to the said election, the court having cognisance of the case shall on proof of the certificate stay the proceeding, and may in their discretion award to the said person such costs as he may have been put to in the proceeding.

(3.) Nothing in this section shall be taken to relieve a person receiving a certificate of indemnity from any incapacity under this Act or from any proceeding to enforce such incapacity (other than a criminal prosecution).

(4.) This section shall apply in the case of a witness before any election commissioners, in like manner as if the expression "election court" in this section included election commissioners.

(5.) Where a solicitor or person lawfully acting as agent for any party to an election petition respecting any election for a county or borough has not taken any part or been concerned in such election, the election commissioners inquiring into such election shall not be entitled to examine such solicitor or agent respecting matters which came to his knowledge by reason only of his being concerned as solicitor or agent for a party to such petition.

Submission of report of election court or commissioners to Attorney-General.

60. An election court or election commissioners, when reporting that certain persons have been guilty of any corrupt or illegal practice, shall report whether those persons have or not been furnished with certificates of indemnity; and such report shall be laid before the Attorney-General (accompanied in the case of the commissioners with the evidence on which such report is based), with a view to his instituting or directing a prosecution against such persons as have not received certificates of indemnity, if the evidence should, in his opinion, be sufficient to support a prosecution.

Breach of duty by officer.  
35 & 36 Vict.  
c. 33.

61. (1.) Section 11 of the Ballot Act, 1872, shall apply to a returning officer or presiding officer or clerk who is guilty of any wilful misfeasance or wilful act or omission in contravention of this Act in like manner as if the same were in contravention of the Ballot Act, 1872.

6 Vict. c. 18.

(2.) Section 97 of the Parliamentary Registration Act, 1843, shall apply to every registration officer who is guilty of any wilful misfeasance or wilful act of commission or omission contrary to this Act in like manner as if the same were contrary to the Parliamentary Registration Act, 1843.

Public notice and service of notices.  
35 & 36 Vict.  
c. 33.

62. (1.) Any public notice required to be given by the returning officer under this Act shall be given in the manner in which he is directed by the Ballot Act, 1872, to give a public notice.

(2.) Where any summons, notice, or document is required to be served on any person with reference to any proceeding respecting an election for a county or borough, whether for the purpose of causing him to appear before the High Court or any election court, or election commissioners, or otherwise, or for the purpose of giving him an opportunity of making a statement, or showing cause, or being heard by himself, before any court or commissioners, for any purpose of this Act, such summons, notice, or document may be served either by delivering the same to such person, or by leaving the same at, or sending the same by post by a registered letter to, his last known place of abode in the said

county or borough, or if the proceeding is before any court or commissioners, in such other manner as the court or commissioners may direct, and in proving such service by post it shall be sufficient to prove that the letter was prepaid, properly addressed, and registered with the post-office.

(3.) In the form of notice of a Parliamentary election set forth in the second schedule to the Ballot Act, 1872, the words "or any illegal practice," shall be inserted after the words "or other corrupt practices," and the words the "Corrupt and Illegal Practices Prevention Act, 1883," shall be inserted after the words "Corrupt Practices Prevention Act, 1854."

63. (1.) In the Corrupt Practices Prevention Acts, as amended by this Act, the expression "candidate at an election," and the expression "candidate," respectively mean, unless the context otherwise requires, any person elected to serve in Parliament at such election, and any person who is nominated as a candidate at such election, or is declared by himself or by others to be a candidate, on or after the day of the issue of the writ for such election, or after the dissolution or vacancy in consequence of which such writ has been issued ;

Definition of candidate, and saving for persons nominated without consent.

(2.) Provided that where a person has been nominated as a candidate or declared to be a candidate by others, then—

(a.) If he was so nominated or declared without his consent, nothing in this Act shall be construed to impose any liability on such person, unless he has afterwards given his assent to such nomination or declaration, or has been elected ; and

(b.) If he was so nominated or declared, either without his consent or in his absence, and he takes no part in the election, he may, if he thinks fit, make the declaration respecting election expenses contained in the second part in the second schedule to this Act, and the election agent shall, so far as circumstances admit, comply with the provisions of this Act with respect to expenses incurred on account of or in respect of the conduct or management of the election in like manner as if the candidate had been nominated or declared with his consent.

64. In this Act, unless the context otherwise requires—

The expression "election" means the election of a member or members to serve in Parliament :

The expression "election petition" means a petition presented in pursuance of the Parliamentary Elections Act, 1868, as amended by this Act :

The expression "election court" means the judges presiding at the trial of an election petition, or, if the matter comes before the High Court, that court :

The expression "election commissioners" means commissioners appointed in pursuance of the Election Commissioners Act, 1852, and the enactments amending the same :

The expression "High Court" means Her Majesty's High Court of Justice in England :

The expressions "court of summary jurisdiction," "petty sessional court," and "Summary Jurisdiction Acts," have the same meaning as in the Summary Jurisdiction Act, 1879 :

The expression "the Attorney-General" includes the Solicitor-General in cases where the office of the Attorney-General

General interpretation of terms.

31 & 32 Vict.  
c. 125.

15 & 16 Vict.  
c. 37.

42 & 43 Vict.  
c. 49.

is vacant or the Attorney-General is interested or otherwise unable to act :

The expression "registration officer" means the clerk of the peace in a county, and the town clerk in a borough, as respectively defined by the enactments relating to the registration of parliamentary electors :

The expression "elector" means any person whose name is for the time being on the register roll or book containing the names of the persons entitled to vote at the election with reference to which the expression is used :

The expression "register of electors" means the said register roll or book :

The expression "polling agent" means an agent of the candidate appointed to attend at a polling station in pursuance of the Ballot Act, 1872, or of the Acts therein referred to or amending the same :

The expression "person" includes an association or body of persons, corporate or unincorporate, and where any act is done by any such association or body, the members of such association or body who have taken part in the commission of such act shall be liable to any fine or punishment imposed for the same by this Act :

The expression "committee room" shall not include any house or room occupied by a candidate at an election as a dwelling, by reason only of the candidate there transacting business with his agents in relation to such election ; nor shall any room or building be deemed to be a committee room for the purposes of this Act by reason only of the candidate or any agent of the candidate addressing therein electors, committee men or others :

The expression "public office" means any office under the Crown or under the charter of a city or municipal borough, or under the Acts relating to municipal corporations or to the poor law, or under the Elementary Act, 1870, or under the Public Health Act, 1875, or under any Acts amending the above-mentioned Acts, or under any other Acts for the time being in force (whether passed before or after the commencement of this Act) relating to local government, whether the office is that of mayor, chairman, alderman, councillor, guardian, member of a board, commission, or other local authority in any county, city, borough, union, sanitary district, or other area, or is the office of clerk of the peace, town clerk, clerk or other officer under a council, board, commission, or other authority, or is any other office, to which a person is elected or appointed under any such charter or Act as above-mentioned, and includes any other municipal or parochial office ; and the expressions "election," "election petition," "election court," and "register of electors," shall, where expressed to refer to an election for any such public office, be construed accordingly :

The expression "judicial office" includes the office of justice of the peace and revising barrister :

The expression "personal expenses," as used with respect to the expenditure of any candidate in relation to any election, includes the reasonable travelling expenses of such candidate, and the reasonable expenses of his living at hotels or elsewhere for the purposes of and in relation to such election :

33 & 36 Vict.  
c. 33.

33 & 34 Vict.  
c. 75.  
38 & 39 Vict.  
c. 55.



The expression "indictment" includes information :

The expression "costs" includes costs, charges and expenses :

The expression "payment" includes any pecuniary or other reward ; and the expressions "pecuniary reward" and "money" shall be deemed to include any office, place, or employment, and any valuable security or other equivalent for money, and any valuable consideration, and expressions referring to money shall be construed accordingly :

The expression "Licensing Acts" means the Licensing Acts, 1872 to 1874 :

Other expressions have the same meaning as in the Corrupt Practices Prevention Acts.

**65.** (1.) The enactments described in the Third Schedule to this Act are in this Act referred to as the Corrupt Practices Prevention Acts. Short titles.

(2.) The Acts mentioned in the Fourth Schedule to this Act are in this Act referred to and may be cited respectively by the short titles in that behalf in that schedule mentioned.

(3.) This Act may be cited as the Corrupt and Illegal Practices Prevention Act, 1883.

(4.) This Act and the Corrupt Practices Prevention Acts may be cited together as the Corrupt Practices Prevention Acts, 1854 to 1883.

**66.** The Acts set forth in the Fifth Schedule to this Act are hereby repealed as from the commencement of this Act to the extent in the third column of that schedule mentioned, provided that this repeal or the expiration of any enactment not continued by this Act shall not revive any enactment which at the commencement of this Act is repealed, and shall not affect anything duly done or suffered before the commencement of this Act, or any right acquired or accrued, or any incapacity incurred before the commencement of this Act, and any person subject to any incapacity under any enactment hereby repealed or not continued shall continue subject thereto, and this Act shall apply to him as if he had become so subject in pursuance of the provisions of this Act. Repeal of Acts.

**67.** This Act shall come into operation on the fifteenth day of October, One thousand eight hundred and eighty-three, which day is in this Act referred to as the commencement of this Act. Commencement of Act.

#### *Application of Act to Scotland.*

**68.** This Act shall apply to Scotland, with the following modifications : Application of Act to Scotland.

(1.) The following expressions shall mean as follows :

The expression "misdemeanour" shall mean crime and offence :

The expression "indictment" shall mean criminal letters :

The expression "solicitor" shall mean enrolled law agent :

The expression "revising barrister" shall mean sheriff :

The expression "barrister" shall mean advocate :

The expression "petty sessional court" shall mean sheriff court :

The expression "quarter sessions" shall mean the Court of Justiciary :

The expression "registration officer" shall mean an assessor under the enactments relating to the registration of Parliamentary voters :

The expression "municipal borough" shall include royal burgh and burgh of regality and burgh of barony :

The expression "Acts relating to municipal corporations" shall include the General Police and Improvement (Scotland) Act, 1862, and any other Act relating to the constitution and government of burghs in Scotland :

The expression "mayor" shall mean provost or chief magistrate

The expression "alderman" shall mean bailie :

The expression "Summary Jurisdiction Acts" shall mean the Summary Jurisdiction (Scotland) Acts 1864 and 1881 and any Acts amending the same.

(2.) The provisions of this Act with respect to polling districts and the expenses of dividing a county or borough into polling districts shall not apply to Scotland.

(3.) The provisions respecting the attendance at the trial of an election petition of a representative of the Director of Public Prosecutions shall not apply to Scotland, and in place thereof the following provisions shall have effect :

(a.) At the trial of every election petition in Scotland Her Majesty's advocate shall be represented by one of his deputies or by the procurator-fiscal of the sheriff court of the district, who shall attend such trial as part of his official duty, and shall give all necessary assistance to the judge with respect to the citation of witnesses and recovery of documents :

(b.) If the judge shall grant a warrant for the apprehension, commitment, or citation of any person suspected of being guilty of a corrupt or illegal practice, the case shall be reported to Her Majesty's advocate in order that such person may be brought to trial before the High Court of Justiciary or the sheriff, according to the nature of the case :

(c.) It shall be the duty of the advocate depute or, in his absence, the procurator-fiscal, if it appears to him that a corrupt or illegal practice within the meaning of this Act has been committed by any person who has not received a certificate of indemnity, to report the case to Her Majesty's Advocate in order to such person being brought to trial before the proper court, although no warrant may have been issued by the judge.

(4.) The jurisdiction of the High Court of Justice under this Act shall, in Scotland, be exercised by one of the Divisions of the Court of Session, or by a judge of the said court to whom the same may be remitted by such division, and subject to an appeal thereto, and the Court of Session shall have power to make Acts of sederunt for the purposes of this Act.

(5.) Court of Oyer and Terminer shall mean a circuit court of Justiciary, and the High Court of Justiciary shall have powers to make Acts of adjournal regulating the procedure in appeals to the circuit court under this Act.

(6.) All offences under this Act punishable on summary conviction may be prosecuted in the sheriff court in manner provided by the Summary Jurisdiction Acts, and all necessary jurisdictions are hereby conferred on sheriffs.

(7.) The authority given by this Act to the Director of public pro-

secutions in England shall in Scotland be exercised by Her Majesty's advocate, and the reference to the Prosecution of Offences Act, 1879, shall not apply.

(8.) The expression "Licensing Acts" shall mean "the Public Houses Acts Amendment (Scotland) Act, 1862," and "The Publicans' Certificates (Scotland) Act, 1876," and the Acts thereby amended and therein recited. 25 & 26 Vict.  
c. 35.  
39 & 40 Vict.  
c. 26.

(9.) The expression "Register of Licenses" shall mean the register kept in pursuance of Section 12 of the Act of the ninth year of the reign of King George the Fourth, chapter 58.

(10.) The references to the Public Health Act, 1875, and to the Elementary Education Act, 1870, shall be construed to refer to the Public Health (Scotland) Act, 1867, and to the Elementary Education (Scotland) Act, 1872.

(11.) Any reference to the Parliamentary Elections Returning Officers Act, 1875, shall not apply.

(12.) The provision with respect to the registration officer sending the corrupt and illegal practices list to overseers and the dealing with such list by overseers shall not apply, and in lieu thereof it is hereby enacted that the assessor shall in counties include the names of such persons in the list of persons who have become disqualified, and in boroughs shall omit the names of such persons from the list of persons entitled to vote.

(13.) The power given by this Act to the Lord Chancellor in England shall in Scotland, except so far as relates to the justices of the peace, be exercised by the Lord Justice General.

(14.) Any reference to the Attorney-General shall refer to the Lord Advocate.

(15.) The provisions with respect to the removal of cases to the Central Criminal Court or to the trial of cases at the Royal Courts of Justice shall not apply.

(16.) Section 38 of the Comty Voters Registration (Scotland) Act, 1861, shall be substituted for Section 97 of the Parliamentary Registration Act, 1843, where reference is made to that section in this Act. 24 & 25 Vict.  
c. 83.

(17.) The provision of this Act with regard to costs shall not apply to Scotland, and instead thereof the following provision shall have effect :

The costs of petitions and other proceedings under "The Parliamentary Elections Act, 1868," and under this Act, shall, subject to any regulations which the Court of Session may make by Act of sederunt, be taxed as nearly as possible according to the same principles as costs between agent and client are taxed in a cause in that court, and the auditor shall not allow any costs, charges, or expenses, on a higher scale.

### *Application of Act to Ireland.*

69. This Act shall apply to Ireland, with the following modifications : Application of  
Act to Ireland.

(1.) No person shall be tried for any offence against this Act under any of the provisions of "the Prevention of Crime (Ireland) Act, 1882." 45 & 46 Vict.  
c. 25.

(2.) The expression "Summary Jurisdiction Acts" means, with reference to the Dublin Metropolitan Police District, the Acts regulating the powers and duties of justices to the peace and

of the police in such district : and with reference to other parts of Ireland means the Petty Sessions (Ireland) Act, 1851, and any Acts amending the said Act.

- (3.) Section one hundred and three of the Act of the Session of the thirteenth and fourteenth years of the reign of Her present Majesty, chapter sixty-nine, shall be substituted for section ninety-seven of the Parliamentary Registration Act, 1843, where reference is made to that section in this Act.
- (4.) The provision with respect to the registration officer sending the corrupt and illegal practices list to overseers and the dealing with such list by overseers shall not apply, and in lieu thereof it is hereby enacted that the registration officer shall, after making out such list, himself publish the same in the manner in which he publishes the lists referred to in the twenty-first and the thirty-third sections of the Act of the Session of the thirteenth and fourteenth years of the reign of Her present Majesty, chapter sixty-nine ; and shall also in the case of every person in the corrupt and illegal practices list enter " objected to " against his name in the register and lists made out by such registration officer in like manner as he is by law required to do in other cases of disqualification.
- (5.) The Supreme Court of Judicature in Ireland shall be substituted for the Supreme Court of Judicature.
- (6.) The High Court of Justice in Ireland shall be substituted for the High Court of Justice in England.
- (7.) The Lord High Chancellor of Ireland shall be substituted for the Lord High Chancellor of Great Britain.
- (8.) The Attorney-General for Ireland shall be substituted for the Director of Public Prosecutions, and the reference to the prosecution of the Offences Act, 1879, shall not apply.
- (9.) The provisions of this Act relative to polling districts shall not apply to Ireland, but in the county of the town of Galway there shall be a polling station at Barna, and at such other places within the parliamentary borough of Galway as the town commissioners may appoint.
- (10.) Any reference to Part IV. of the Municipal Corporations Act, 1882, shall be construed to refer to the Corrupt Practices (Municipal Elections) Act, 1872.
- (11.) Any reference to the Licensing Acts shall be construed to refer to the Licensing Acts (Ireland), 1872-1874.
- (12.) The Public Health (Ireland) Act, 1878, shall be substituted for the Public Health Act, 1875.
- (13.) The provisions with respect to the removal of cases to the Central Criminal Court, or to the trial of cases at the Royal Courts of Justice, shall not apply to Ireland.

#### *Continuance.*

41 & 42 Vict.  
c. 52.

Continuance.

70. This Act shall continue in force until the thirty-first day of December one thousand eight hundred and eighty-four, and no longer, unless continued by Parliament ; and such of the Corrupt Practices Prevention Acts as are referred to in Part One of the Third Schedule to this Act shall continue in force until the same day, and no longer, unless continued by Parliament.

## SCHEDULES.

### FIRST SCHEDULE.

#### PART I.

##### PERSONS LEGALLY EMPLOYED FOR PAYMENT.

- (1.) One election agent and no more.
- (2.) In counties one deputy election agent (in this Act referred to as a sub-agent) to act within each polling district and no more.
- (3.) One polling agent in each polling station and no more.
- (4.) In a borough one clerk and one messenger, or if the number of electors in the borough exceeds five hundred, a number of clerks and messengers not exceeding in number one clerk and one messenger for every complete five hundred electors in the borough, and if there is a number of electors over and above any complete five hundred or complete five hundreds of electors, then one clerk and one messenger may be employed for such number, although not amounting to a complete five hundred.
- (5.) In a county for the central committee-room one clerk and one messenger, or if the number of electors in the county exceeds five thousand, then a number of clerks and messengers not exceeding in number one clerk and one messenger for every complete five thousand electors in the county; and if there is a number of electors over and above any complete five thousand or complete five thousands of electors, then one clerk and one messenger may be employed for such number, although not amounting to a complete five thousand.
- (6.) In a county a number of clerks and messengers not exceeding in number one clerk and one messenger for each polling district in the county, or where the number of electors in a polling district exceeds five hundred one clerk and one messenger for every complete five hundred electors in the polling district, and if there is a number of electors over and above any complete five hundred or complete five hundreds of electors, then one clerk and one messenger may be employed for such number, although not amounting to a complete five hundred: Provided always, that the number of clerks and messengers so allowed in any county may be employed in any polling district where their services may be required.
- (7.) Any such paid election agent, sub-agent, polling agent, clerk, and messenger may or may not be an elector but may not vote.
- (8.) In the case of the boroughs of East Retford, Shoreham, Crick-lade, Much Wenlock, and Aylesbury, the provisions of this part of this schedule shall apply as if such borough were a county.

#### PART II.

##### LEGAL EXPENSES IN ADDITION TO EXPENSES UNDER PART I.

- (1.) Sums paid to the returning officer for his charges not exceeding the amount authorised by the Act 38 & 39 Vict. c. 84.

- (2.) The personal expenses of the candidate.
- (3.) The expenses of printing, the expenses of advertising, and the expenses of publishing, issuing, and distributing addresses and notices.
- (4.) The expenses of stationery, messages, postage, and telegrams.
- (5.) The expenses of holding public meetings.
- (6.) In a borough the expenses of one committee-room and if the number of electors in the borough exceeds five hundred then of a number of committee-rooms not exceeding the number of one committee-room for every complete five hundred electors in the borough, and if there is a number of electors over and above any complete five hundred or complete five hundreds of electors, then of one committee-room for such number, although not amounting to a complete five hundred.
- (7.) In a county the expenses of a central committee-room, and in addition of a number of committee-rooms not exceeding in number one committee-room for each polling district in the county, and where the number of electors in a polling district exceeds five hundred one additional committee-room may be hired for every complete five hundred electors in such polling district over and above the first five hundred.

## PART III.

*Maximum for Miscellaneous Matters.*

Expenses in respect of miscellaneous matters other than those mentioned in Part I. and Part II. of this schedule not exceeding in the whole the maximum amount of two hundred pounds, so nevertheless that such expenses are not incurred in respect of any matter or in any manner constituting an offence under this or any other Act, or in respect of any matter or thing, payment for which is expressly prohibited by this or any other Act.

## PART IV.

*Maximum Scale.*

(1.) In a borough the expenses mentioned above in Parts I., II., and III. of this Schedule, other than personal expenses and sums paid to the returning officer for his charges, shall not exceed in the whole the maximum amount in the scale following:—

If the number of electors on the register—		The maximum amount shall be—	
Does not exceed 2,000 . . . . .		£350.	
Exceeds 2,000 . . . . .		£380, and an additional £30 for every complete 1,000 electors above 2,000.	
Provided that in Ireland if the number of electors on the register—		The maximum amount shall be—	
Does not exceed 500 . . . . .		£200.	
Exceeds 500, but does not exceed 1,000 . . . . .		£250.	
Exceeds 1,000, but does not exceed 1,500 . . . . .		£275.	

(2.) In a county the expenses mentioned above in Parts I., II., and III. of this Schedule, other than personal expenses and sums paid to the returning officer for his charges, shall not exceed in the whole the maximum amount in the scale following :—

If the number of electors on the register—		The maximum amount shall be—
Does not exceed 2,000	.	£650 in England and Scotland, and £500 in Ireland.
Exceeds 2,000	.	£710 in England and Scotland, and £540 in Ireland, and an additional £60 in England and Scotland, and £40 in Ireland, for every complete 1,000 electors above 2,000.

## PART V.

*General.*

(1.) In the case of the boroughs of East Retford, Shoreham, Cricklade, Much Wenlock and Aylesbury, the provisions of Parts II., III., and IV. of this schedule shall apply as if such borough were a county.

(2.) For the purposes of this schedule the number of electors shall be taken according to the enumeration of the electors in the register of electors.

(3.) Where there are two or more joint candidates at an election the maximum amount of expenses mentioned in Parts III. and IV. of this schedule shall, for each of such joint candidates, be reduced by one-fourth, or if there are more than two joint candidates, by one-third.

(4.) Where the same election agent is appointed by or on behalf of two or more candidates at an election, or where two or more candidates, by themselves or any agent or agents, hire or use the same committee-rooms for such election, or employ or use the services of the same sub-agents, clerks, messengers, or polling agents at such election, or publish a joint address or joint circular or notice at such election, those candidates shall be deemed for the purposes of this enactment to be joint candidates at such election.

Provided that—

- (a.) The employment and use of the same committee-room, sub-agent, clerk, messenger, or polling agent, if accidental or casual, or of a trivial and unimportant character, shall not be deemed of itself to constitute persons joint candidates.
- (b.) Nothing in this enactment shall prevent candidates from ceasing to be joint candidates.
- (c.) Where any excess of expenses above the maximum allowed for one of two or more joint candidates has arisen owing to his having ceased to be a joint candidate, or to his having become a joint candidate after having begun to conduct his election as a separate candidate, and such ceasing or beginning was in good faith, and such excess is not more than under the circumstances is reasonable, and the total expenses of such candidate do not exceed the maximum amount allowed for a separate candidate, such excess shall be deemed to have arisen from a

reasonable cause within the meaning of the enactments respecting the allowance by the High Court or Election Court of an exception from the provisions of this Act which would otherwise make an act an illegal practice, and the candidate and his election agent may be relieved accordingly from the consequences of having incurred such excess of expenses.

## SECOND SCHEDULE.

### PART I.

#### FORM OF DECLARATIONS AS TO EXPENSES.

##### *Form for Candidate.*

I, \_\_\_\_\_, having been a candidate at the election for the county [or borough] of \_\_\_\_\_ on the \_\_\_\_\_ day of \_\_\_\_\_, do hereby solemnly and sincerely declare that I have examined the return of election expenses [about to be] transmitted by my election agent [or if the candidate is his own election agent, "by me"] to the returning officer at the said election, a copy of which is now shown to me and marked \_\_\_\_\_, and to the best of my knowledge and belief that return is correct ;

And I further solemnly and sincerely declare that, except as appears from that return, I have not, and to the best of my knowledge and belief no person, nor any club, society, or association, has on my behalf, made any payment, or given, promised, or offered any reward, office, employment, or valuable consideration, or incurred any liability on account of or in respect of the conduct or management of the said election ;

And I further solemnly and sincerely declare that I have paid to my election agent [if the candidate is also his own election agent, leave out "to my election agent"] the sum of \_\_\_\_\_ pounds and no more for the purpose of the said election, and that, except as specified in the said return, no money, security, or equivalent for money has to my knowledge or belief been paid, advanced, given, or deposited by anyone to or in the hands of my election agent [or if the candidate is his own election agent, "myself"] or any other person for the purpose of defraying any expenses incurred on my behalf on account of or in respect of the conduct or management of the said election ;

And I further solemnly and sincerely declare that I will not, except so far as I may be permitted by law, at any future time make or be party to the making or giving of, any payment, reward, office, employment, or valuable consideration for the purpose of defraying any such expenses as last mentioned, or provide or be party to the providing of any money, security, or equivalent for money for the purpose of defraying any such expenses.

*Signature of declarant*

*C.D.*



Signed and declared by the above-named declarant on the  
day of \_\_\_\_\_, before me.

(Signed) *E.F.*

Justice of the Peace for

*Form for Election Agent.*

I, \_\_\_\_\_, being election agent to \_\_\_\_\_, candidate  
at the election for the county [or borough] of \_\_\_\_\_, on the  
day of \_\_\_\_\_, do hereby solemnly and sincerely  
declare that I have examined the return of election expenses about to  
be transmitted by me to the returning officer at the said election, and  
now shown to me and marked \_\_\_\_\_, and to the best of my knowledge  
and belief that return is correct ;

And I hereby further solemnly and sincerely declare that, except as  
appears from that return, I have not and to the best of my knowledge  
and belief no other person, nor any club, society, or association has on  
behalf of the said candidate made any payment, or given, promised, or  
offered any reward, office, employment, or valuable consideration, or  
incurred any liability on account of or in respect of the conduct or  
management of the said election ;

And I further solemnly and sincerely declare that I have received from  
the said candidate \_\_\_\_\_ pounds and no more [or nothing] for  
the purpose of the said election, and that, except as specified in the said  
return sent to me, no money, security, or equivalent for money has been  
paid, advanced, given, or deposited by any one to me or in my hands,  
or, by the best of my knowledge and belief, to or in the hands of any  
other person for the purpose of defraying any expenses incurred on  
behalf of the said candidate on account of, or in respect of the conduct  
or management of the said election.

*Signature of declarant*

*A.B.*

Signed and declared by the above-named declarant on the  
day of \_\_\_\_\_ before me.

(Signed) *E.F.*

Justice of the Peace for

FORM OF RETURN OF ELECTION EXPENSES.

I, *A.B.*, being election agent to *C.D.*, candidate at the election for  
the county [or borough] of \_\_\_\_\_ on the \_\_\_\_\_ day of \_\_\_\_\_  
make the following return respecting election expenses  
of the said candidate at the said election [or where the candidate has  
named himself as election agent, "I, *C.D.*, candidate at the election for  
"the county [or borough] of \_\_\_\_\_ on the \_\_\_\_\_ day of \_\_\_\_\_  
"\_\_\_\_\_, acting as my election agent, make the following  
"return respecting my election expenses at the said election"].

*Receipts.*

Received of [the above-named candidate] [or where the  
candidate is his own election agent, "Paid by \_\_\_\_\_  
me"] \_\_\_\_\_ £

Received of *J.K.* . . . . . £  
*[Here set out the name and description of every person, club, society, or association, whether the candidate or not, from whom any money, securities, or equivalent of money was received in respect of expenses incurred on account of or in connexion with or incidental to the above election, and the amount received from each person, club, society, or association separately.]*

### *Expenditure.*

Paid to <i>E.F.</i> , the returning officer for the said county [or borough], for his charges at the said election . . . . .	£
Personal expenses of the said <i>C.D.</i> , paid by himself [or if the candidate is his own election agent, "Paid by me as candidate"] . . . . .	£
Do. . . . . paid by me [or if the candidate is his own election agent, add "acting as election agent"] . . . . .	£
Received by me for my services as election agent at the said election [or if the candidate is his own election agent, leave out this item] . . . . .	£
Paid to <i>G.H.</i> as sub-agent of the polling district of . . . . .	£
<i>[The name and description of each sub-agent and the sum paid to him must be set out separately.]</i>	
Paid to . . . . . as polling agent . . . . .	£
Paid to . . . . . as clerk for . . . . . days services . . . . .	£
Paid to . . . . . as messenger for . . . . . days services . . . . .	£

*[The names and descriptions of every polling agent, clerk, and messenger, and the sum paid to each, must be set out separately either in the account or in a separate list annexed to and referred to in the account, thus, "Paid to polling agent (or as the case may be) as per annexed list £ . . ."]*

Paid to the following persons in respect of goods supplied or work and labour done :

To <i>P.Q.</i> (printing) . . . . .	£
To <i>M.N.</i> (advertising) . . . . .	£
To <i>R.S.</i> (stationery) . . . . .	£

*[The name and description of each person, and the nature of the goods supplied, or the work and labour done by each, must be set out separately either in the account or in a separate list annexed to and referred to in the account.]*

Paid for postage . . . . .	£
Paid for telegrams . . . . .	£
Paid for the hire of rooms as follows :—	
For holding public meetings . . . . .	£
For committee-rooms . . . . .	£

*[A room hired for a public meeting or for a committee-room must be named or described so as to identify it; and the name and description of every person to whom*

*any payment was made for each such room, together with the amount paid, must be set out separately either in the account or in a separate list annexed to and referred to in the account.]*

Paid for miscellaneous matters, namely— . . . £

*[The name and description of each person to whom any sum is paid, and the reason for which it was paid to him, must be set out separately either in the account or in a separate list annexed to and referred to in the account.]*

In addition to the above, I am aware, as election agent for C.D., [or if the candidate is his own election agent, leave out "as election agent for C.D."] of the following disputed and unpaid claims; namely—  
Disputed claims.

By T.U. for . . . . . £

*[Here set out the name and description of each person whose claim is disputed, the amount of the claim, and the goods, work, or other matter on the ground of which the claim is based.]*

Unpaid claims allowed by the High Court to be paid after the proper time or in respect of which application has been or is about to be made to the High Court.

By M.O. for . . . . . £

*[Here state the name and description of each person to whom any such claim is due, and the amount of the claim, and the goods, work, and labour or other matter on account of which the claim is due.]*

(Signed) A.B.

## PART II.

### FORM OF DECLARATION AS TO EXPENSES.

*Form for candidate where declared a candidate or nominated in his absence and taking no part in the election.*

I, \_\_\_\_\_, having been nominated [or having been declared by others] in my absence [to be] a candidate at the election for the county or borough of \_\_\_\_\_, held on the \_\_\_\_\_ day of \_\_\_\_\_, do hereby solemnly and sincerely declare that I have taken no part whatever in the said election.

And I further solemnly and sincerely declare that [or with the exception of \_\_\_\_\_] I have not, and no person, club, society, or association at my expense has, made any payment or given, promised, or offered, any reward, office, employment, or valuable consideration, or incurred any liability on account of or in respect of the conduct or management of the said election.

And I further solemnly and sincerely declare that [*or* with the exception of ] I have not paid any money or given any security or equivalent for money to the person acting as my election agent at the said election, or to any other person, club, society, or association on account of or in respect of the conduct or management of the said election, and that [*or* with the exception of ] I am entirely ignorant of any money security or equivalent for money having been paid, advanced, given, or deposited by any one for the purpose of defraying any expenses incurred on account of or in respect of the conduct or management of the said election.

And I further solemnly and sincerely declare that I will not, except so far as I may be permitted by law, at any future time make or be party to the making or giving of any payment, reward, office, employment, or valuable consideration for the purpose of defraying any such expenses as last mentioned, or provide or be party to the providing of any money, security, or equivalent of money for the purpose of defraying any such expenses.

*Signature of declarant*

*C.D.*

Signed and declared by the above-named declarant on the  
day of. , before me,

(Signed) *E.F.*

Justice of the Peace for

### THIRD SCHEDULE.

#### CORRUPT PRACTICES PREVENTION ACTS.

Session and Chapter.	Title of Act.	Enactments referred to as being the Corrupt Practices Prevention Act.
<b>PART I.</b>		
<i>Temporary.</i>		
17 & 18 Vict. c. 102 .	The Corrupt Practices Prevention Act, 1854.	The whole Act so far as unrepealed.
26 & 27 Vict. c. 29 .	An Act to amend and continue the law relating to corrupt practices at elections of Members of Parliament.	The whole Act so far as unrepealed.
31 & 32 Vict. c. 125 .	The Parliamentary Elections Act, 1868.	The whole Act so far as unrepealed.
35 & 36 Vict. c. 33 .	The Ballot Act, 1872.	Part III. so far as unrepealed.
42 & 43 Vict. c. 75 .	The Parliamentary Elections and Corrupt Practices Act, 1879.	The whole Act so far as unrepealed.

Session and Chapter.	Title of Act.	Enactments referred to as being the Corrupt Practices Prevention Acts.
PART TWO.		
<i>Permanent.</i>		
30 & 31 Vict. c. 102.	The Representation of the People Act, 1867.	Sections eleven, forty-nine, and fifty.
31 & 32 Vict. c. 48 .	The Representation of the People (Scotland) Act, 1868.	Sections eight and forty-nine.
31 & 32 Vict. c. 49 .	The Representation of the People (Ireland) Act, 1868.	Sections eight and thirteen.
44 & 45 Vict. c. 40 .	The Universities Elections Amendment (Scotland) Act, 1881.	Sub-section seventeen of section two.



## PART THREE.

## ENACTMENTS DEFINING THE OFFENCES OF BRIBERY AND PERSONATION.

[The full text of all these enactments is given in the body of the work. See pp. 3, 4, 5].

## FOURTH SCHEDULES.

## SHORT TITLES.

Session and Chapter.	Long Title.	Short Title.
15 & 16 Vict. c. 57 .	An Act to provide for more effectual inquiry into the existence of corrupt practices at the election of Members to serve in Parliament.	Election Commissioners Act, 1852.
26 & 27 Vict. c. 29 .	An Act to amend and continue the law relating to corrupt practices at elections of Members of Parliament.	The Corrupt Practices Prevention Act, 1863.

## FIFTH SCHEDULE.

## ENACTMENTS REPEALED.

NOTE.—Portions of Acts which have already been specifically repealed are in some instances included in the repeal in this Schedule in order to preclude henceforth the necessity of looking back to previous Acts.

A description or citation of a portion of an Act is inclusive of the words, section, or other part first or last mentioned, or otherwise referred to as forming the beginning or as forming the end of the portion comprised in the description or citation.

Session and Chapter.	Title or Short Title.	Extent of Repeal.
60 Geo. 3. & 1 Geo. 4 c. 11.	An Act for the better regulation of polls, and for making further provision touching the election of Members to serve in Parliament for Ireland.	Section thirty-six.
1 & 2 Geo. 4. c. 58.	An Act to regulate the expenses of election of Members to serve in Parliament for Ireland.	The whole Act except section three.
4 Geo. 4. c. 55.	An Act to consolidate and amend the several Acts now in force so far as the same relate to the election and return of Members to serve in Parliament for the counties of cities and counties of towns in Ireland.	Section eighty-two.
17 & 18 Vict. c. 102.	The Corrupt Practices Prevention Act, 1854.	Section one.  Section two, from “and any person so offending” to “with full costs of suit.”  Section three, from “and any person so “offending” to the end of the section.  Section four.  Section five.  Section six.

Session and Chapter.	Title or Short Title.	Extent of Repeal.
17 & 18 Vict. c. 102 .	The Corrupt Practices Prevention Act, 1854.	Section seven, from "and all payments" to the end of the section.  Section nine, section fourteen, section twenty-three, section thirty-six, section thirty-eight, from "and the words personal expenses" to the end of the section, and section thirty-nine and Schedule A.
21 & 22 Vict. c. 87. .	An Act to continue and amend the Corrupt Practices Prevention Act, 1854.	The whole Act.
26 & 27 Vict. c. 29 .	An Act to amend and continue the law relating to corrupt practices at elections of Members of Parliament.	The whole Act, except section six.
30 & 31 Vict. c. 102.	The Representation of the People Act, 1867,	Section thirty-four, from "and in other boroughs the justices" to "greater part thereof is situate" and section thirty-six.
31 & 32 Vict. c. 48 .	The Representation of the People (Scotland) Act, 1868.	Section twenty-five.
31 & 32 Vict. c. 49 .	The Representation of the People (Ireland) Act, 1868.	Section twelve.
31 & 32 Vict. c. 58. .	The Parliamentary Electors Registration Act, 1868.	Section eighteen, from "the power of dividing their county" to the end of the section.
31 & 32 Vict. c. 125 .	The Parliamentary Elections Act, 1868.	So much of section three as relates to the definitions of "candidate."  Section sixteen.

Session and Chapter.	Title or Short Title.	Extent of Repeal.
31 & 32 Vict. c. 125 .	The Parliamentary Elections Act, 1868.	<p>Section thirty-three.</p> <p>Section thirty-six.</p> <p>Section forty-one, from "but according to the same principles" to "the High Court of Chancery."</p> <p>Section forty-three.</p> <p>Section forty-five.</p> <p>Section forty-six.</p> <p>Section forty-seven.</p> <p>Section fifty-eight, from "The principles" down to "in the court of session," being subsection sixteen.</p>
35 & 36 Vict. c. 33. .	The Ballot Act, 1872.	<p>Section five, from the beginning down to "one hundred registered electors."</p> <p>Section twenty-four, from "The offence of personation, or of aiding," to "hard labour," and from "The offence of personation shall be deemed to be" to the end of the section.</p>
42 & 43 Vict. c. 75. .	The Parliamentary Elections and Corrupt Practices Act, 1879.	Section three and schedule.
43 Vict. c. 18. . .	The Parliamentary Elections and Corrupt Practices Act, 1880.	The whole Act, except sections one and three.



# INDEX.

- ADDRESS, contracts for exhibition of, when illegal practice, 58.
- ADVERTISING AGENT, may be paid for bill posting, &c., 58.
- AGREEMENT by one candidate to pay expenses of another, not generally bribery, 33.
- AGENCY,  
A question of fact, 72.  
In case of joint candidature, 83.
- AGENTS,  
Of candidate, 66 *et seq.*  
★ Candidate liable for acts of, 66, 68.  
Sub-agents, extent of their authority, 67.  
Number of unpaid, not limited, 68.  
Authority to canvass, effect of, 68.  
Limitations of their authority, 69, 70.  
Disobedient, candidate liable for, 69.  
Implied, how constituted, 71.  
Need not be paid, 71.  
Canvassing does not constitute agency, 72.  
Nor being on a large committee, 72, 73.  
Sufficient evidence of being, what is, 73.  
May act by sub-agents, 75.  
Members of political associations, how far, 76, 82.  
Effect of repudiation by candidate, 79.  
Candidate using political association, makes its officers, 80.  
Responsibility of candidates for, when treacherous, 84.  
When their agency begins, 85.  
And ends, 85.  
Excessive number of paid, 92.  
Number allowed, if paid, in counties, 92.  
Number allowed, if paid, in boroughs, 93.
- AGENTS convicted of corruption, employment of, avoids election, 100.
- ALIENS, if they should vote, 97.
- AMENDMENT of petition, 140.
- APPOINTMENT of election agent, 107 *et seq.*
- ASSOCIATIONS,  
Political, 76, 82.  
Political, repudiation of, 79, 80.  
Political, when candidate responsible for, 81.
- BALLOT,  
Test, bribery at, 21.  
Advertising, to be a sham, 55.
- BANDS and banners, payments for, illegal 91.
- BARRISTER'S court money, payment of, when bribery, 16.
- BARRISTERS, special punishment of, 181.
- BETS on election, 34.
- BILL POSTING, contracts for, when illegal practice, 58 *et seq.*
- BOROUGHs, close, sale of, 33.
- "BOTTLING" voters, 50.
- BRIBERY,  
By agent, avoids election, 2.  
Statutory definition of, 2, 3, 4.  
Need not be direct, 7.  
Time when done, how far material, 8, 9.  
Effect of, when done after election, 9.  
Amount given in, immaterial, 10.  
Form of, immaterial, 10.  
Committed, although vote not affected, 10.  
By colourable payments, 12-19.  
At municipal election may avoid parliamentary election, 19, 20.  
At test ballot, 21.  
At former election, 21.  
By proper household expenditure, 23.  
By charitable gifts, 25-32.  
By purchasing influence, 32, 33.  
By wages, 34.  
No relief from consequences of, 46, 47.
- CABS, excessive hiring of, when bribery, 14.
- CANDIDATE'S EXPENSES, agreement by another candidate to pay, 33, 34.
- CANDIDATE,  
Bribery by, 2 *et seq.*  
Illegal practices by, 87 *et seq.*  
Illegal payments by, 87.  
Personal expenses of, 114, 122.  
Election expenses of, 113 *et seq.*  
Subscriptions to pay expenses of, 121.  
To make declaration of purity, 128.  
Declaration by, when abroad, 128.  
False declaration by, 129.
- CANVASSERS, colourable payments to, bribery, 11.
- CANVASSING, illegitimate, 49.
- CHARITIES, subscriptions to, 25.

- CHARITABLE GIFTS, 25-32.
- CHILDREN, payments to, may be bribery, 7.
- CLERICAL ORGANISATION, when candidate responsible for, 82.
- CLERGYMEN, intimidation by, 53, 54.  
Special punishment of, 181.
- CLERKS, to be appointed by election agent, 112.  
Colourable payments to, bribery, 11.
- CLOSE BOROUGHs, sale of, 33.
- CLUBS, when use of, as committee-rooms, prohibited, 94.
- COALS, gifts of, to electors, 29.
- COCKADES, payments for, illegal, 91.
- COLOURABLE PAYMENTS, bribery, 11.
- COMMITTEE, election, agency of, 76.
- COMMITTEE ROOM, what is, 62.
- COMMITTEE ROOMS,  
Employment of, when bribery, 14.  
Excessive number of, contracts for, 58.  
Number allowed, 61, 62, 94.
- COMMONS, House of, resolution by, not law, 50.
- CONVEYANCE OF VOTERS,  
Contracts for payment for, an illegal practice, 58.  
By sea, 91.  
To poll, when bribery, 15, 16.  
To poll, old law as to, 59.
- CORRUPTLY," meaning of, 37.
- CORRUPT PRACTICES,  
Defined, 2.  
How punished, 175 *et seq.*
- COSTS,  
On election petitions, 164 *et seq.*  
Usually follow the event, 165.  
Exceptions to the rule where petition succeeds, 165, 166.  
Exceptions to the rule where petition fails, 165, 166.  
When returning officer in fault, 166.  
Agreement not to ask for, 166.  
Where constituency may be ordered to pay, 166.  
Where persons (not parties to petition) ordered to pay, 167, 168.  
Expenses of witnesses, 168.  
Taxation of, 168 *et seq.*  
To be taxed on a liberal scale, 170,  
Counsel's fees, 171, 172.  
Instructions for hiring, 172.  
Number of witnesses allowed, 173.  
When to be incurred, 173.  
How recovered, 174.  
Payment out of security fund, 174.
- COUNTIES, conveyance of voters by sea, when legal, 91.

- COURT,  
Attendance of director of public prosecutions at election court, 177, 179.  
By what courts offenders tried and punished, 180 *et seq.*  
Election commissioners and their powers, 181.  
Effect of their report, 181, 182.  
Appeal from election commissioner, to which, 183.  
Report of election court, 184.  
Effect of report of election court, 185, 187.  
Power of election, to try offenders, 187.  
Sentences by election, 188.  
Trial by court of summary jurisdiction, 189, 193.  
Time for prosecuting before any, 190.  
Appeal from summary jurisdiction, 192.  
Prosecutions before assize, 193, *et seq.*  
Venue may be changed, 193.  
Actions in civil, for penalties, 196.
- CRIMINAL LAW, offences against. See *Punishments.*
- DECLARATION OF ELECTION,  
Expenses by election agent, 128.  
By candidate, 128.
- DENTISTS, special punishment of, 181.
- DISCOVERY, 143.
- DISPUTED CLAIM,  
Action for, 125.  
May be taxed, 126.
- DISSENTERS, intimidation by, 53.
- DISSENTING MINISTERS,  
Intimidation by, 54.  
Intimidation of, 53.
- DOCTORS, special punishment of, 181.
- DOCUMENTS, production of, 162.
- DRUNKENNESS, general, evidence of general treating, 104.
- ECCLESIASTICS,  
Limits of their influence, 53.  
Undue influence by, 54.  
May select candidate, 53.  
And canvass for him, 53.
- ELECTION COMMITTEE, agency of, 76.
- ELECTION EXPENSES, payment of, except through election agent, an illegal practice, 63, 113.
- ELECTION AGENT,  
Illegal practices by, avoiding election, 87.  
His appointment and duties, 107 *et seq.*  
Who should be appointed, 108.  
Should be a solicitor, 107.  
When to be appointed, 108.  
When to be named, 108.

ELECTION AGENT,

- And to whom to be named, 109.
- Notice of appointment of, 109.
- May be changed, 109.
- Offices of, 111.
- Service of documents on, 112.
- Remuneration of, 123.
- To pay election expenses, 121.
- To make return of election expenses, 127.
- To make declaration, 128.

ELECTION EXPENSES,

- Should be estimated in advance, 114.
- What need not be estimated or returned, 114.
- What kinds are allowable, 115.
- Maximum amount allowed, 116.
- Scale of, in boroughs and counties, 117, 118.
- Certain boroughs considered as counties, 118, 119.
- In case of joint candidature restricted, 119.
- Relief in case of limit being exceeded, 120.
- To be paid by election agent, 121.
- Claims for, to be sent to election agent, 122.
- When to be sent in, 122.
- Late claims for, barred, 123.
- When to be paid, 124.
- Leave to pay out of time, how obtained, 124 *et seq.*
- Return of, 127.
- Declaration verifying return of, 128.

ELECTION PETITION. See *Petition*.

ELECTION AUDITORS, 108.

ELECTION, avoided at common law when, 103.

EMPLOYERS, intimidation by, 52.

EMPLOYMENT OF VOTERS,

- When bribing, 11-14.
- Of corrupt agent, avoids election, 100.
- When "personal," 100, 101.

ESTIMATE OF ELECTION EXPENSES, 114.

EVIDENCE,

- Cogent, of mere offer required, 7.
- Of agency, what is sufficient, 73-83.

EXPENDITURE,

- Lavish household, not necessarily bribery, 24.

EXPENSES,

- Election, through whom to be paid, 63.
- As to petty expenses, 63.
- Of election, see *Election Expenses*.

EXPENSE AGENT, 108.

EVIDENCE ON ELECTION PETITIONS,

- Rules of common law generally apply, 157.
- Exceptions, 157, 158.
- Witnesses ordered out of court, 158.
- Improper rejection or admission of, 158.
- Discrediting witness, 159.
- Cross-examining hostile witness, 159.

EVIDENCE ON ELECTION PETITIONS,

- Use of witness's previous statements, 156, 160.
- Admissions by witness, 160.
- Court may require proof of agency first, 161.
- Political opinions of witness, 161.
- Of acts done at previous elections, 161.
- Of acts done at municipal elections, 162.
- Admissions by agent after poll, 163.
- Production of documents, 162.

FALSE DECLARATION,

- Avoids election, 57.
- A corrupt practice, 57.

FLYS,

- Payments for, illegal, 91.

FORFEITURE OF THE SEAT,

- How caused, 1.

FRAUDULENT devices to impede voting, 55.

FREEMEN'S ADMISSION FEES,

- Payment of, when bribery, 21.

GENERAL,

- Corruption, 103.
- Bribery, 103.
- Treating, 104.
- Intimidation, 105.
- Intimidation, effect of on poll, 105.

GIFTS,

- To non-electors, may be bribery, 6, 7.
- To children, may be bribery, 7.
- To women, may be bribery, 8.

HACKNEY CARRIAGES, when illegal to hire, 89.

HASTY WORDS, not undue influence, 55.

HIRING, illegal, what is, 59, 60.

HIRING, illegal, by candidate or his election agent, 88.

HOUSE OF COMMONS, resolution of, not law, 50.

HOUSEHOLD EXPENDITURE, lavish, not necessarily bribery, 24.

ILLEGAL PRACTICES,

- Avoiding the seat if done by any agent, 58 *et seq.*
- Avoiding the seat if done by election agent, 87.
- Avoiding the seat if done by any agent, 95.

ILLEGITIMATE CANVASSING, 49, 50.

IMPLIED PROMISE TO TREAT, 44.

INFERIOR AGENTS, &c., to be paid by election agent.

INFLUENCE,

- Purchase of, may be bribery, 32, 33.
- Undue. See *Undue Influence*, 48 *et seq.*

- INSPECTION OF BALLOT PAPERS, &c., 143, 151.
- INTERROGATORIES, not allowed, 143.
- INTIMIDATION. See *Undue Influence*, 48 *et seq.*
- JOINT CANDIDATURE,  
 Agency in case of, 83.  
 Expenses restricted in case of, 119.  
 What is, 119.  
 Severance of, 120.  
 Relief against excessive expenditure in, 120.
- JOINT COST, conveyance to the poll at, 89.
- JUSTICE OF PEACE, special punishment of, 181.
- LANDLORDS,  
 Undue influence by, 50.  
 May select their tenants, 51.
- LEGITIMATE INFLUENCE, 49.
- LENDING CARRIAGES, for conveyance of voters, when illegal, 59, 90.
- LIABILITY  
 Of candidate for agents, 66 *et seq.*  
 Of candidate for political associations, 76-82.
- LICENSED PREMISES may not be used as committee rooms, 94
- LIVERY STABLE KEEPER, payments to for carriages, &c., 59, 60.
- MASTER, what jurisdiction vested in, 134.
- MESSENGERS,  
 Colourable payments to, bribery, 11, 12.  
 To be appointed by election agent, 112.
- MONEY PROVIDED FOR ELECTION, to be paid to election agent, 113.
- MOTIVE OF DONOR, test of bribery, 6, 32.
- MUNICIPAL ELECTIONS,  
 Effect of bribery at, 19, 20.  
 Effect of treating at, 39.
- NON-ELECTORS,  
 Gifts to, may be bribery, 6, 7, 27.  
 Treating, may be corrupt treating, 27, 39.
- NON-RESIDENTS, may vote, when, 97.
- OBJECTIONS TO RETURN, particulars of, 145.
- OFFENCES. See *Punishments*.
- OFFENDERS,  
 Their detection and punishment, 175, *et seq.*  
 By what courts punished, 180 *et seq.*
- OFFER,  
 Corrupt, may be bribery, 6, 7.  
 Corrupt, cogent evidence of, required, 7.
- OFFICE, offer of an, bribery, 23.
- OPERATIVE, threats, to avoid an election, must be, 51.
- ORANGE LODGE, subscriptions to, 25.
- PAID AGENTS, excessive number of, 92.
- PAIRING, 55.
- PARTICULARS, delivery of, 143 *et seq.*
- PAYMENTS, what, illegal practices, 58 *et seq.*
- PAYMENTS, illegal, 95 *et seq.*
- PAUPERS, may vote, when, 97.
- PEERS may not vote, 97.
- PENALTIES, suits for, 196 *et seq.*
- PERSONATION,  
 Defined, 56.  
 Innocent, 56.  
 Offence of, when complete, 57.
- PERSONAL EXPENSES OF CANDIDATE,  
 What are, 115.  
 To be returned, 122.
- PETITION,  
 Who may petition, 134 *et seq.*  
 When to be presented, 135, 136.  
 How abated, 135  
 Practice on filing, 138.  
 Service of, 138,  
 Security for costs of, 139.  
 Objections to the security, 139.  
 Payment into court, how made, on, 139.  
 Amendment of, 140.  
 Formal objections to, 140.  
 Withdrawal of, 140-142.  
 Corrupt bargain to withdraw, 141.  
 Practice on withdrawal of, 141.  
 Withdrawing, opposition to, 142.  
 Discovery and interrogatories in aid of, 143.  
 Inspection of ballot papers, 143, 150.  
 Particulars, delivery of, 143-146.  
 Objections, particulars of, 145.  
 Production of telegrams, 145.  
 Commission to examine witness on, 145.  
 Witnesses on, 145-147.  
 Offering rewards for evidence, 146.  
 Trial of, 146, 147.  
 Relief on hearing of, 148.  
 Taxation of witnesses' expenses, 149.
- PETTY expenses by volunteers, 121.
- PLACARDS,  
 Excessive payments for, when bribery, 14.  
 Contracts for, when illegal practice, 58.
- POLITICAL CLUBS, premises of, may be used as committee-rooms, 94.
- POLITICAL SOCIETIES, treating, 45.
- POLLING agents, to be appointed by election agent, 112.
- POSTERS, issued without printer's name, 98.

- POPULARITY, treating to obtain, effect of, 39.
- PAYMENTS, illegal, 87.
- PRACTICES, illegal, by candidate or election agent, 87.
- PROFUSION before elections, 23, 24.
- PROHIBITED PAYMENTS, 116.
- PROMISE to treat, given before election, 44.
- PUBLIC-HOUSES,  
Opening, 41, 42.  
Opening, effect of, on elections, 103.
- PUBLIC MEETINGS, expenses of, 115.
- PRACTICE. See *Election Petition, Relief, Scrutiny and Criminal Law.*
- PROCEDURE. See *Election Petition, Scrutiny, Relief and Criminal Law.*
- PROSECUTIONS, Director of public, his functions, 177 *et seq.*  
Private, 178.
- PUNISHMENTS,  
By what courts awarded, 180 *et seq.*  
Effect of report of commissioners, 180, 182.  
Of barristers reported, 181.  
Of solicitors reported, 181.  
Of doctors, dentists and clergymen reported, 182.  
Before report, party to be heard, 183.  
Appeal upon report, 183, 184.  
By election court, 184, 187.  
Of candidate guilty of corrupt practice, 185.  
Of candidate guilty by his agent, 186.  
Effect of report of election court upon other persons, 187.  
Committal for trial by election court, 188.  
By a court of summary jurisdiction, 189.  
By the court of assize, 193.
- RABBITS, leave to take, when bribery, 22.
- RAILWAY FARE, payment of, when bribery, 15.
- RATES, corrupt payment of, bribery, 5, 18.
- REFRESHMENTS to paid agents, 40, 41.
- REGISTER, how far conclusive of right to vote, 97.
- REGISTRATION COURT, payments for attending, when bribery, 17.
- RELIEF.  
Against consequences of treating or undue influence, 46, 47, 56.  
None after bribery, 47.  
Against consequences of illegal practices, 63, 64, 98, 99.
- RELIEF BY THE COURT,  
Against effect of excessive expenditure, 121.  
Procedure to obtain, 131 *et seq.*  
Applications for, 131.
- RELIEF BY THE COURT,  
Parties to be heard on, 131.  
On default concerning return of election expenses, 132.  
On default concerning declaration, 132.  
Should be sought without delay, 132.  
How obtained when sub-agent in default, 133.  
In case of excessive expenditure, 134.  
On hearing of petition, 148.
- REPUDIATION OF AGENTS, 71, 78.
- RESOLUTION OF HOUSE OF COMMONS, not law, 50.
- RETIREMENT OF CANDIDATE, when illegal practices, 91.
- RETURNING OFFICER'S CHARGES, 114, 123, 127.
- REVISING BARRISTER'S COURT,  
Payment for attendance at, 16  
Treating for attendance at, 40.
- REWARDS FOR EVIDENCE, 146.
- RIBBONS, payment for, 91.
- RIOTING, general, effect of, 105, 106.
- ROOMS. See *Committee Rooms*, 58.
- SCALE OF EXPENDITURE on election allowed, 116, 118.
- SCHOOLROOM, when use of, as committee rooms, allowed, 94.
- SCRUTINY, where votes come off on a, 97.
- SOLICITORS, special punishment of, 181.
- SEAT, the, how forfeited, 1.
- SECURITY for costs of petition, 139 *et seq.*
- SERVICE OF NOTICES and documents, 112.
- SERVICE OF PETITION, 138.
- SEA, conveyance of voters by, when legal, 91.
- SPECIAL CASE, 143.
- SUB-AGENTS,  
How and when appointed, 110.  
Revocation of their appointment, 111.  
Candidate's liability for, 110.  
Offices of, 111.  
Service of notices on, 112.  
Relief for default on, 133.
- SUBSCRIPTIONS,  
To charities, 25.  
Towards candidate's expenses, legal, 34.  
Towards candidate's election expenses, 121.
- SCRUTINY OF VOTES,  
When made, 150.  
Recriminatory case upon, 150.  
Practice where claimed, 150 *et seq.*  
Delivery of scrutiny lists, 151.  
And list of objections, 151.  
Inspection of ballot papers, 150.  
Order of proceeding at trial, 152.

# SCRUTINY OF VOTES,

- Elector has no *locus standi*, 153.
- Register, how far conclusive on, 154.
- Ballot papers, ill marked, 155.
- Votes struck off, 155.
- When ballot papers examined, 156.
- Practice as to tendered votes, 157.

TELEGRAMS, production of, 145.

TENANTS, intimidation of, 50.

# TEST-BALLOT,

- Bribery at, 21.
- Treating at, 39, 40.

THREATS, when undue influence, 50, 52.

TORCHES, payments for, illegal, 91.

# TRAVELLING EXPENSES,

- Payment of, when bribery, 15, 16.
- Payment of, now always illegal, 16.

TREACHERY, by agent, 84.

TREATING BY AGENT, avoids election, 34.

# TREATING, 34, 47,

- On the nomination or polling day, 35.
- Statutory definitions of, 35, 36.
- Must be done corruptly, 37.
- Must be done to influence the vote, 38.
- Offer to treat is not, 39.
- But may be bribery, 39.
- Non-electors, may avoid election, 39.
- At municipal elections, 39.
- To obtain popularity, effect of, 39.
- At revision courts, 40.
- By refreshments to paid agents, 40.
- By opening public houses, 41.
- Amount of, immaterial, 42.
- Relief where, trivial, 42.
- Conditions on which relief granted, 46, 47.
- Time of, very material, 43, 45.

TRIAL OF PETITION, 146 *et seq.*

# UNDUE INFLUENCE,

- Defined, 48.
- Antiquity of law against, 48.
- Meaning of, 49.
- By illegitimate canvassing, 49, 50.
- Compared with bribery, 50.
- By bottling voters, 50.
- By landlords, 51.
- By employers, 52.

# UNDUE INFLUENCE,

- By workpeople, 52.
- Withdrawal of custom, 52.
- Spiritual intimidation, 53.
- Attempts to use, avoid election, 54.
- Hasty words not, 55.
- Relief against consequences of, 56.

UNIVERSITIES, corrupt payment of members' fees, bribery, 5.

VALUE OF BEIBE, immaterial, 10.

# VOLUNTARY AGENTS,

- number of, unlimited, 68, 71, 93.
- Candidate liable for, 68.
- Repudiation of, 76, 78.

VOTE, if not free, is bad, 48.

VOTERS, "bottling," 50.

VOTING, when illegal, 95.  
who are prohibited from, 96.

VOTING CARDS, when a fraudulent device, 55.

WAGERS on result of election, 34.

WAGES, day's, payment of, when bribery, 15, 21.

WATCHERS, colourable payments to, bribery, 11.

WITHDRAWAL of candidate (false statement of), 97.

# WITHDRAWAL

- Of custom, undue influence by, 52.
- Should be substantial, 53.

WITHDRAWAL of petition, 140 *et seq.*

# WITNESS,

- Commission to examine, 145.
- Attendance of, 145, 146.

# WITNESSES

- May be called by the court, 163.
- May be called by the public prosecutor, 146 *et seq.*

WORDS, hasty, not undue influence, 55.

# WORKPEOPLE,

- Holiday to, may be bribery, 21, 22.
- Intimidation of, 52.
- Intimidation by, 52.

# WOMEN,

- Gifts to, may amount to bribery, 8.
- Treating, may amount to bribery, 39.
- May not vote, 97.

# **WATERLOW & SONS LIMITED,**

*Law, Parliamentary and General Stationers.*

---

## **WRITING AND ENGROSSING.**

WATERLOW & SONS LIMITED have a large and competent staff of Clerks constantly engaged at their City and West End Establishments, and are enabled to undertake that Deeds or other documents, of whatever length, shall be carefully and correctly engrossed or copied, and returned if required, by Return Mail, or within a few hours after the receipt of the drafts.

## **LAW LITHOGRAPHY.**

The staff retained by WATERLOW & SONS LIMITED in this department is capable of completing in a few hours an amount of work which would formerly have required as many days. Briefs, Abstracts, Minutes of Evidence, Reports, and Legal Documents, Builders' Quantities, Specifications, &c., lithographed with the greatest accuracy, in good plain round hand. A Brief of 100 sheets can be lithographed in three or four hours.

## **ILLUMINATED ADDRESSES, VOTES OF THANKS, &c.**

WATERLOW & SONS LIMITED have attained a high degree of perfection in this department. Numerous works of great artistic beauty have been executed by them for presentation to Her Majesty, the Prince and Princess of Wales, and other important personages.

## **LETTER-PRESS PRINTING**

For Chancery Bills and Answers, Pleadings and Proceedings under the Judicature Act, Memoranda and Articles of Association, Particulars of Sale, Circulars, Notices, Special Forms, &c., &c. The Company offer the advantages of an extensive and varied assortment of Type and the aid of Machinery of the most approved construction.

*100 Copies of an ordinary Particulars of Sale and Plan can be executed in one day, if required.*

## **PARCHMENT.**

An extensive stock of the best Parchment, plain or ruled and red lined, for Indentures, Followers and Bookway Skins, or with black lines for Probates of Wills.

## **LAW FORMS.**

Writs, Notices, &c., under the Judicature Acts, Probate Forms, Drafts and Precedents, Bills of Sale, &c., Bankruptcy Forms, Joint-Stock Companies' Forms, &c., &c.

## **COPYING PRESSES,**

Letter Copying Books, and all materials.

**FIREPROOF SAFES,** of the best quality.

**DEED BOXES, CASH BOXES, CASES FOR FORMS, &c.**

**WRITING INKS,** Black, Red and Blue, **COPYING INK, &c.**

**ENGRAVING AND COPPER PLATE PRINTING**

For Cards, Cheques, Receipts, Bonds, Certificates, &c.

## **GENERAL STATIONERY**

Of every description, including Quill and Steel Pens and Pen-holders, Drawing Pencils, Inkstands, Despatch Boxes, Writing Cases, Brief Bags, Stationery Cabinets, Sealing Wax and Wafers, Tapes and Ferret, Cutlery, String and Twine, Postage Balances and Scales, Date Cases and Indicators, Wicker Office Baskets, Elastic Bands, &c., &c.

*An Illustrated Catalogue will be sent Free by Post on application.*

---

95 & 96, LONDON WALL; 25, 26 & 27, GREAT WINCHESTER STREET;  
49, PARLIAMENT STREET, AND FINSBURY FACTORIES.

# LIST OF PUBLICATIONS.

- THE BANKERS' MAGAZINE.**—Journal of the Money Market and Commercial Digest, A First Class Monthly Financial Publication, and the recognised organ of communication for the Banking interest. 1s. 6d. per number, or 21s. per annum, including two double numbers.
- THE BANKING ALMANAC, DIRECTORY, AND DIARY.**—Published annually in November. Cloth lettered, 7s. 6d.
- THE COUNTY COMPANION, DIARY, STATISTICAL CHRONICLE, AND MAGISTERIAL AND OFFICIAL DIRECTORY.**—Published annually in December. Prices—5s., 7s. 6d. and 12s., according to diary space and binding.
- THE SOLICITORS' DIARY, ALMANAC, AND DIRECTORY.**—Published annually in October. Prices—3s. 6d., 5s., 6s., and 8s. 6d., according to diary space. The POCKET EDITION, in leather tuck, 2s. 6d.; Roan Wallet, 4s. 6d.; and Russia Wallet, 7s. 6d.
- THE MUNICIPAL CORPORATIONS COMPANION, DIARY, DIRECTORY, AND YEAR-BOOK OF STATISTICS.**—Published annually in December. Prices—5s., 7s. 6d., 12s., according to diary space and binding.
- ENGLISH MUNICIPAL INSTITUTIONS; THEIR GROWTH AND DEVELOPMENT STATISTICALLY ILLUSTRATED.**—"A most useful and valuable work."—*Vide* Public Press. By J. R. SOMERS VINE, F.S.S. Royal 8vo, cloth, bevelled boards, 10s. 6d.
- THE ENGLISH MUNICIPAL CODE, or the MUNICIPAL CORPORATIONS (Consolidation) ACT, 1882,** with Notes, Comments, References, Statistical Appendix, and Voluminous Index, by J. W. HUME WILLIAMS, Barrister-at-Law, of the Middle Temple, and J. R. SOMERS VINE, F.S.S. Royal 8vo, stiff covers, 5s.; cloth lettered, 7s. 6d.
- THE NEW PRACTICE AND PLEADING UNDER THE JUDICATURE ACTS.**—With Notes and References, Rules of Court, Forms of Proceedings, and Pleadings, and a Copious Index. By Sir W. T. CHARLEY, Q.C. Third Edition. Price 7s. 6d., cloth lettered.
- THE NEW PRACTICE CASES.**—Containing important decisions upon the Judicature Acts. By Sir W. T. CHARLEY, Q.C. Nos. 1 to 12 are now ready, 1s. each number. The first two vols. (four numbers in each) bound in cloth, 5s. 6d. each. (Published at intervals.)
- CHAMBER CASES.**—Comprising all the Cases reported at Judges' Chambers and in the New Practice, With Notes and Comments. By Sir W. T. CHARLEY, Q.C. 3s. 6d., cloth.
- THE CONSOLIDATED COUNTY COURT ORDERS AND RULES, 1875, WITH FORMS AND SCALES OF COSTS AND FEES.**—(Reprinted, 1880.) Cloth back, 3s.
- The same, together with Scott's Index, Queen's Printers' Copy of the Act, and the additional Rules of 1876, 1880 and 1883. Cloth back, 7s. 6d.
- AN INDEX TO THE CONSOLIDATED COUNTY COURT ORDERS, RULES, AND FORMS, 1875.**—By H. ALAN SCOTT, of the Inner Temple, Barrister-at-Law, 2s.
- A COMPLETE TABLE OF THE TIMES FIXED UNDER THE COUNTY COURT ACT,** showing the Periods within or after which any proceeding may be taken. Price 1s.
- A TABLE (SECOND EDITION)** showing the various steps (down to the Hearing) of all ordinary Actions commenced in the country, for the use of Country Solicitors. The Table is published on an open sheet, 20 inches by 15 inches, showing at a glance the desired information. Price 1s.; or mounted on cardboard, varnished, 2s. 6d.
- A COMPLETE TABLE OF THE TIMES FIXED BY THE RULES OF THE SUPREME COURT OF JUDICATURE ACTS,** settled down to and including the Rules of December, 1876, showing the periods within or after which the different proceedings in an action should be taken. Price 1s.
- GUIDE TO THE PREPARATION OF BILLS OF COSTS,** with Precedents in all the Divisions, Schedule of Fees, Allowances to Witnesses, &c. By T. W. PRIDMORE, Esq. Sixth Edition, greatly enlarged. Cloth boards, lettered, 10s. 6d.
- THE SUMMARY JURISDICTION ACT, 1879,** with Notes, Rules, Index, &c. By H. MARTIN GREEN, Clerk to Justices. Price, in cloth, 3s. 6d.
- THE LAW OF MERCHANT SHIPPING AND FREIGHT,** with Tables of Cases, Forms, and Complete Index. (Royal 8vo, 700 pages.) By J. T. FOARD, of the Inner Temple, Barrister-at-Law. Price, in half-calf, One Guinea.
- PRINCIPLES AND PRECEDENTS OF MODERN CONVEYANCING, 1882.**—A Concise Exposition of the Draftsman's Art, with a Series of Forms framed in accordance with recent Legislation. By C. CAVANAGH, B.A., LL.B. (Lond.), of the Middle Temple and Northern Circuit, Barrister-at-Law; Author of "The Law of Money Securities." Cloth, 15s.
- MANUAL OF HYDROLOGY.** By N. BEARDMORE, C.E. In cloth, 24s.
- INDIAN EXCHANGE TABLES.** By J. I. BERRY. In cloth, 21s., or with Supplement, 25s.
- SUPPLEMENT TO DITTO,** separately, 5s.
- THE EMPLOYERS' LIABILITY ACT,** with Notes. By C. T. PART, Barrister-at-Law, 1s.



## LIST OF PUBLICATIONS—CONTINUED.

- THE BANKRUPTCY ACT, 1883**, with Introduction and Index. By M. D. CHALMERS, M.A., Barrister-at-Law, and E. HOUGH, of the Board of Trade. Demy 8vo., 2s. 6d.
- THE AGRICULTURAL HOLDINGS (ENGLAND) ACT, 1883**, with Notes and Forms, and a Summary of the Procedure. By J. W. JEUDWINE, of Lincoln's-Inn, Barrister-at-Law. Demy 8vo. In boards, 2s. 6d., or in cloth, 3s. 6d.
- THE LAW RELATING TO CORRUPT PRACTICES AT ELECTIONS, AND THE PRACTICE ON ELECTION PETITIONS**, with an Appendix of Statutes, Rules and Forms. By MILES WALKER MATTINSON and STUART CUNNINGHAM MACASKIE, of Gray's Inn, Barrister-at-Law. Demy 8vo.: in cloth, 7s. 6d.
- THE BILLS OF EXCHANGE ACT, 1882**.—An Act to Codify the Law relating to Bills of Exchange, Cheques, and Promissory Notes. With Comments and Explanatory Notes. By M. D. CHALMERS, Esq., M.A., Barrister-at-Law (Draughtsman of the Bill). In stiff boards, 2s. 6d.; in cloth, 3s. 6d.
- THE MARRIED WOMEN'S PROPERTY ACT (45 & 46 Vic., c. 75)**. A concise Treatise showing the effect of this Act upon the existing Law. By THOMAS BARRETT-LENNARD, Esq., of the Middle Temple, Barrister-at-Law. In stiff boards, 1s. 6d.
- THE BILLS OF SALE ACTS, 1878 & 1882**, with Copious Notes, Index, and Precedents, showing the Alteration in the Law under the New Act. By MICHAEL G. GUTRY, LL.B., of the Middle Temple, Barrister-at-Law. In cloth, 5s.
- THE POSITION IN LAW OF WOMEN**.—Showing how it differs from that of Men, and the effect of the Married Women's Property Act, 1882. By THOMAS BARRETT-LENNARD, of the Middle Temple, Barrister-at-Law. In cloth, 6s.
- THE ELECTRIC LIGHTING ACT**, with Hints to Local Authorities, Explanatory Notes, and Amended Rules of the Board of Trade, &c. By ARTHUR P. POLEY, B.A., of the Inner Temple, Barrister-at-Law, and FRANK DETHRIDGE, Esq. In boards, 2s.
- HANDBOOK ON STAMP DUTIES (FIFTH EDITION)**, revised and corrected by H. S. BOND, Esq., of the Solicitors' Department, Inland Revenue, Somerset House. Stiffened covers, 1s.; cloth, 2s.
- BALLOT ACT, 1872**.—Parliamentary and Municipal Elections Act, 1872, 35 and 36 Vic., cap. 33. 8vo. paper cover, 6d.
- BALLOT ACT, 1872**.—Abstract of the principal provisions of the Parliamentary and Municipal Elections Act, 1872, 35 and 36 Vic., cap. 33. Prepared for the information of Returning Officers at Parliamentary and Municipal Elections in England and Wales. 8vo., sewed, 3d.
- LAW ON BILLS OF EXCHANGE, PROMISSORY NOTES, CHEQUES, &c.**, of England Germany, France, Italy, and Spain. By H. D. JENCKEN, Barrister-at-Law. Price 5s.
- THE PRACTICE AND PROCEEDINGS OF THE COURTS OF INVESTIGATION INTO SHIPPING CASUALTIES AND COURTS OF SURVEY**.—With Index and References. By C. J. PEILE, Esq., Barrister-at-Law, of the Inner Temple. Cloth lettered, 2s. 6d. The work is dedicated, by permission, to the Wreck Commissioner.
- A DIGEST OF THE ELEMENTARY EDUCATION ACT, 1870**, with Orders of the Privy Council. A Concise Guide to Members of School Boards, and Instructions to Returning Officers and Town Clerks for conducting Elections, with Forms, by H. MONCKTON, Solicitor. Post 8vo. cloth lettered, 2s. 6d.
- GENERAL RAILWAY ACTS, 1830—1874**.—A Collection of the General Railway Acts for the Regulation of Railways in England and Ireland, including the Companies, Lands, and Railways Clauses Consolidation Acts. Thirteenth Edition, with the Amending Enactments complete to the close of 1874. 12mo. cloth, 18s.
- CLAUSES CONSOLIDATION ACTS, 1845—1877**. Cloth, 16s.
- STANDING ORDERS**.—The Standing Orders of the Lords and Commons relative to Private Bills, with Appendix. Published at the close of each Session. Cloth, 5s.
- PRACTICAL HINTS ON THE REGISTRATION OF FORMS AND RETURNS REQUIRED TO BE FILED** under the "Joint Stock Companies Acts, 1862 and 1867," and "The Railway Companies Security Act, 1866." 8vo. limp cloth, 1s. 6d.
- WATERLOW'S SCRIBBLING DIARY**. Foolscap folio, 6 days on a page, interleaved strong paper cover, 1s.; ditto 3 days, 1s. 6d.; ditto 2 days, 4 bound cloth, 3s.

# PRINCIPLES AND PRECEDENTS

OF

## MODERN CONVEYANCING,

1882,

*A Concise Exposition of the Draughtsman's Art, with a Series of Forms framed in accordance with the New Legislation.*

---

THE VOLUME IS DIVIDED INTO THREE PARTS :

I.—PRELIMINARY DISSERTATION.

II.—PRACTICAL CONVEYANCING ACTS, INCLUDING THE CONVEYANCING AND LAW OF PROPERTY ACT, 1881, WITH NOTES.

III.—PRECEDENTS.

---

The object of the present work is to supply a Handbook which shall at once explain the leading features of the system of Conveyancing inaugurated by the above statute and the Solicitors' Remuneration Act, 1881, and at the same time furnish such a selection of Precedents as will meet the ordinary needs of a Solicitor's office.

To render the book more complete, suggestions and directions are given, by the aid of which the forms in existing treatises may be adapted to the New Law.

BY

C. CAVANAGH, B.A., LL.B. (LOND.),

OF THE MIDDLE TEMPLE AND NORTHERN CIRCUIT, BARRISTER-AT-LAW.

*Author of "The Law of Money Securities."*

PRICE 15s.

---

WATERLOW & SONS LIMITED, LAW PUBLISHERS.

---

SECOND EDITION.

---

THE  
MARRIED WOMEN'S PROPERTY ACT

(45 & 46 VICT., c. 75.)

A CONCISE TREATISE,  
SHOWING THE  
EFFECT OF THIS ACT UPON THE EXISTING LAW,

BY

THOMAS BARRETT-LENNARD, Esq.,

OF THE MIDDLE TEMPLE, BARRISTER-AT-LAW.

---

IN STIFF BOARDS, 1s. 6d.

---

THE ENGLISH MUNICIPAL CODE

OR THE

MUNICIPAL CORPORATIONS (Consolidation) ACT, 1882,

WITH NOTES, COMMENTS, REFERENCES, STATISTICAL APPENDIX,  
AND VOLUMINOUS INDEX,

BY

J. W. HUME WILLIAMS,

BARRISTER-AT-LAW, OF THE MIDDLE TEMPLE,

AND

J. R. SOMERS VINE, F.S.S.,

AUTHOR OF "ENGLISH MUNICIPAL INSTITUTIONS—THEIR GROWTH AND DEVELOPMENT."

---

Royal 8vo., stiff covers, 5s.; cloth lettered, 7s. 6d.

---

95 & 96, LONDON WALL: 25, 26 & 27, GREAT WINCHESTER STREET;  
49, PARLIAMENT STREET, AND FINSBURY FACTORIES.

# THE BANKING ALMANAC AND DIARY, YEAR-BOOK OF STATISTICS, AND DIRECTORY.

EDITED BY R. H. INGLIS PALGRAVE, Esq., F.S.S.

THIS WORK, WHICH HAS LONG BEEN

PATRONISED BY THE BANK OF ENGLAND,

*The Private and Joint-Stock Banks, the Private and Public Discount Establishments, the Credit and Finance Companies, and the principal Financial and Mercantile Establishments,*

Contains much valuable Statistical Information from Official Documents.

The DIARY is printed on Supertine Paper, Svo, and Subscribers wishing to have Diaries with one page for each day, can obtain the same on application, at a slight increase of charge.

The ALMANAC—CALENDAR and USUAL TABLES—is full and complete.

The YEAR-BOOK embraces a variety of useful Statistics, and includes—

- I. Banking Retrospect.
- II. Statistics of the Bank of England, giving a complete analysis of the progress of its business from 1845, with the principal details of importance.
- III. Bills brought forward in Parliament concerning Banking in Great Britain and Ireland.
- IV. Returns of Bank Notes of the Bank of England held by the Public and in Reserve by the Bank, Bullion, Bills Discounted, London Bankers' Balances, &c.
- V. Information associated with Suspended Banks, Finance and Discount Companies.
- VI. Useful Information for Bank Managers and Cashiers. Tables of the value of the Coins in use in the various States of the World (including the nominal and metallic values)—Explanations of the Terms generally employed in Foreign Bills, Usance, Days of Grace, &c., &c.
- VII. Stamp Duties.
- VIII. Notices of Books referring to Banking, published during the year.
- IX. Abbott's Analysis of Joint-Stock Banks.
- X. Parliamentary Directory.
- XI. Insurance Directory, with Comparative Table of the Rates charged for Life Insurance by the Principal Offices in Great Britain.

TABLE OF PUBLIC GENERAL ACTS OF PAST SESSION.  
IMPORTANT PARLIAMENTARY PAPERS ON BANKING AND COMMERCE.

## THE BANKING DIRECTORY.

This portion of the work is made as complete and accurate as possible. It is *carefully revised*, and contains—

1. *Bank of England*.—List of all the Officers of the several Departments.
2. *London Bankers*—Names, Residences and Occupations, as given in the Official Returns.
3. *A List of all the Private Banks*, with the Names and Addresses of each of the Partners, carefully corrected from their own returns. Statement of Branches, and the Names of the Agents.
4. *A List of all the Joint-Stock Banks* in the United Kingdom, with the Dates of their Establishment; Number of Partners; Paid-up Capital; Guarantee Fund; Fixed Issues; and List of Branches and Sub-Branches, with the Names of the Managers at each.
5. *A List of Foreign and British Colonial Joint-Stock Banks* having Offices in London.
6. *The Particulars of the Finance and Credit Companies*, Capital, Reserve Fund, and the Principal Officers.
7. *An Alphabetical List of Colonial and Foreign Banks and Bankers*, greatly extended and improved.
8. *A List of Colonial and Foreign Banks and Bankers*.
9. *An Alphabetical List of all the Towns in Great Britain* where Banks are established, with the Title of the Bank, Name of its Manager, and London Agent.
10. *An Alphabetical List of all the Bankers* in the United Kingdom.
11. *An Alphabetical List of the Directors of the principal London Joint-Stock Banks* Discount Companies and Finance and Credit Companies.

Published in November. Price Seven Shillings and Sixpence.

WATERLOW & SONS LIMITED, LAW PUBLISHERS.

---

THE COUNTY COMPANION,  
DIARY, STATISTICAL CHRONICLE,  
AND  
Magisterial and Official Directory,  
*PUBLISHED ANNUALLY IN DECEMBER;*  
AND THE  
MUNICIPAL CORPORATIONS COMPANION.  
DIARY, DIRECTORY,  
AND  
YEAR BOOK OF STATISTICS.  
*PUBLISHED ANNUALLY IN DECEMBER.*

EDITED BY J. R. SOMERS VINE, F.S.S.

(*Author of "English Municipalities ; their Growth and Development."*)

---

WATERLOW & SONS LIMITED

Have much pleasure in stating that these Works have been unanimously declared to be  
INDISPENSABLE TO EVERY MAGISTRATE AND COUNTY OFFICIAL  
IN ENGLAND AND WALES,  
AND TO ALL WHO HOLD OFFICE IN OR UNDER ANY MUNICIPALITY,  
And unequalled Works of Reference for the general Public.

---

PRICE OF EITHER OF THE WORKS :

In Strong Cloth Binding, Lettered, with a Diary Space of one-third of a page to each day,  
*FIVE SHILLINGS.*

In Strong Cloth Boards, Gilt, with a Diary Space of one page for each day,  
*SEVEN SHILLINGS AND SIXPENCE.*

In Elegant Morocco or Russia Binding, with Subscriber's Name lettered on Cover,  
*TWELVE SHILLINGS.*

FREE BY POST.

---

95 & 96, LONDON WALL; 25, 26 & 27, GREAT WINCHESTER STREET  
49, PARLIAMENT STREET, AND FINSBURY FACTORIES.

FORTIETH YEAR OF PUBLICATION.

# THE SOLICITORS' DIARY, LEGAL DIGEST AND DIRECTORY, FOR 1884.

---

*An excellent Diary, with Legal Notes for each day in the year—The Stamp Act, with Amendments to the present time—Succession and Legacy Duties—List of Banks, etc.—County Courts, etc.—Municipal Boroughs, Recorders, Town Clerks—Clerks of the Peace—Undersheriffs—Queen's Counsel and Serjeants-at-Law—Oaths in Supreme Court—Jurats, etc.—Suggestions on Registering Deeds and Papers at Public Offices—Insurance Directory—Table of Protective Statutes—Index to Public General Acts—Scales of Commission in Conveyancing business—Time Tables and Tables of Costs under Judicature Acts—Parliamentary Directory—District Registries, etc.*

A digest of the Public General Acts of the past Session,  
WITH ALPHABETICAL INDEX, ETC.;

TOGETHER WITH

NAMES AND ADDRESSES OF BARRISTERS IN PRACTICE;

ALSO

LISTS OF LONDON AND COUNTRY SOLICITORS,

WITH

APPOINTMENTS HELD BY THEM.

*(Revised with the Official Roll, by permission of the Council of the Incorporated Law Society, and corrected by direct correspondence.)*

- No. 1. With *One* page for each day, Half-bound Law Calf—Price 6s.
- No. 2. Ditto, ditto, with Money columns.
- No. 3. Interleaved, giving two pages to each day, ditto „ 8s. 6d.
- No. 4. With *Two* days on each page, ditto ditto „ 5s.
- No. 5. Ditto, ditto with Money Columns.
- No. 6. With *Three* days on each page, bound in Embossed Cloth, price 3s. 6d.

The DIARY is printed on Superfine Paper, and can be obtained *ruled*, and with *cash columns* for receipts and payments if desired, or otherwise, as specially ordered.

The POCKET EDITION of the "SOLICITORS' DIARY" contains in a very small space the leading features of the large edition. Price, in leather tuck, 2s. 6d.; Roan Wallet, 4s. 6d.; and Russia Wallet, 7s. 6d.

---

95 & 96, LONDON WALL; 25, 26 & 27, GREAT WINCHESTER STREET;  
49, PARLIAMENT STREET, AND FINSBURY FACTORIES.

WATERLOW & SONS LIMITED, LAW PUBLISHERS.

---

THIRD EDITION.

# THE BILLS OF EXCHANGE ACT, 1882.

*AN ACT TO CODIFY THE LAW RELATING TO BILLS OF EXCHANGE,  
CHEQUES, AND PROMISSORY NOTES.*

With Explanatory Notes and Index,

BY

M. D. CHALMERS, Esq., M.A.,

BARRISTER-AT-LAW (DRAFTSMAN OF THE BILL).

"Lawyers will find it a most convenient and portable edition of a most important Statute."—*Law Journal*. In Stiff Boards, 2s. 6d. In Cloth, 3s. 6d.

"To say that Mr. Chalmers is the draftsman of the Act is almost to guarantee that his notes explaining the sections or the reasons for their becoming law are absolutely correct. The index is satisfactory, so far as we have tested it. We may add that the book is beautifully printed."—*Law Times*.

---

SECOND EDITION.

# THE NEW BILLS OF SALE ACT.

THE BILLS OF SALE ACTS,

1878 and 1882,

*WITH COPIOUS NOTES, INDEX AND PRECEDENTS, SHOWING THE  
ALTERATION IN THE LAW UNDER THE NEW ACT,*

BY

MICHAEL G. GUIRY, Esq., LL.B.

(OF THE MIDDLE TEMPLE, BARRISTER-AT-LAW.)

"There is one feature for which the author deserves to be rewarded with the proceeds of a large sale of his book—the references are given to *all* the reports. We can recommend the volume as a most useful one to take into court or chambers: and in County Courts, where libraries are rather scarce, the book will be of the greatest value."—*Law Times*.

---

## EXTRACT FROM INTRODUCTION:

"An attempt is made in the following pages to furnish the legal profession with a useful hand-book in offices and courts where a law library is not at hand. The writer has found in practice that although quotations from text-books may be faithful representations of the expressions of learned judges, yet, since the *ipsissima verba* of the judgments are not given, courts refuse to act upon the authority of such quotations. As far as possible, therefore, the facts of cases are here given, together with such portions of judgments as are relevant; and it is thereby hoped that the book may be more useful to practitioners than if it contained, in a sentence, the result of each case."

IN CLOTH, 5s. ; or for Cash with Order, 4s.

---

95 & 96, LONDON WALL; 25, 26 & 27, GREAT WINCHESTER STREET;  
49, PARLIAMENT STREET, AND FINSBURY FACTORIES.

# THE BANKRUPTCY ACT, 1883,

WITH INTRODUCTION AND INDEX,

BY

M. D. CHALMERS, M.A., Barrister-at-Law, & E. HOUGH, of the Board of Trade.

130 pages, Demy 8vo., 2s. 6d.

# THE AGRICULTURAL HOLDINGS (ENGLAND) ACT, 1883,

WITH

NOTES AND FORMS, AND A SUMMARY OF THE PROCEDURE,

BY

J. W. JEUDWINE,

OF LINCOLN'S INN, BARRISTER-AT-LAW.

120 pages, Demy 8vo. In Boards, 2s. 6d., or in Cloth, 3s. 6d.

# THE LAW RELATING TO CORRUPT PRACTICES AT ELECTIONS, AND THE PRACTICE ON ELECTION PETITIONS,

WITH AN

APPENDIX OF STATUTES, RULES AND FORMS,

BY

MILES WALKER MATTINSON & STUART CUNNINGHAM MACASKIE

OF GRAY'S INN, BARRISTERS-AT-LAW.

300 pages, Demy 8vo. ; in Cloth, 7s. 6d.

*A Complete List of our Publications sent free on application.*



## Price List of Parchment.

### PLAIN.

Depth.	Width.		Each.	Best picked.	Per doz.	Per doz. Best picked.
10	× 15	.. .. .	-/5	.. -/6	.. 4/-	.. 5/-
12	× 16	.. .. .	-/9	.. -/10	.. 8/-	.. 9/-
13	× 17	.. .. .	-/10	.. 1/-	.. 9/6	.. 11/-
15	× 20	.. .. .	1/-	.. 1/2	.. 11/6	.. 12/6
16	× 21	.. .. .	1/2	.. 1/4	.. 13/-	.. 14/6
17	× 22	.. .. .	1/4	.. 1/6	.. 15/-	.. 16/6
18	× 24	.. .. .	1/6	.. 1/8	.. 17/6	.. 19/-
19	× 25	.. .. .	1/10	.. 2/-	.. 20/-	.. 22/-
22	× 27	.. .. .	2/-	.. 2/3	.. 22/-	.. 25/-
23	× 28	.. .. .	2/3	.. 2/6	.. 25/-	.. 28/-
26	× 29	.. .. .	2/6	.. 2/9	.. 28/6	.. 31/-
26	× 31	} .. .. .	2/9	3/-	31/6	34/-
27	× 30					
28	× 32	.. .. .	3/3	.. 3/6	.. 35/-	.. 37/-

*Larger sizes can be supplied.*

### RED-LINED AND RULED.

			Each.	Best picked.	Per doz.	Best picked. Per doz.
Indentures Texted	15	× 20	.. 1/6	.. 1/9	.. 15/-	.. 18/-
	26	× 29	.. 3/-	.. 3/6	.. 30/-	.. 36/-
	27	× 30	.. 3/6	.. 4/-	.. 32/-	.. 38/-
Followers ..	23	× 28	.. 2/6	.. 3/-	.. 26/-	.. 30/-
	25	× 30	.. 3/-	.. 3/6	.. 30/-	.. 36/-
Bookways Texted	10½	× 17	.. 1/-	.. 1/2	.. 10/6	.. 12/-
	13	× 17	.. 1/3	.. 1/6	.. 14/-	.. 16/-
	16	× 21	.. 2/-	.. 2/3	.. 21/-	.. 23/-
These are the sizes of Skins before folding.	18	× 24	.. 2/3	.. 2/6	.. 22/-	.. 25/-
	19	× 25	.. 2/6	.. 2/9	.. 26/-	.. 28/-
	22	× 27	.. 2/9	.. 3/-	.. 28/-	.. 30/-

## MEMORIALS.

### RULED OR PLAIN.

				Each.	Per doz.
10	× 15	.. .. .	..	-/6	.. 5/-
13	× 17	.. .. .	..	-/10	.. 9/6
15	× 20	.. .. .	..	1/-	.. 11/6
18	× 24	.. .. .	..	1/6	.. 17/6
23	× 28	.. .. .	..	2/3	.. 25/-

*These can be had with or without 2/6 stamp impressed.*

# PROBATES.

WITH OR WITHOUT HEADING, BLACK LINED AND RULED.

				Each.		Best picked.		Per doz.		Best picked.
12 X 16	..	..	..	1/-	..	1/2	..	10/6	..	12/-
15 X 20	..	..	..	1/6	..	1/9	..	15/-	..	18/-
18 X 24	..	..	..	2/-	..	2/3	..	22/-	..	25/-
22 X 27	..	..	..	2/3	..	2/6	..	26/-	..	28/-
26 X 29	..	..	..	3/-	..	3/6	..	30/-	..	36/-
28 X 32	..	..	..	3/9	..	4/-	..	40/-	..	45/-

## Paper Indentures, Agreements, &c.,

PRINTED, RULED, AND RED-LINED.

					PER QUIRE.		
					Large Post 4to.	Fcap.	Demy.
					s. d.	s. d.	s. d.
THIS INDENTURE	...	...	...	...	2 6	3 6	4 6
MEMORANDUM OF AGREEMENT	...	...	...	...	2 6	3 6	4 6
AN AGREEMENT	...	...	...	...	2 6	3 6	4 6
"THIS IS THE LAST WILL," &c. (not red lined)					2 6	3 6	4 6
FOLLOWERS for same	...	...	...	...	2 6	3 6	4 6

Per Quire,  
s. d.

THIS INDENTURE, on Blue Wove Copy, half sheets, ruled ... 1 6

THIS INDENTURE, on Water-lined Brief ... 2 0

THIS IS THE LAST WILL, &c., on Lined Brief ... 2 6

SPECIMENS OF ANY OF THE ABOVE SENT ON APPLICATION.

95 & 96, LONDON WALL; 25, 26 & 27, GREAT WINCHESTER STREET;  
49, PARLIAMENT STREET, AND FINSBURY FACTORIES.

# "ZEPHYR" COPYING PAPER

TAKES 8 COPIES.

IS CHEAP AND EFFECTIVE.

In introducing this Paper to the Public, WATERLOW & SONS LIMITED feel sure it will meet with general approval, owing to its remarkable thinness and toughness. EIGHT COPIES can be easily taken, and, with a little extra care, as many as TEN COPIES. It will, therefore, be found invaluable to Bankers, Solicitors, and others having extensive correspondence.

Quarto—per Ream, 960 Sheets .. .. .	6/-
Foolscap    ,,       ,,       .. .. .	8/-

*Or in Books, Half Calf, Indexed, Paged, and Lettered.*

Quarto—500 Leaves .. .. .	6/-
,,   1,000    ,,       .. .. .	10/-
Foolscap—500 Leaves .. .. .	8/-
,,   1,000    ,,       .. .. .	14/-

# "STOUT BUFF" COPYING PAPER

(AS USED IN THE GOVERNMENT OFFICES),

AN EXCELLENT SUBSTITUTE FOR WRITTEN DUPLICATES,

*Saving manual labour.*

Quarto—per Ream, 480 Sheets .. .. .	4/6
Foolscap       ,,       ,,       .. .. .	6/6
Books, Half Basil, Quarto, 500 pages .. .. .	7/6
,,       ,,       ,,       750    ,,       .. .. .	10/6
,,       ,,       Foolscap, 500    ,,       .. .. .	10/6
,,   in Half Calf, Quarto, 600    ,,       .. .. .	10/6
,,       ,,       Foolscap 600    ,,       .. .. .	13/6



This Paper will Copy Documents long after writing, and with almost any Ink if sufficiently damped—even Correspondence *Received*, which has been previously copied.

## INSTRUCTIONS.

For Copying Ink recently written, thoroughly remove all superfluous moisture; when more than one copy is required, *take them separately*, making each succeeding one a little damper and pressing longer. In this manner from four to six copies may be taken.

For Copying Ink which has been some days written, or copied before, or for Non-copying Ink, *damp well on both sides and press for a few minutes. One and sometimes two copies can be taken in this way.*

## FORM CASES.



### DROP DOORS,

COVERED GREEN CLOTH.

					s.	d.
12 Divisions	JUDICATURE SIZE..	..	..	..	19	0 each.
20	"	"	"	"	28	0 "
12	"	BANKRUPTCY SIZE	..	..	21	0 "
20	"	"	"	"	30	0 "

### OAK OR MAHOGANY,

WITH TWO FOLDING DOORS.

			s.	d.
12 Divisions,	JUDICATURE SIZE..	33	0	each.
20	"	"	48	0 "
12	"	BANKRUPTCY	42	0 "
20	"	"	50	0 "

### JAPPANED IRON.

			s.	d.
12 Divisions,	JUDICATURE SIZE..	28	6	each.
20	"	"	42	0 "
20	"	BANKRUPTCY	55	0 "

*Hand Endorsement Stamps for Commissioners for Oaths, in Mahogany Box, with Ink Pad complete, 10s. 6d.*

## JUDICATURE PAPER.

REQUISITE UNDER THE ACT.

Price per Ream,	Ruled with proper Margins ...	...	22s.	6d.
"	" Printed Headings for Special Forms	...	30s.	0d.
"	" Plain ...	...	18s.	6d.

## PRINTING OF PLEADINGS, &c.

By Order XIX., Rule 5, of the first Schedule of the Supreme Court of Judicature Acts, 1875, amended by Rule 5a of the Rules of the Supreme Court, June 1876, all proceedings of more than 10 folios in length must be printed. WATERLOW & SONS LIMITED have therefore made arrangements to undertake the printing of the Pleadings, Affidavits, Depositions, Special Cases, Petitions of Right, &c., in the manner prescribed by the Rules of Court, and, when required, to furnish Proofs or Printed Copies by return of Post.

95 & 96, LONDON WALL; 25, 26 & 27, GREAT WINCHESTER STREET;  
49, PARLIAMENT STREET, AND FINSBURY FACTORIES.

## LAW AND PARLIAMENTARY STATIONERY AND PRINTING.

Forms under the Judicature Acts, 1873 & 1875—Conveyancing Forms and Engrossments  
—Auction, Shipping, Commercial and Miscellaneous Forms—Bankruptcy and Liquidation  
—Trade Mark, Naturalization, and Companies' Forms.

*A Catalogue of Legal and General Forms sent on application.*

## INLAND REVENUE STAMPING.

*WATERLOW & SONS LIMITED devote special attention to this department, and are in daily attendance at the Stamp Office, Somerset House. They are thus enabled to ensure the Stamping of Bankers' Cheques, Drafts, Bills of Exchange, &c., with the utmost possible despatch.*

Deeds and all executed instruments stamped and forwarded by return of Post, a small charge being made for attendance and postage. The greatest care is exercised in the assessment of Stamp Duty payable on any document entrusted to the Company for stamping, but they incur no responsibility in the event of an improper assessment being made.

As the amount of Stamp Duty must be paid to the Stamp Office before any document can be stamped, it is particularly requested that a remittance accompany the instructions for stamping.

Cheques and Post Office Orders to be made payable to the Company, and to be crossed "Union Bank of London.—Not Negotiable."

Spoiled Stamps accompanied with the requisite Affidavits, or Allowance Tickets for Spoiled Stamps, are credited in full where the amount is taken out in Printing or Stationery, but a small amount for commission is deducted when exchanged for Cash.

## LAW AGENCY.

*RESIDUARY AND SUCCESSION ACCOUNTS PASSED  
LEGACY AND SUCCESSION OR OTHER DUTIES PAID.*

All payments in respect of these duties have now to be made at the Office at Somerset House instead of at the Local Offices as formerly.

*BILLS OF SALE STAMPED AND FILED,*

*JOINT-STOCK COMPANIES REGISTERED.*

*ADVERTISEMENTS INSERTED IN THE "LONDON GAZETTE."*

*ANNUAL SUMMARIES, SPECIAL RESOLUTIONS, &c., FILED*

*SEARCHES MADE AT ANY OF THE PUBLIC OFFICES WITH THE GREATEST CARE AND EXPEDITION.*

*TRADE MARKS REGISTERED*

*Designs furnished and Blocks cut for same.*

## LAW WRITING AND ENGROSSING.

WATERLOW & SONS LIMITED desire to call the attention of Solicitors and Professional Gentlemen to the facilities which they are enabled to offer for the execution of all classes of Legal Work.

A competent staff of law writers and clerks are constantly engaged at Great Winchester Street, London Wall, and W. & S. are therefore enabled to execute any work entrusted to them with the utmost care and despatch.

DEEDS, &c., carefully and correctly engrossed.

STAMP DUTIES assessed and paid.

*Charges for copying, at per folio of 72 words :—*

	<i>s. d.</i>
Engrossments in Round-hand .. .. .	0 2
Attested Copies and Fair Copies of every description .. .. .	0 1½
Wills, Abstracts, Parliamentary Briefs and Minutes of Evidence .. .. .	0 2
Abstracting Titles and Fair Copy .. .. .	0 6

Drafts, &c., received from the country can be engrossed or copied and sent by return post when required.

A large stock of STAMPED PARCHMENT AND PAPER of every description being kept ready for immediate use, any order can be executed without the slightest delay.

## LAW LITHOGRAPHY.

The facilities afforded by WATERLOW & SONS LIMITED in this department having led to so great an increase of their business, they are now enabled to retain a staff of hands capable of completing, in a few hours, an amount of work which would formerly have required as many days to accomplish.

Briefs, Abstracts, Minutes of Evidence, Reports, and Legal Documents, Builders' Quantities, Contracts, Specifications, &c., lithographed in good plain round-hand, with the greatest accuracy.

A Brief of 100 sheets can, if necessary, be lithographed in three or four hours. The evidence taken daily on Private Bills or Arbitration Cases may be neatly and correctly lithographed or printed *during the night*, and delivered to Counsel *before 9 o'clock the following morning*.

The following prices are intended as a guide to the charges for the ordinary description of Law Lithography; where a greater number of copies of any Document are required, special estimates will be given.

Abstracts copied Briefwise, 5 to 8 folios 1 per sheet, on Superfine Paper :—	Drafts, 4 to 5 folios per page, on Super- fine Laid Copy :—
8 Copies .. .. . 6d. per sheet.	10 Copies .. .. . 4d. per page.
12 „ .. .. . 4½d. „	20 „ .. .. . 2½d. „
20 „ .. .. . 3½d. „	50 „ .. .. . 1½d. „
30 „ .. .. . 3d. „	100 Copies .. .. . 7s. 9d.
50 „ .. .. . 2d. „	Per 100, after the first 100, 5s. 9d.
100 „ .. .. . 1½d. „	Deeds, Law Letters, and Forms Litho- graphed at reasonable prices.

Per 100, after the first 100, 10s. 6d.

Where preferred, the charge will be made by the folio, in proportion to the above scale. Minutes of Evidence and Parliamentary documents are charged at 2d. per folio.

## LAW AND PARLIAMENTARY PRINTING.

WATERLOW & SONS LIMITED have for years devoted special attention to the perfecting of this Department, and undertake the printing of all legal matters, such as Appeals to the House of Lords, &c., in strict conformity to the New Standing Orders. Admiralty and Appeal Cases and Appendices printed, Memorandum and Articles of Association, Books of Reference, Deeds, Conveyances, Mortgages, &c.

In the Parliamentary Printing Department, where expedition and punctuality are of the greatest importance, W. & S. employ a large staff having a practical knowledge of the work. They are therefore enabled to execute all orders entrusted to them, however large, in the shortest possible space of time.

Minutes of evidence printed during the night and delivered wherever desired by 9 o'clock the following morning.

Parliamentary Bills, Notices, Petitions, Reports, &c. Addresses and Circulars to Electors printed or lithographed, and posted with the greatest despatch.

95 & 96, LONDON WALL; 25, 26 & 27, GREAT WINCHESTER STREET;  
49, PARLIAMENT STREET, AND FINSBURY FACTORIES.



UNIVERSITY OF CALIFORNIA LIBRARY  
Los Angeles

This book is DUE on the last date stamped below.



JN  
1083  
M43 1  
The law relat-  
ing to corrupt  
practices at  
elections.

UCLA Young Research Library

JN1083 .M43I

yr



L 009 563 720 3

JN  
1083  
M43 1

UC SOUTHERN REGIONAL LIBRARY FACILITY



AA 001 352 891

4

